

CONCRETE & MASONRY SAFETY



Safety and Quality Relationship

**REINFORCING MISS-PLACED
IN CONCRETE RESULTS IN
WEAKEN STRUCTURE**

**IMPROPER PLACEMENT OF
LINTEL BEAMS**

**INCORRECT MASONRY
CEMENT
OR GROUT MIX DESIGN**



CONCRETE & MASONRY SAFETY



CONCRETE PLACEMENT OPERATIONS POTENTIAL FOR MULTIPLE SERIOUS SAFETY PROBLEMS

CRANES/BUCKET
CONCRETE PUMPING
EQUIPMENT
FALL PROTECTION
LARGE CREWS
TIGHT PLACEMENT TIMING
ELECTRICAL GFCI
POWER FINISHING
FORMWORK FAILURE
IMPROPER SHORING RE-SHORING



MASONRY WALLS



**BRACING OF MASONRY WALLS
OVER 8 FEET HIGH TO BE
BRACED 27.G.02**

**SCAFFOLDING CANNOT BE
USED TO SUPPORT WALLS
27.G.03**



Masonry Walls



LIMITED ACCESS ZONE

ESTABLISHED PRIOR TO START OF WORK
LOCATED OPPOSITE SIDE OF SCAFFOLDING
RESTRICTED ACCESS TO ACTUAL WORKERS
SPECIFIC HEIGHT AND LENGTH RESTRICTIONS!
ZONE TO REMAIN IN PLACE UNTIL
WALL IS ADEQUATELY SUPPORTED

27.G.01



**Don't forget,
The limited access
zone when the wall
gets to 8' high!!**



LIMITED ACCESS ZONE




HEIGHT OF WALL PLUS 4 FOOT

ENTIRE LENGTH OF WALL

ON OPPOSITE SIDE OF SCAFFOLDING

RESTRICTED ACCESS/NECESSARY EMPLOYEES



Look on
Page #6




Limited Access Zone Questions

What is the length & Height of the Limited Access zone for this Wall?



Which side of this wall
is the limited access zone?



Note: Scaffold is on the opposite side shown



LIMITED ACCESS ZONE



ON THIS SIDE >>>

Note: Clean-outs to be on opposite side of wall of the scaffolding?

Concrete Safety



Horizontal slabs/footings



Vertical Wall/columns

Concrete Safety Issues



**NO LOADING OF STRUCTURES UNTIL
CAPABLE TO SUPPORT LOADS**

IMPALEMENT PROTECTION FOR RE-BAR

**NO RIDING CONCRETE BUCKETS
OR UNDER LOADS**

PROPER PPE (RUBBER BOOTS, ETC)

POWER TROWELS WITH DEAD MAN SWITCH

INSULATE BULL FLOAT HANDLES AS NEEDED

PROPER FORMS/SHORING/RE-SHORING



CONCRETE BUCKET SAFETY PRECAUTIONS



**NO WORKERS UNDER
CONCRETE BUCKET**

TAG LINE ADVISED

NO RIDING!

You Safety folks
Are taking all the
Fun out of my
Job!



Good thing that
Inspector is not here!

Automatic shut off switch required on power troweling machines 27.A.04



WHICH ITEM IS APPROVED FOR IMPALEMENT PROTECTION?



ITEM "A"



ITEM "B"

See Pages 7 through 10

QUESTION



ON YOUR CONSTRUCTION JOB, WHAT IS THE LEGAL USE OF THIS ITEM THAT IS COMMONLY CALLED A “MUSHROOM CAP”?



IMPALEMENT AND SCRATCH GUARD PROTECTION



ALTERNATE IMPALEMENT PROTECTION



CONCRETE SHORING & RE-SHORING



PLANNING AND DESIGN OF FORMWORK AND SHORING SHALL BE IN ACCORDANCE WITH THE PROVISIONS OF ACI PUBLICATION 347. 27.B.02

THE DESIGN AND THE ERECTION AND REMOVAL PLANS FOR FORMWORK AND SHORING SHALL BE SUBMITTED FOR REVIEW TO THE GDA.

THE MANUFACTURER'S SPECIFICATIONS FOR FABRICATED SHORING SHALL BE AVAILABLE AT THE JOB SITE DURING JOB PLANNING AND EXECUTION.



**Yipee I found
It Boss!**

**Quit Guessing!
Just look
It up!!**



See page 3 and COE 27.B


SHORING & RE-SHORING



SHORING: A SUPPORT MEMBER THAT RESISTS COMPRESSIVE FORCES IMPOSED BY A LOAD.



Single Post Shores



Single Post Shore

SINGLE POST SHORES




**ADJUSTMENT
OF SINGLE
POST SHORES
TO RAISE
FORMWORK
SHALL **NOT** BE
MADE AFTER
CONCRETE IS
IN PLACE.**

27.B.09



MODULAR TYPE SHORES



See 27. B. 10 & 11

TUBULAR WELDED FRAME SHORES



FORMWORK & SHORING SYSTEMS



ALL FORM WORK, SHORING, AND BRACING SHALL BE DESIGNED, FABRICATED, ERECTED, SUPPORTED, BRACED & MAINTAINED SO THAT IT WILL SAFELY SUPPORT ALL VERTICAL AND LATERAL LOADS UNTIL SUCH LOADS CAN BE SUPPORTED BY THE STRUCTURE. 27.B.01

RESHORING PLANS



OSHA: RESHORING: The Construction Operation In Which Shoring Equipment (Also Called Re-shores Or Re-shoring Equipment) Is Placed As The Original Forms And Shores Are Removed In Order To Support Partially Cured Concrete An Construction Loads.



27.B.07 Re-shoring shall be provided to safely support slabs & beams after stripping or where such members are subject to superimposed loads due to construction




SHORING FAILURE



THE RESULTS OF NOT FOLLOWING SPECIFIC PROCEDURES & SCHEDULE PRESSURES

PRECAST CONCRETE




SLABS, BEAMS, LINTELS, COLUMNS, TILT-PANEL

PRECAST CONCRETE OPERATIONS



- **Precast concrete members shall be adequately supported to prevent overturning or collapse until permanent connections are complete.**
- **Lifting inserts which are embedded or otherwise attached to tilt – up precast concrete members shall be capable of supporting at least two times the maximum intended load.**
- **Lifting inserts which are embedded or otherwise attached to precast concrete members , other than tilt–up members, shall be capable of supporting at least four times the maximum intended load.**
- **Lifting hardware shall be capable of supporting at least five times the maximum intended load applied load applied or transmitted to the lifting device**

PRECAST CONCRETE PANEL



**Inserts 2
times
the load**

**Hardware 5 times
the load**



27.C.02

PRE-CAST TILT PANEL



**LIFTING INSERTS
& REINFORCING
PLACEMENT IS
CRITICAL!**



LIFT-SLAB OPERATIONS



- Lift-slab operations shall be planned and designed by a registered engineer or architect. Such plans and designs shall include detailed instructions and sketches indicating the prescribed method of erection and shall be submitted to the GDA for review
- During lifting, all points of the slab support shall be kept within $\frac{1}{2}$ inch of that needed to maintain the slab in a level position
- No one shall be permitted under the slab during jacking operations



27.D

LIFT SLAB OPERATIONS




INITIAL CASTING OF SLABS

LIFT SLAB OPERATIONS



START OF LIFTING SLABS

LIFT SLAB OPERATIONS



LIFT SLAB PROGRESS

PRE-STRESSED- POST TENSION CONCRETE



**SAFE CLEARANCE FROM THESE
TYPE OF OPERATIONS!**

Post Tension Placement



Post Tension Placement



Placing Cables in a Pre-Cast Member