

**Proposed Plan
Operable Unit 4 (OU-4)**

for

**Naval Weapons Station Earle
Colts Neck, New Jersey**



**Northern Division
Naval Facilities Engineering Command
Contract No. N62472-90-D-1298
Contract Task Order 300**

November 1997



BROWN & ROOT ENVIRONMENTAL

Department of the Navy



Proposed Remedial Action Plan for OU-4

Naval Weapons Station (NWS) Earle
Colts Neck, New Jersey

NOVEMBER 1997

NAVY ANNOUNCES PROPOSED REMEDIAL ACTION PLAN

This Proposed Plan summarizes the findings of the Operable Unit 4 (OU-4) **remedial investigation** (RI) report, summarizes remedial activities and the determination of **no further action** (NFA) by the Navy and the United States Environmental Protection Agency (EPA), and explains the reasons for this determination. In addition, this Proposed Plan explains how the public can participate in the decision-making process and provides addresses for the appropriate Navy contacts.

The Department of the Navy has completed an RI for OU-4 addressing contamination associated with Sites 14, 20, 22, 23, 24, 25, 27, and 29 at Naval Weapons Station (NWS) Earle in Colts Neck, New Jersey. The OU-4 sites were grouped together based on the results of the RI and associated remedial actions (RAs). The RI and associated RAs were completed as part of the Navy's Installation Restoration Program (IRP) and the Superfund Remedial Program.

PUBLIC PARTICIPATION IS ENCOURAGED

This Proposed Plan is issued by the Navy, the lead agency for the IRP and Superfund activities at the NWS Earle facility, and by EPA, the support agency for Superfund activities. The public is encouraged to comment on this Proposed Plan; procedures for public comment are discussed at the end of this Plan. After the public comment period has ended and after any comments have been reviewed and considered, the Navy and EPA will select a remedy for Sites 14, 20, 22, 23, 24, 25, 27, and 29.

NOTE: A glossary of relevant technical and regulatory terms is provided at the end of this Proposed Plan. These terms are initially indicated in **boldface** within the Proposed Plan.

NAVY'S RESPONSIBILITY

The Navy is issuing this Proposed Plan as part of its public participation responsibilities under the Superfund law and, in particular, Sections 113(k), 117(a), and 121(f) of the **Comprehensive Environmental Response, Compensation, and Liability Act** (CERCLA, commonly referred to as Superfund) as amended by the Superfund Amendments and Reauthorization Act (SARA).

This document summarizes information that can be found in greater detail in the RI report for OU-4 sites at NWS Earle, as well as other site documents contained in the **Administrative Record** file for this site. The Navy invites the public to review the available materials and to comment on this Proposed Plan during the public comment period.

The Administrative Record file is available at the
Monmouth County Library, Eastern Branch
Route 35, Shrewsbury, NJ

PUBLIC MEETING

A public meeting to discuss this Proposed Plan will be held on **Month/Day/Year** at 7:00 PM at Building C-54 at NWS Earle, Colts Neck, NJ. The meeting date will also be published in the *Asbury Park Press*.

The Navy, with EPA, may modify the selected remedy presented in this Proposed Plan for OU-4 based on new information from the public comments. **The public is encouraged to review and comment on the recommendations identified here.**

SITE BACKGROUND

NWS Earle is located in Monmouth County, New Jersey, approximately 47 miles south of New York City. The station consists of two areas, the 10,248-acre Main Base (Mainside area), located

inland, and the 706-acre Waterfront area (see Figure 1). The two areas are connected by a Navy-controlled right-of-way.


Commissioned in 1943, the facility's primary mission is to supply ammunition to the naval fleet. An estimated 2,500 people either work or live at the NWS Earle station.

The Mainside area is located in Colts Neck Township, which has a population of approximately 6,500 people. The surrounding area includes agricultural land, vacant land, and low-density housing. The Mainside area consists of a large, undeveloped portion associated with ordnance operations, production, and storage; this portion is encumbered by explosive safety quantity distance arcs. Other land use in the Mainside area consists of residences, offices, workshops, warehouses, recreational space, open space, and undeveloped land. Sites 14, 20, 22, 23, 24, 25, 27, and 29 are all located in the Mainside area (Figure 2). A brief description of each of these sites follows.

The Waterfront area is located in Middletown Township, which has a population of approximately 68,200 people.

Site 14 - Mercury Spill Area


The Defense Property Disposal Office Warehouse, Building C-33, is a 16,000-square-foot storage building for items awaiting processing (Figure 3). A small amount of mercury (estimated at from one to several ounces) was reportedly spilled inside the warehouse in 1970. The location of the spill was not documented; however, on-site interviews confirmed that the spill was inside the building.



LEGEND

⑤ SITE LOCATION

---> STREAM WITH FLOW DIRECTION




DRAWN BY	DATE
MRM	1/7/97
CHECKED BY	DATE
RET	1/7/97
COST/SCHED.-AREA	
SCALE	
1" = 5000'	



Brown & Root Environmental

**MAINSIDE SITE LOCATIONS
NAVAL WEAPONS STATION EARLE
COLTS NECK, NEW JERSEY**

CONTRACT NO.	OWNER NO.
APPROVED BY	DATE
APPROVED BY	DATE
DRAWING NO.	REV.
FIGURE 2	



LEGEND

- ☒ FLOOR SWEEPINGS
- ☒ GRAB LOCATIONS

SAMPLE LOCATIONS
SITE 14 - BUILDING C-33
NWS EARLE, NEW JERSEY

FIGURE 3



Brown & Root Environmental

Site 20 - Grit Blasting Area at Building 544

The grit blasting area at Building 544 is a small area behind Building 544 that houses grit blasting operations for the removal of paint from ordnance (Figure 4). Activities at the site included the disposal of paint chips and spent grit from site operations. The spent grit was dumped in an open pile southwest of Building 544. A leaching field is present behind this building.

Sit 22 - Paint Chip Disposal Area

Site 22 is a former paint chip disposal area where waste sand blasting material and paint wastes were disposed (Figure 5). The site is located south of Building D-2 and previously consisted of approximately 50 square feet of stressed vegetation and discolored (black) soils. The discolored soils resulted from past grit blasting and painting operations. However, the discolored soils and stressed vegetation are no longer visible at the site.

Sit 23 - Paint Disposal Area

The paint disposal area near Building D-5 was used from the early 1970s until approximately 1993 for paint wastes from repainting and stenciling torpedoes, aerial bombs, and other large ordnance (Figure 6). The site consists of approximately 200 square feet of ground surface west of the northwestern corner of Building D-5 where paint disposal to the ground surface

Sites 24 and 25 - Closed Pistol Ranges


Sites 24 and 25 are closed pistol ranges that were once used for target practice (Figure 7). Due to the sites' similar nature, history, and close proximity, they have been treated together. During target practice at the sites, lead- and copper-jacketed bullets were fired into 70-foot-high impact berms (natural sand banks). Preserved wooden posts at the sites formed the firing platform.

Site 27 - Projectile Refurbishing Area

Site 27 includes Building E-14 and a small storage locker located off Oran Road (Figure 8). Projectiles are refurbished at the site by shot-blasting, repainting, and stenciling. Oil-contaminated rags, paint chips, and spent sandblasting shot were disposed behind the facility. A small portion of the site surface (approximately 80 square feet) near the southeast corner of Building E-14 was covered by a red paint sludge.

Site 29 - PCB Spill Site


This site is located in a storage yard (north of Site 16/F) where an unknown quantity of **polychlorinated biphenyl's (PCBs)** spilled from a transformer in 1981 (Figure 9). No record exists suggesting that PCB compounds flowed any significant distance overland or in a ditch.




SAMPLE LOCATION

FIGURE 4

SITE 20 - GRIT BLASTING AREA AT BLDG 544




Brown & Root Environmental



SAMPLING LOCATIONS
SITE 22 - PAINT CHIP DISPOSAL AREA

FIGURE 5






SAMPLE LOCATIONS
SITE 23 - PAINT DISPOSAL AREA




FIGURE 6





SAMPLE LOCATIONS
SITE 24/25 - CLOSED PISTOL RANGES




SCALE IN FEET

FIGURE 7




Brown & Root Environmental



SAMPLE LOCATIONS
SITE 27 - PROJECTILE REFRUBISHING

FIGURE 8





SAMPLE LOCATIONS
SITE 29 - PCB SPILL SITE



FIGURE 9

NWS Earle has built a one-story, brick building at the site that will function as the new hazardous waste storage facility.

STUDIES AND RESULTS

Potential hazardous substance releases at NWS Earle were addressed in an **Initial Assessment Study (IAS)** in 1982, a **Site Inspection Study (SI)** in 1986, and a Phase I RI in 1993. These were preliminary investigations to determine the number of sources, compile histories of waste-handling and disposal practices at the sites, and acquire data on the types of contaminants present and potential human health and/or environmental receptors. The RI investigation at the OU-4 sites included the installation and sampling of monitoring wells, collection of soil, surface water, and sediment samples, and excavation of test pits to observe wastes and sample subsurface soils. Remedial action has consisted of material excavation and removal and confirmatory sampling.

In 1990, NWS Earle was placed on the **National Priorities List (NPL)**, which is a list of sites where uncontrolled hazardous substance releases may potentially present serious threats to human health and the environment. The sites at NWS Earle were subsequently addressed by Phase II RI activities to further define the nature and extent of contamination at these sites. Activities included installation and sampling of groundwater monitoring wells, surface water and sediment sampling, and surface and subsurface soil sampling. The Phase II RI was initiated in 1995 and completed in July 1996, when the final RI report was released. Results of all the investigations for each site are discussed below.

SITE - 14 MERCURY SPILL

Site Background and Physical Setting

The Defense Property Disposal Office Warehouse, Building C-33, is a 16,000-square-foot storage building for items awaiting processing. On-site interviews indicated that a small amount of mercury (estimated to have totaled from one to several ounces) was spilled inside the warehouse in 1970 (IAS, 1983). The location of the spill was not documented. However, interviews confirmed that the spill was inside the building and that the mercury was removed by vacuuming.

The warehouse has solid concrete floors that would prevent the mercury spill from affecting the soil below the building. The floors of the warehouse have been coated with a concrete protective material since the spill, and it is unlikely that any residue from the spill remains. Materials are stored in a protected manner; thus, the likelihood of environmental contamination is low.

Geology and Hydrogeology

Regional mapping places Site 14 within the outcrop area of the Kirkwood Formation. The Kirkwood Formation consists of gray and tan, very fine- to medium-grained quartz sand and dark-colored, micaceous, diatomaceous clay.

Groundwater conditions beneath the site could not be confirmed because no wells were installed at the site. However, groundwater in the Kirkwood and Vincentown aquifer beneath Site 23 (located approximately 3,000 feet southeast of Site 14), and presumably Site 14, occurs under unconfined conditions and the formations are interpreted to be hydraulically interconnected. The direction of

shallow groundwater flow in the aquifer beneath Site 23, as indicated by both the August and October groundwater contour maps for Site 23, is toward the north-northeast.

Remedial Investigations

IAS

The IAS (1983) consisting of interviews, concluded minimal impact because clean-up action was taken at the time of the spill.

SI

No sampling was conducted within the Defense Property Disposal Warehouse during the SI because the location of the spill was not documented and the impact was judged to be minimal.

1995 Remedial Investigation

In December 1995, B&R Environmental conducted field investigations at Site 14 which included sampling and analysis of warehouse floor sweepings. Since the exact location of the spill is unknown, sweepings from different areas of the warehouse were collected to determine if any traces of mercury remained on the floor surface.

Floor sweepings were collected from five grab sample points and composited into one floor sweepings sample. Figure 3 depicts the locations of these grab samples in Building C-33.

Mercury was detected at 8.6 mg/kg in the composite sample of floor sweepings. The concentration of mercury is below New Jersey state standards for Residential Direct Contact Soil

Cleanup Criteria for mercury of 14 mg/kg. Although this site is inside an industrial facility, it should be noted that the EPA value for residential levels of mercury in soil at a **hazard index (HI)** of 1 is 7.8 mg/kg.

Conclusions and Recommendations

The spill reportedly occurred on a solid concrete floor in an enclosed building with solid walls. The building has been maintained against the weather continuously since the spill. The spill was reportedly cleaned up using a vacuum.

Investigation confirms the interview reports. It appears as if the spill was adequately cleaned up at the time, and no evidence of a wider environmental contamination or risk to human health was found.

The mercury found in floor sweepings at Building C-33 represents no apparent health threat. The mercury concentration found in floor sweepings is lower than the concentration in soil (which could be tracked in on the shoes of workers or on the tires of handling equipment) and would be considered protective of non-residential or even lifetime residential exposure under NJDEP clean-up criteria. The corresponding EPA residential level at an HI of 1 is approximately equal to the concentration found and would be considered protective of human health.

There is no known evidence that the mercury spill may have affected the area around building C-33. No further investigation or ecological risk assessment appears necessary.

SITE 20 - GRIT BLASTING AREA AT BUILDING 544

Sit Background and Physical Setting

The grit blasting area at Building 544 is a small area behind Building 544 that houses grit blasting operations for the removal of paint from ordnance. Activities at the site included the disposal of paint chips and spent grit from site operations.

Spent grit from mine refurbishing grit blasting operations would typically contain lead and zinc from the coatings removed during blasting. An estimated yearly volume of 53 gallons of paint chips was disposed (IAS, 1983). The spent grit was dumped in an open pile southwest of Building 544. The pile was approximately 10 feet in diameter and 1 foot high.

A leaching field is present behind this building. Past disposal activities at this leaching field are unknown.

The site is bordered on the northeast by a marsh and wetlands. A gravel road accesses the site from Midway Road. A shallow drainage depression, which is approximately 300 feet in length and 1 foot deep, runs along the eastern and southeastern boundaries of the site and discharges to the northeast toward the marsh. Surface water flows toward this marshy area. Figure 4 is a map of the site.

Geology and Hydrogeology

Regional mapping places Site 20 within the outcrop area of the Kirkwood Formation. The Kirkwood Formation ranges between 60 to 100 feet in thickness and consists of gray and tan,

very fine- to medium-grained quartz sand and dark-colored, micaceous diatomaceous clay.

Groundwater conditions beneath the site could not be confirmed because no wells were installed at the site. However, groundwater in the Kirkwood and Vincentown aquifer beneath Site 10 (located approximately 1,000 feet north-northeast of Site 20), and presumably Site 20, occurs under unconfined conditions. The direction of shallow groundwater flow in the aquifer beneath Site 10, as indicated by both the August and October groundwater contour maps for Site 10, is toward the northwest, north, and north-northeast.

Remedial Investigations/Remedial Actions

IAS

The 1983 IAS, consisting of interviews and site observations, concluded minimal probable impact based on the presumption that metals in paint chips would not leach to the environment. The site was not recommended for a confirmation study.

SI

A site investigation (Confirmation Study) in 1986 consisted of four soil samples obtained from areas of grit deposition. Soil samples were analyzed for metals (EPTOX) and petroleum hydrocarbons. Analytical results from the 1986 SI indicated that no metals above EPTOX limits, and a maximum **total petroleum hydrocarbons (TPH)** of 65.7 mg/kg was found in site soil samples taken.

1993 RI/FS

During the 1993 **RI/feasibility study (FS)**, five sediment (surface soil) samples were collected,

one in the grit pile and four spaced along the drainage ditch which discharges to the northeast. The soil samples were analyzed for **target analyte list (TAL)** inorganics and cyanide. Two samples were also analyzed for pesticides/PCBs and **semivolable organic compounds (SVOCs)**, and one sample was analyzed for **volatile organic compounds (VOCs)**. Elevated levels of semivolatile compounds and metals were detected from samples along the drainage. Only very low levels of volatiles (possible laboratory artifacts) were detected in surface soil samples.

Remedial Action

A remedial action was performed at the site and consisted of removal and disposal of contaminated grit and related site media. The remedial action was executed in two stages. Stage one removal, in December 1994, consisted of excavation of approximately 300 cubic yards of grit tainted soils, which were stockpiled for sampling and off-site disposal. Figure 4 shows the approximate limits of excavation.

Post-excavation Stage One confirmation sampling consisted of 12 surface soil samples and duplicates analyzed for TAL metals and **target compound list (TCL)** semivolatile compounds. Sample analysis indicated metals residues remained at concentrations above NJDEP residential surface soil cleanup standards at three locations near the southern end of Site 20 (sample locations 2, 6, and 8).

On February 28, 1995, the Navy submitted a report entitled "Interim Remedial Action Report for Site 20" to the NJDEP for review and comment. The NJDEP responded to this report on April 5, 1995 and indicated their concurrence with the

Navy report and recommendations for additional excavation near sample locations 2, 6, and 8.

Stage two excavation, consisting of additional removal at locations with metals above NJDEP cleanup criteria, was carried out in March 1995. Stage two excavation was followed closely by the 1995 RI sampling to verify site cleanup results.

1995 Remedial Investigation

Based on previous investigations and removal actions, follow-up remedial investigation activities were developed to meet the following objectives:

- Determine the effectiveness of the removal action.
- Perform risk analysis to determine if further action is required.
- Determine if downgradient wetlands have been impacted.
- Evaluate potential impact from the leach field.

Between June and August 1995, B&R Environmental conducted field investigations at Site 20 which included sampling and analysis of surface soil, subsurface soil, sediment and the contents of the septic tank. Figure 4 depicts the sample locations.

1995 RI Nature and Extent of Contamination

Surface Soils

Tables 1 and 2 present the occurrence and distribution of inorganic and organic chemicals (respectively) detected in surface soil samples at Site 20 and compare them to background. Tables

3 and 4 present a comparison of detected compounds to **applicable or relevant and appropriate requirements (ARARs)** and **requirements to be considered (TBCs)**. Figure 10 shows sample locations and concentrations of compounds which exceed ARARs and TBCs.

Subsurface Soils

Tables 5 and 6 present the occurrence and distribution of inorganic and organic chemicals (respectively) detected in Site 20 background and site-related subsurface soil samples and compares them to background. Table 7 presents a comparison of detected compounds to ARARs and TBCs. Figure 10 shows sample locations.

Sediment

Tables 8 and 9 present the occurrence and distribution of inorganic and organic chemicals (respectively) detected in Site 20 background and site-related sediment samples. Tables 10 and 11 present a comparison of detected compounds to ARARs and TBCs. Figure 10 shows sample locations.

Aqueous Waste

One aqueous waste sample from the septic tank was collected at Site 20 to investigate if the compounds found in other site samplings are related to the septic tank as a possible source (Figure 4). Table A-c presents the analytical sample results.

Summary of Site Risks

Human Health Risk Assessment

As part of the Phase II RI, a human health risk assessment and ecological risk assessment were performed. Tables 12 through 14 provide the selected **chemicals of potential concern (COPCs)** and representative concentrations of inorganics and organics in site-related surface soil, subsurface soil, and sediment, respectively. Exposure pathways, potential receptors, uncertainties, and conclusions are included.


The conservative baseline risk assessment resulted in an HI greater than a value of 1.0 for non-cancer risk; therefore, additional risk analysis was performed according to EPA guidance.

The identified potential receptors were evaluated on the basis of current land use (industrial employee) and hypothetical future land use (residential, recreational, and industrial receptors).

Estimated carcinogenic risks and non carcinogenic **hazard quotents (HQs)** are summarized in Tables 15 through 24.

Conclusions of Human Health Risk Assessment

Surface soil, subsurface soil, and sediment were sampled at Site 20. The potential receptors for this site were current industrial, future industrial and residential, and recreational receptors. The cancer risks associated with the future residential and current industrial (surface soil) exposure scenarios were within the mid-range of the target risk range. Arsenic (via ingestion of and dermal contact with surface soil) was the major COPC that contributed to these cancer risks. The noncarcinogenic HIs associated with the current industrial (surface soil) and future residential (surface soil) exposure scenarios were less than 1.0; the cutoff point below which adverse noncarcinogenic effects are not expected to



**CONCENTRATIONS ABOVE SCREENING LEVELS
SITE 20 - GRIT BLASTING AREA AT BLDG 544**



FIGURE 10

Brown & Root Environmental

occur. Lead soil concentrations were below EPA guidelines. These lead concentrations are not expected to be associated with significant increases in blood-lead levels based on the results of the **Integrated Exposure Uptake Biokinetic Model (IEUBK) Lead Model (v. 0.99)**.

Risk characterization results (total cancer risks and total noncarcinogenic HIs) are presented for all potential receptors at Site 20 in Table 25 for surface soil, subsurface soil, and sediment.

Ecological Risk Assessment

The ecological risk assessment estimated the risk posed to ecological receptors, such as aquatic and terrestrial biota, from contamination at Site 20.

Site 20 is mostly developed and contains minimal terrestrial habitat. A drainage depression drains the entire site, but is small with ephemeral flow, and hence, provides no aquatic habitat. The surrounding areas contain some wetland habitats. Nearby wooded areas also provide excellent upland habitats. Groundwater-to-surface water contaminant migration is unlikely, but runoff from Site 20 to the wetlands east of the site is possible via the drainage depression.

Although the drainage depression contains no aquatic habitat, four sediment samples were collected in the depression and one in the grit area in the southeastern section of the site during 1993 RI/FS activities to ascertain whether contaminants are migrating off-site. Elevated levels of several metals, including chromium, copper, nickel, lead, and zinc, were detected in drainageway sediments. Several SVOCs, including some **polycyclic aromatic hydrocarbons (PAHs)**, were detected in the grit

area sample. However, the grit area and contaminated areas in the drainage depression were removed in 1994.

A sediment sample was taken where the drainage depression exits the site during 1995 RI activities. No excavation has occurred in this area. Due to topography, all runoff exits the site via this pathway, the sediment sample was taken in this area to determine possible off-site migration to the wetlands. Surface soil samples were collected at the site, but were taken in areas that contain limited terrestrial habitat (former grit storage areas). However, potential contaminant runoff from these soils should collect in the drainage ditch and, therefore, be present in drainage depression sediments. Concentrations of inorganics in this sediment sample were low, with all concentrations similar to background. Some PAHs were present in this sample, but were also present in low concentrations. The low levels of inorganics and organics where the drainage depression exits the site suggests limited off-site contaminant migration. However, since both the site and the drainage depression are relatively small, and since the potential contaminant source has already been removed, future off-site migration would most likely be limited. For these reasons, quantitative ecological risk assessment at this site was considered not applicable (since any risk numbers would be mitigated by the factors discussed above). Potential risks to ecological receptors at Site 20 are considered to be low, and the site was excluded from quantitative ecological risk assessment.

Site 20 - Evaluation and Recommendations

The human health risk assessment indicates that there is no present or future scenario of carcinogenic risk above the target acceptable

range. The comparison of COPCs with corresponding HIs exceeding 1, to background concentrations, indicates that this site is within the range of background risk or lower.

The removal action appears to have been effective since metals concentrations in soils were determined to be within the range of background.

Low levels of inorganics and organics where the drainage depression exits the site suggests limited off-site contaminant migration at a level of potential ecological concern. However, since both the site and the drainage depression are relatively small, and since the potential contaminant source has already been removed, future off-site migration would most likely be limited.

Site 22 - PAINT CHIP DISPOSAL AREA

Site Background and Physical Setting

Site 22 is a former paint chip disposal area where waste sand blasting material and paint wastes were disposed. The site is located south of Building D-2. The ground surface at the site is predominantly sand and gravel. A macadam road services the site from Midway Road.

The site is bordered to the north by a railroad siding and to the east by a marshy area. A shallow drainage depression, measuring approximately 275 feet in length and 0.5 to 1 foot in depth, runs the length of the site behind Building D-2, and discharges toward the southeast to a marsh. Figure 5 shows the site layout.

Geology and Hydrogeology

Regional mapping placed Site 22 in the outcrop area of the Kirkwood Formation; upper colluvium may be present at the site. The upper colluvium consists of massive sand and gravel and may contain quartz and ironstone pebbles. The Kirkwood Formation consists of gray and tan, very fine- to medium-grained quartz sand and dark-colored, micaceous, diatomaceous clay. The presence of upper colluvium or the Kirkwood Formation beneath the site cannot be confirmed because no soil borings were drilled at the site. However, the lithology of the sediments encountered in borings at Site 23, located approximately 700 feet north-northwest of Site 20 generally agrees with the published description of the upper colluvium and the Kirkwood and Vincentown Formations.

Groundwater conditions at the site could not be confirmed because no wells were installed at the site. However, groundwater in the Kirkwood and Vincentown aquifer beneath Site 23, and presumably Site 22, occurs under unconfined conditions and the formations are interpreted to be hydraulically interconnected. The direction of shallow groundwater flow in the aquifer beneath Site 23; as indicated by the August and October groundwater contour maps for Site 23, is toward the north-northeast.

Remedial Investigations

IAS

The 1983 IAS consisted of interviews and concluded minimal impact based on a small area (50 square feet) of stressed vegetation and discolored soil behind building D-2. The site was not recommended for a confirmation study.

SI

A site investigation (Confirmation Study) in 1986 consisted of four soil samples obtained from areas of stained soils at a depth of 0-3 feet. These soil samples were obtained in the general vicinity of the subsurface soil samples 22-007, 22-008 and 22-009 obtained during the RI in 1992 (see Figure 5). Soil samples were analyzed for TPH and EPTOX metals. Analytical results from the 1986 SI indicated that no metals above EPTOX limits, and a maximum TPH of 45.8 mg/kg were found in site soil samples taken.

1992 RI/FS

During the RI/FS (1993), six soil samples were collected at three locations designated as stained areas. Traces of paint stains were barely evident at the surface and were limited to black and red staining on the surface. The sample locations are identified as sample numbers 22-007, 22-008, and 22-009. Figure 5 shows the existing sample locations from the Paint Chip Disposal Area.

Three shallow samples (0 to 1 ft bgs) were analyzed for TAL inorganics with cyanide, BNAs, and pesticides/PCBs. Three deep samples (approximately 2 ft bgs) were analyzed for VOCs. Although several metals were detected at elevated concentrations, the concentrations of these metals were within the normal range for naturally occurring soils. Very low concentrations of volatile and semivolatile compounds were detected in some samples. The pesticide compound 4,4-DDT was found in one sample.

Six sediment samples (22-001 through 22-006) were collected in the drainage ditch south of Building D-2. Samples were analyzed for TAL inorganics, BNAs, TPH, and pesticides/PCBs.

Several semivolatile derivative compounds of anthracene, pyrene, and chrysene were detected at elevated levels. Other semivolatile compounds were detected at estimated (J) levels. The pesticide compound 4,4-DDT was found in sample 22-003. Some metals were detected at slightly elevated levels, but were within the normal range for naturally occurring soils.

1995 Remedial Investigation

Based on limited investigations, follow-up remedial investigation activities were developed to meet the following objectives:

- Compare metals levels to background conditions.
- Perform risk analysis to determine if further action is required.

Sampling and analysis during previous investigations were biased toward areas of visible soil staining or discoloration. In addition, samples were obtained from drainageways from these areas to gauge the potential for off-site transport of compounds. No groundwater samples were obtained because the amount of waste disposed, based on observed residues on the soil, was considered to be minimal. Low levels of heavy molecular weight PAHs and phthalates found in site soils were assumed to have little potential for migration to groundwater.

Based on the lack of significant contamination noted in samples collected during previous investigations, no additional samples were collected at the site during this phase of investigation.

Nature and Extent of Contamination

Subsurface Soil

Eight subsurface soil samples were collected including two duplicates at Site 22 (Figure 5) during the 1992 RI/FS. Tables 26 and 27 present the occurrence and distribution of inorganic and organic chemicals, respectively, in site-related subsurface soil samples and compare them to background values. Table 28 presents a comparison of detected compounds to ARARs and TBCs. Figure 11 shows sample locations.

Sediment

Seven sediment samples, including one duplicate were collected at Site 22 (Figure 5) during the 1992 RI/FS. Tables 29 and 30 present the occurrence and distribution of inorganic and organic chemicals, respectively, in site related samples and compare them to background values. Table 31 presents a comparison of detected compounds to ARARs and TBCs. Figure 11 shows sample locations and concentrations of compounds which exceed ARARs or TBCs.

SUMMARY OF SITE RISKS

As part of the 1995 RI, a human health risk assessment and ecological risk assessment were performed. Tables 32 and 33 provide the selected COPCs and representative concentrations of inorganics and organics in site-related subsurface soil and sediment, respectively. Exposure pathways, potential receptors, uncertainties, and conclusions are included.

Human Health Risk Assessment


The result of the conservative first-level screening (baseline) risk assessment was greater than 1E-04 for cancer risk and greater than a value of 1.0 for non-cancer risk; therefore, additional risk analysis was performed according to EPA guidance.

The identified potential receptors were evaluated on the basis of current land use (industrial employee) and hypothetical future land use (residential, recreational, and industrial receptors).

Estimated carcinogenic risks and non carcinogenic HQs are summarized in Tables 34 through 42.

The human health risk assessment concluded that the total RME cancer risk associated with the future residential (subsurface soil) exposure scenario was approximately 1E-04; the upper end of the target risk range. However, the RME estimate for the future residential receptor was probably overconservative because a central tendency calculation shows that cancer risks were more likely to be within the mid-range of the target acceptable risk range.

The RME cancer risk associated with the future industrial (subsurface soil) exposure scenario was approximately 5E-05; within the target acceptable risk range. The cancer risk associated with the future recreational (sediment) exposure scenario via ingestion and dermal contact was below 1E-06. Arsenic (via ingestion of and dermal contact with subsurface soil) was the major COPC that contributed to the cancer risk for the future residential receptor and the future industrial receptor exposure scenarios.



**CONCENTRATIONS ABOVE SCREENING LEVELS
SITE 22 - PAINT CHIP DISPOSAL AREA**

FIGURE 11

Noncarcinogenic HQs associated with the future residential and future industrial (subsurface soil) exposure scenarios and the future recreational (sediment) exposure scenario were below 1.0; the cutoff point below which adverse effects are not expected to occur.

Lead concentrations detected at the site were below the EPA guidelines are not expected to be associated with significant increases in blood-lead levels based on the results of the IEUBK Lead Model (v. 0.99).

The risk assessment procedure resulted in the elimination of all COPCs with calculated risk above target guideline limits. Arsenic could not be eliminated from consideration because it is a class A carcinogen.

Risk characterization results (total RME cancer risks and noncarcinogenic HIs) are presented for all potential receptors at Site 22 in Table 41 for subsurface soil and sediment. Table 42 presents the relevant central tendency risk estimates associated with potential receptors for subsurface soil.

Ecological Risk Assessment

Ecotox threshold (ET) values were used for screening potential ecological risks from contaminated sediments and surface soil. Sediment and surface soil ET values are presented in Tables 43 and 44, respectively.

Site 22 provides only limited habitat of relatively poor ecological value, while the swamp to the south provides excellent wetland habitat. Most of the swamp is wooded, and hence, provides habitat primarily for terrestrial and semi-aquatic receptors. A drainage swale runs along the inside

border of the berm and receives all overland flow in the area. The swale exits the site and runs southeast along the railroad tracks. A small tributary of Hockhockson Brook runs through the swamp and connects with the drainage swale several hundred feet southeast of the site. Runoff of contaminants to the swamp is precluded by the berm that surrounds most of the site, but runoff may exit the site via the swale. Groundwater-to-surface water contaminant migration in the wetlands is unlikely due to the presumed direction of groundwater flow.

Site 22 - Evaluation and Recommendations

Metals concentrations in soils were determined to be within the range of background.

All COPCs contributing to risk above the guideline range, or to HQs above one, were less than the corresponding background concentration. However, arsenic which is a class A carcinogen, cannot be removed from consideration.

PAHs and metals found in sediments at levels above ecological toxicity threshold values could migrate with surface water runoff.

The presence of metals in the shallow subsurface soil appears to be a result of surface disposal of paint chips and paint sludge. The limited extent of contamination (vertically and horizontally) would facilitate a limited soil removal, with disposal according to visual inspection for evidence of paint particles in the soil.

The risk assessment concluded that limited removal of contaminated soils and sediments near the building would preclude migration of potentially ecotoxic compounds to downstream ecological receptors. Post excavation soil sampling would

be required to evaluate interim soil remediation efforts.

1996 Remedial Action

Based on the results of the 1995 RI, a focused remedial action was performed at Site 22 to address specific areas of soil contamination. The results of this remedial action were summarized in a report entitled "Close-out Report - Removal Actions at Sites 22, 23, and 27" dated February 14, 1997.

The remedial action included excavation of contaminated soils in areas of known contamination. Figure 12 depicts the areas which were excavated. An area of approximately 38 feet by 50 feet by 1 foot deep was excavated on the western side of Building D-2. An additional area, measuring approximately 16 feet by 4 feet was excavated to a depth of approximately 3 feet. Excavated soil was transported to R-3 Technologies (Morrisville, Pennsylvania) for disposal.

Approximately 250 tons of contaminated soil were excavated as part of this effort. At the completion of excavation activities and collection of confirmatory samples, the excavated areas were backfilled with clean fill to be level with the surrounding grade, and were re-vegetated.

Confirmatory samples were collected after soil excavation activities were complete. A total of 8 confirmatory samples were collected, including 6 soil samples from the sidewall of the excavation and 2 samples from the bottom of the excavation (Figure 12). Analytical results of the confirmatory soil samples are summarized in Table 45. NJDEP Soil Cleanup Criteria are also included on Table 45.

Analytical results from the 8 confirmatory soil samples indicated that contaminant levels in all soil samples were below regulatory cleanup levels when compared with NJDEP Residential Direct Contact, Non-Residential Direct Contact, and Impact to Groundwater soil cleanup criteria. Based on these results, no further action was taken at Site 22.

SITE 23 - PAINT DISPOSAL AREA

Site Background and Physical Setting

The paint disposal area near Building D-5 was used from the early 1970s until approximately 1993 for paint wastes from repainting and stenciling torpedoes, aerial bombs, and other large ordnance. The site consists of approximately 200 square feet of ground surface west of the northwest corner of building D-5 where paint disposal to the ground surface reportedly occurred in the past (IAS).

Figure 6 is a map of the site. During 1993 SI work at the site, a small amount of paint residue was present inside the fence line, southwest of Building D-5; no such residue was visible during an October 1993 preliminary RI site visit, nor was an area of bare ground evident. Considering the contradictory reports of where the "site" was, and the metals concentrations found in shallow soil samples taken, it seems likely that paint wastes may have been dumped anywhere on the ground near Building D-5 to the west or southwest. Documentation of past removal actions was not available.

The building D-5 complex is constructed into a naturally sloping hillside. Natural grade is higher to the north and east making a natural soil "berm"

UNNAMED ROAD

12' PIPE
CATCH BASIN

3x3' PAD
w/COVER

8000 gal.
(UST) NEW

22-CS05

22-CS08

22-CS04

22-CS03

22-CS02

22-CS07

TOP OF SLOPE

TOE OF BERM

3' Deep
excavation

BOILER
ROOM

BLDG. D-2

GROUND
CABLE

LOADING DOCK

DRAINAGE DITCH

BERM

PONDED WATER

PFOIC

26


Legend

● Confirmatory Soil Sample Location

Wetlands

Excavated Area
(1' Deep except where noted)

BASE MAP DEVELOPED FROM BROWN & ROOT ENVIRONMENTAL
REMEDIAL INVESTIGATION REPORT FOR NAVAL WEAPONS STATION EARLE,
COLTS NECK, NJ, MARCH 1996



<p>U.S. Navy RAC NWS Earle, Colts Neck, NJ</p>
<p>FIGURE 12 Site 22 - Paint Chlp Disposal Area Area Remediated</p>
<p>FOSTER WHEELER ENVIRONMENTAL CORPORATION</p>

wall about 20 feet high on those sides. To the west and southwest, an earthen berm has been placed about 20 feet high to complete the soil berm enclosure of the D-5 complex on three sides. A drainage ditch is present west of the building, within the bermed area. A small wetland is located northwest and uphill of the building, which appears to be the source of a small stream which runs intermittently in the drainage ditch west of Building D-5.

The site is partially paved, and overland runoff flows radially across the site into shallow drainage depressions that surround the site on three sides. The drainage flows toward the southeast. A tributary of Hockhockson Brook is located approximately 500 feet southwest of the site. SI work indicated that a shallow perched-water layer may be present above the water-table aquifer at the site. Shallow groundwater generally flows toward the north-northeast.

Geology and Hydrogeology

Regional mapping places Site 23 in the outcrop area of the Kirkwood Formation; upper colluvium may be present at the site. The upper colluvium has a maximum thickness of 10 feet, the Kirkwood Formation ranges between 60 to 100 feet in thickness, and the soil borings are no more than 27 feet deep. Based upon the boring log descriptions, the wells penetrated the upper colluvium and the Kirkwood and Vincentown Formations.

Groundwater in the upper colluvium, Kirkwood, and Vincentown aquifer beneath the site occurs under unconfined conditions and the formations are interpreted to be hydraulically interconnected. Groundwater elevations for August 1995 and October 1995 are contoured on Figures 13 and

14, respectively. The direction of shallow groundwater flow in the aquifer, as indicated by both the August and October groundwater contour maps, is toward the north-northeast. There does not appear to be a significant seasonal variation in groundwater flow direction.

Based on boring log descriptions, the wells are screened across the contact between the Kirkwood and Vincentown Formations. The hydraulic conductivities calculated for MW23-01 and MW23-02 are 2.79×10^{-3} cm/sec (7.91 ft/day) and 2.04×10^{-3} cm/sec (5.78 ft/day), respectively.


Remedial Investigations

IAS

The 1983 IAS, consisting of interviews and observations, concluded that a bare area of approximately 200 square feet had been used for paint disposal to surface soil. The site was not recommended for confirmation study because it was believed that the amount of paint dumped on the area was not enough to pose a significant environmental or public health hazard.

SI

During the 1993 SI, six soil samples (from 0 to 3 feet bgs), eight sediment samples, and one hydropunch groundwater sample were collected for analysis. Sample analysis indicated that low levels of VOCs and metals were present in soil samples, the highest levels of chromium and lead were detected in a soil sample taken west of Building D-5 in the vicinity of RI soil boring 23 SB 04. Low levels of organics and one pesticide were detected in sediment, and elevated metals were detected in sediments. Groundwater




GROUNDWATER CONTOUR MAP AUGUST 7, 1995

SITE 23 - PAINT DISPOSAL AREA



FIGURE 13






GROUNDWATER CONTOUR MAP OCTOBER 17, 1995

FIGURE 14

SITE 23 - PAINT DISPOSAL AREA



contained low levels of organics and some elevated levels of metals.

The IAS concluded that surface soils had slight signs of staining from paint residues. Elevated levels of metals (mainly chromium and lead) at concentrations sometimes above regulatory guideline limits were found in soil and sediments. Elevated levels of lead and chromium were also found in groundwater samples. Low levels of organics were found in direct-push groundwater samples.

1995 Remedial Investigation

Based on previous investigations, follow-up remedial investigation activities were developed to meet the following objectives:

- Determine vertical extent of soil contamination in soil west of Building D-5.
- Determine whether surface water or wetland has been impacted by past practices.
- Investigate groundwater quality in the area of former paint dumping.
- Compare metals data to background levels and risk based criteria.
- Determine impact of turbidity on metals results by using the low-flow sampling technique.

Between July and October 1995, B&R Environmental conducted the following field investigation activities at Site 23:

- Sampling and analysis of subsurface soil samples from three soil borings and one hand-auger boring
- Drilling and installation of three shallow permanent monitoring wells
- Sampling and analysis of groundwater from the wells
- Measurement of static water-levels in the wells
- Execution of slug tests in two of the wells
- Sampling and analysis of surface water
- Sampling and analysis of sediment


Nature and Extent of Contamination

Subsurface Soils

Seven site-related subsurface soil samples (23 SB 01-04, 23 SB 01-16, 23 SB 02-02, 23 SB 02-16, 23 SB 03-06, 23 SB 03-14, and 23 SB 04-02) were collected at Site 23 (Figure 6). Tables 46 and 47 present the occurrence and distribution of inorganic chemicals detected in site-related subsurface soil samples and compare them to background. Tables 48 and 49 present a comparison of detected compounds to ARARs and TBCs. Figure 15 shows sample locations and concentrations of compounds which exceed ARARs and TBCs.

Sediment

Five sediment samples were collected at Site 23: 23 SD 01 through 23 SD 05 (Figure 6). Tables 50 and 51 present the occurrence and distribution of



**CONCENTRATIONS ABOVE SCREENING LEVELS
SITE 23 - PAINT DISPOSAL AREA**

FIGURE 15



inorganic and organic chemicals in site-related sediment samples and compare them to background. Table 52 presents a comparison of detected compounds to ARARs and TBCs. Figure 15 shows sample locations and concentrations of compounds which exceed ARARs and TBCs.

Groundwater

Three site-related groundwater samples (23 GW 01 through 23 GW 03) were collected at Site 23 (Figure 6). Tables 53 and 54 present the occurrence and distribution of inorganic and organic chemicals detected in site-related groundwater samples and compare them to background. Table 55 presents a comparison of detected compounds to ARARs and TBCs. Figure 15 shows sample locations and concentrations of compounds which exceed ARARs and TBCs.

Surface Water

Three surface water samples were collected at Site 23: 23 SW 03 through 23 SW 05 (Figure 6). Tables 56 and 57 present the occurrence and distribution of inorganic and organic chemicals in site-related surface water samples. Table 58 presents a comparison of detected compounds to ARARs and TBCs. Figure 15 shows sample locations and concentrations of compounds which exceed ARARs and TBCs.

Summary of Site Risks

A human health risk assessment and ecological risk assessment were performed. Tables 59 through 62 provide the selected COPCs and representative concentrations of inorganics and organics in site-related subsurface soil, sediment, groundwater, and surface water, respectively.

Exposure pathways, potential receptors, uncertainties, and conclusions are included.

Human Health Risk Assessment

The result of the conservative first level screening (baseline) risk assessment was greater than a value of 1.0 for non-cancer risk and greater than 1E-04 for cancer risk; therefore, additional risk analysis was performed according to EPA guidance.

The identified potential receptors were evaluated on the basis of current land use (industrial employee) and hypothetical future land use (residential, recreational, and industrial receptors).

Estimated carcinogenic risks and non carcinogenic HQs are summarized in Tables 63 to 83.

The human health risk assessment concluded that RME cancer risks associated with future industrial (subsurface soil and groundwater) and future residential (subsurface soil and groundwater) exposure scenarios exceeded 1E-04, the upper end of the target risk range. Arsenic (via ingestion of and dermal contact with groundwater and subsurface soil) was the major COPC that contributed to the cancer risks for these exposure scenarios. However, these RME estimates are probably overconservative because a central tendency calculation shows that cancer risks are more likely to be in the mid-range of the target acceptable range for the future industrial receptor (groundwater and subsurface soil), and approximately 1E-04, at the upper end of the target acceptable risk range, for the future residential receptor (groundwater or subsurface soil). In addition, filtered metals results, which are considered more representative of dissolved-

phase concentrations, are considerably lower than the unfiltered concentration and would yield a commensurate reduction in the estimated risk.

RME estimates for noncarcinogenic HIs associated with future industrial (groundwater) and future residential (subsurface soil and groundwater) exposure scenarios exceeded 1.0; the cutoff point below which adverse noncarcinogenic effects are not expected to occur. Chromium, cadmium, iron, and arsenic (chiefly via ingestion of groundwater) were the COPCs that exceeded 1.0 or contributed to the HI exceeding 1.0 for these exposure scenarios. In addition, central tendency risk estimates for residential and industrial exposure to groundwater yielded HIs greater than 1.0 for the target organs liver, kidney, skin, and digestive system. The RME estimates of noncancer risk from exposure to subsurface soil for the future residential child are probably overconservative because associated central tendency noncancer HIs are less than 1.0. In addition, filtered metals results, which are considered more representative of dissolved-phase concentrations, are considerably lower than the unfiltered concentration and would yield a commensurate reduction in the estimated risk.

Lead was detected at the site at levels greater than the EPA screening guidelines. Based on the results of the IEUBK Lead Model (v. 0.99), the maximum detected soil and groundwater concentrations might be expected to be associated with significant increases in blood-lead levels (i.e., above 10 ug/dL) in 6.8 percent of children from a population exposed under similar conditions. This slightly exceeds the EPA guideline of no more than 5 percent of the population exhibiting elevated blood-lead levels.

The risk assessment procedure did not result in the elimination of all cancer or non-cancer risks above guideline limits. Although several metals by groundwater ingestion remained with cancer risks greater than the target acceptable range and HIs above 1.0, the estimated risks may not be representative of dissolved phase metals contamination receptor impacts because only unfiltered sampling results were used to calculate risks.

Risk characterization results (total cancer risks and total noncarcinogenic HIs) are presented for all potential receptors at Site 23 in Table 84 for subsurface soil, sediment, groundwater, and surface water. Table 85 presents the relevant central tendency risk estimates associated with potential receptors for subsurface soil and groundwater.

Ecological Risk Assessment

Ecotox threshold (ET) values were used for screening potential ecological risks from contaminants in surface water and sediments. Surface water and sediment ET values are presented in Tables 86 and 87, respectively.

The ecological risk assessment determined that potential risks to ecological receptors from contaminants detected in surface water and sediment samples taken as part of the 1995 RI were relatively low.

Since potential risks to ecological receptors at Site 23 appear to be low and off-site contaminant migration is minimal, further study or remediation based on ecological risk concerns at the site appear to be unnecessary.

1996 Remedial Action

Based on the results of the 1995 RI, a focused remedial action was performed at Site 23 to address specific areas of soil contamination. The results of this remedial action was summarized in a report entitled "Close-out Report - Removal Actions at Sites 22, 23, and 27" dated February 14, 1997.

The remedial action included excavation of contaminated soils in areas of known contamination. Figure 16 depicts the areas which were excavated.

An area of approximately 18 feet by 3 feet by 2.8 foot deep was excavated on the southwestern side of Building D-5. Excavated soil was transported to R-3 Technologies (Morrisville, Pennsylvania) for disposal.

Approximately 86 tons of contaminated soil were excavated as part of this effort. At the completion of excavation activities and collection of confirmatory samples, the excavated areas were backfilled with clean fill to a level to match the surrounding grade and were re-vegetated.

Confirmatory samples were collected after soil excavation activities were complete. A total of 8 confirmatory samples were collected, including 6 soil samples from the sidewall of the excavation and 2 samples from the bottom of the excavation (Figure 16).

Analytical results of the confirmatory soil samples are summarized in Table 88. NJDEP Soil Cleanup Criteria are also included on Table 88.

Analytical results from the 8 confirmatory soil samples indicated that contaminant levels were

generally below regulatory cleanup levels when compared with NJDEP Residential Direct Contact, Non-Residential Direct Contact, and Impact to Groundwater soil cleanup criteria. Thallium was the only contaminant which exceeded any of the soil cleanup criteria (Residential Direct Contact and Non-Residential Direct Contact).

Since the contaminated surface soil was removed and replaced by clean fill as part of the Site 22 remediation, the Impact to Groundwater soil cleanup criteria were deemed applicable. None of the 8 confirmatory soil samples exceeded the Impact to Groundwater soil cleanup criteria. Based on these results, no further action was taken at Site 23.

SITES 24 AND 25 - CLOSED PISTOL RANGES

Site Background and Physical Setting

Sites 24 and 25 are closed pistol ranges that were once used for target practice. Due to the sites' similar nature, history, and close proximity, they have been treated together.

During target practice at the sites, lead- and copper-jacketed bullets were fired into 70-foot-high impact berms (natural sand banks). Preserved wooden posts at the sites formed the firing platform. No drainage swales or wetlands are on or near the sites (Figure 7).

Geology and Hydrogeology

Regional mapping places Sites 24 and 25 in the outcrop area of the Cohansey Sand; upland colluvium and gravel, undivided, may be present at the sites. The upland colluvium and gravel,

LEGEND



Area Excavated

Confirmatory Soil Sample Location


MONITORING WELL LOCATION

WETLANDS

WETLANDS DELINEATION
SOURCE NJDEP (SEE SECTION 1.5)

DRAINAGE DITCH

DLG STREAM COVERAGE
SOURCE: USGS RESTON, VA



BASE MAP DEVELOPED FROM BROWN & ROOT ENVIRONMENTAL
REMEDIAL INVESTIGATION REPORT FOR NAVAL WEAPONS STATION EARLE,
COLTS NECK, NJ, MARCH 1996

navyraclerlefig3-2

<p>U.S. Navy RAC NWS Earle, Colts Neck, NJ</p>
<p>FIGURE 16 Site 23 - Paint Disposal Area Area Remediated (Confirmatory Soil Sample Locations Depicted)</p>
<p>FOSTER WHEELER ENVIRONMENTAL CORPORATION</p>

undivided, has a maximum thickness of 10 feet, the Cohansey Sand ranges between 0 and 30 feet in thickness, and the hand-auger borings at Sites 24 and 25 were no more than 9 feet deep. The sediments encountered in the hand-auger borings generally agree with the published descriptions of the upland colluvium and gravel, undivided, and the Cohansey Sand. In general, the borings encountered gray and brown medium- and coarse-grained sand and brown, medium- to coarse-grained sand.

Groundwater conditions beneath the site cannot be confirmed because no wells were installed at the site. However, groundwater in the Cohansey aquifer beneath Site 4, and presumably Sites 24 and 25, occurs under unconfined conditions. Site 4 is located about 1,300 feet south-southeast of Sites 24 and 25. The direction of shallow groundwater flow in the aquifer beneath Site 4, as indicated by both the August and October groundwater contour maps for Site 4, is toward the east and east-southeast.

Remedial Investigations

IAS

The 1983 IAS, consisting of interviews and visual inspection, concluded minimal impact. The site was not recommended for a confirmation study.

SI

Four soil samples were collected from shallow soil borings from the berms behind the target areas during the 1993 SI field activities. The samples were collected from approximately 3 feet bgs. Lead slugs were removed from the material before the samples were sent for analysis. Soil samples were analyzed for lead, zinc, copper,

chromium, and cadmium. Analysis indicated that lead was the primary metal of concern at the site.

1995 Remedial Investigation

Based on previous investigations, follow-up remedial investigation activities were developed to meet the following objectives:

- Determine the extent of penetration and the density of projectiles in the impact areas.
- Perform ecological risk assessment.

In August 1995, B&R Environmental conducted the following field investigation activities at Sites 24 and 25:

- The total number of lead slugs (bullets) was counted, in 6-inch-depth intervals, at two locations at each site.
- Subsurface soil samples from two borings at each site were sampled and analyzed.

Nature and Extent of Contamination - Site 24

Subsurface Soils

Four site-related subsurface soil samples (24 SB 01-05, 24 SB 01-08, 24 SB 02-03, and 24 SB 02-06) were collected at Site 24 (Figure 7). Table 89 presents the occurrence and distribution of inorganic chemicals detected in site-related subsurface soil samples and compares them to background. Tables 90 and 91 present a comparison of detected compounds to ARARs and TBCs.

Nature and Extent of Contamination - Site 25

Subsurface Soils

Four site-related subsurface soil samples (25 SB 01-05, 25 SB 01-08, 25 SB 02-03, and 25 SB 02-06) were collected at Site 25 (Figure 7). Table 92 presents the occurrence and distribution of inorganic chemicals detected in Site 25 background and site-related subsurface soil samples. Tables 93 and 94 present a comparison of detected compounds to ARARs and TBCs.

Summary of Site Risks

A human health risk assessment and ecological risk assessment were performed. Tables 95 and 96 provide the selected COPCs and representative concentrations of inorganics in site-related subsurface soil for Sites 24 and 25, respectively. Exposure pathways, potential receptors, uncertainties, and conclusions are included.

Human Health Risk Assessment

The results of the risk assessment are presented in the risk characterization and are discussed on a receptor-specific basis. The identified potential receptors have been evaluated on the basis of hypothetical future land use (residential and industrial receptors).

Conclusions - Site 24

The potential receptors for this site were future industrial and residential receptors. Tables 97 through 100 summarize carcinogenic risks and non carcinogenic HQs for Site 24.

The cancer risk associated with the future residential (subsurface soil) exposure scenario was approximately $6E-05$, in the middle of the target risk range. Arsenic (via ingestion of and dermal contact with subsurface soil) and beryllium (via dermal contact with subsurface soil) were the major COPCs that contributed to the cancer risk for this exposure scenario. The noncarcinogenic HQs associated with the future industrial and future residential (subsurface soil) exposure scenarios were below 1.0; the cutoff point below which adverse effects are not expected to occur.

Lead concentrations at the site were detected at concentrations that are not expected to be associated with significant increases in blood-lead levels based on the results of the IEUBK Lead Model (v. 0.99). Risk characterization results (total cancer risks and total noncarcinogenic HIs) are presented for all potential receptors at Site 24 in Table 101 for subsurface soil.

Conclusions - Site 25

The potential receptors for this site were future industrial and residential receptors. Tables 102 through 105 summarize carcinogenic risks and non carcinogenic HQs for Site 25.

The cancer risk associated with the future residential (subsurface soil) exposure scenario was approximately $3E-05$, near the middle of the target risk range. Arsenic (via ingestion of and dermal contact with subsurface soil) and beryllium (via dermal contact with subsurface soil) were the major COPCs that contributed to the cancer risk for this exposure scenario. The noncarcinogenic HIs associated with the future industrial and residential (subsurface soil) exposure scenario were below 1.0, the cutoff point below which

adverse noncarcinogenic effects are not expected to occur.

Lead concentrations at the site were detected at concentrations that are not expected to be associated with significant increases in blood-lead levels based on the results of the IEUBK Lead Model (v. 0.99).

Risk characterization results (total cancer risks and total noncarcinogenic HIs) are presented for all potential receptors at Site 25 in Table 106 for subsurface soil.

The areas inside the firing ranges are primarily exposed soil with little vegetation, precluding the existence of significant ecological habitat. Excellent upland habitats are present surrounding the sites, and a wide variety of terrestrial wildlife is expected to use these areas. However, runoff of contaminants to off-site habitats is partially limited by berms surrounding the sites, and no drainageways from the site are present. In addition, groundwater contaminant discharge to surface water is not likely since no surface waters are present near Sites 24 and 25.

SI soil samples from the impact berms contained low levels of some metals, including cadmium, chromium, lead, copper, and zinc. The results of RI subsurface soil sampling indicate the presence of some inorganic contaminants, but concentrations were similar to background concentrations. Contaminant levels in samples taken below the deepest slug penetration were below levels of regulatory concern, suggesting no migration to groundwater. There are no significant contaminant migration pathways to the upland areas that surround the sites, and no migration pathways into the Hockhockson Brook Watershed. Quantitative ecological risk

assessment was not applicable at Sites 24 and 25 since any risk numbers would be mitigated by the factors discussed above. Hence, potential risks to ecological receptors appear insignificant and the site was excluded from quantitative ecological risk

1996 Remedial Action

The results of previous remedial investigations recommended removal of bullets and shell casings from Sites 24 and 25. A focused remedial action was later performed at Sites 24 and 25 to remove bullets and shell casings from each site. The remedial action involved mechanical separation of the metal bullets from the sandy impact berms and subsequent washing of the soils.

As part of the remedial action, approximately 1,500 tons of soil was processed from the sites. A total of 10 tons of bullets were recovered as part of this effort.

The bullets were sold to a local metal recycler. Lead-containing sludge from the soil washing system was sent to an asphalt batch plant for recycling. The washed soils were backfilled at each site and the wash water was discharged to the Station's wastewater treatment plant for final processing.

Table 107 summarizes the results of confirmatory soil samples collected after excavation of the berms and firing lines were complete. Table 108 summarizes the results of samples collected of the washed soils. Results show lead levels below regulatory criteria.

SITE 27 - PROJECTILE REFURBISHING AREA

Site Background and Physical Setting

Site 27 includes Building E-14 and a small storage locker located off Oran Road (Figure 8). Projectiles are refurbished at the site by shot-blasting, repainting, and stenciling. Oil-contaminated rags, paint chips, and spent sandblasting shot were disposed behind the facility (IAS, 1983). A small portion of the site surface (approximately 80 square feet) near the southeast corner of Building E-14 was covered by a red paint sludge.

A railroad siding and small drainage depression exist on the east side of the site behind the building. Overland runoff drains towards the southeast to the shallow depression approximately 15 feet downslope from the paint sludge area. Surface water infiltration occurs within the drainage depression. The east branch of Mingamahone Brook is located approximately 1200 to 1500 ft east-southeast of the site.

Geology and Hydrogeology

Regional mapping places Site 27 within the outcrop area of the Kirkwood Formation. The Kirkwood Formation ranges between 60 and 100 feet in thickness and the soil borings are no more than 12 feet deep. The lithology of the sediments encountered in the on-site soil borings generally agrees with the published description of the Kirkwood Formation. The borings encountered light brown, pebbly, fine-grained sand with varying amounts of clay and silt.

Groundwater conditions beneath the site cannot be confirmed because no wells were installed at the site. However, groundwater in the Kirkwood

Formation beneath Sites 3 and 26, and presumably Site 27, occurs under unconfined conditions. Site 3 is located about 3,200 feet south-southeast and Site 26 is located about 3,000 feet north of the site. The direction of shallow groundwater flow in the aquifer beneath Site 3, as indicated by the August groundwater contour map for Site 3, is toward the southeast. The direction of groundwater flow in the aquifer beneath Site 26, as indicated by both the August and October groundwater contour maps for Site 26, is toward the southwest.

Remedial Investigations

IAS

The 1983 IAS, consisting of interviews, concluded that the approximately eighty cubic feet of paint chips and blast shot posed no significant threat to the environment or public health because the material was considered relatively inert. The site was not recommended for a confirmation study.

SI

The 1993 SI field activities included collection of ten soil samples and eight sediment samples. Two soil samples (at 0 to 0.5 ft bgs and 0.5 to 1.5 ft bgs) were collected at five different locations concentrated in the area of observed soil staining behind Building E-14. Shallow soils encountered within the zone were disturbed in places and composed of red brown gravelly sand with some slag, sand blasting material, and paint chips. Analysis of soil samples detected elevated concentrations of metals, PCBs, and semivolatiles.

The eight sediment samples were collected within the drainage ditch between the railroad tracks located behind Building E-14 and one sediment sample was collected to the east of the main railroad track in a dry drainage depression. Low concentrations of metals and pesticides and trace levels of SVOCs were detected in several sediment samples.

1995 Remedial Investigation

Based on previous investigations, follow-up remedial investigation activities were developed to meet the following objectives:

- Determine vertical extent of soil contamination.
- Compare data to background levels and risk based criteria.
- Using all data collected to date, determine whether wetlands, or surface water has been impacted.

In December 1995, B&R Environmental conducted the following field investigation activities at Site 27:

- Sampling and analysis of subsurface soil samples from two soil borings
- Sampling and analysis of subsurface soil samples from one had-augured boring

Nature and Extent of Contamination

Subsurface Soils

Nine subsurface soil samples were collected at Site 27 (Figure 8). Tables 109 and 110 present

the occurrence and distribution of inorganic and organic chemicals in site-related samples and compare them to background values. Tables 111 and 112 present a comparison of detected compounds to ARARs and TBCs. Figure 17 shows sample locations and concentrations of compounds which exceed ARARs and TBCs.

SUMMARY OF SITE RISKS


A human health risk assessment and ecological risk assessment were performed.

Table 113 provides the selected COPCs and representative concentrations of inorganic and organics in site-related subsurface soil.

Human Health Risk Assessment


The identified potential receptors have been evaluated on the basis of hypothetical future land use (residential receptors and industrial receptors). Tables 114 through 118 summarize the RME Carcinogenic risks and the RME noncarcinogenic risks associated with Site 27.

The results of the human health risk assessment determined that the RME cancer risk associated with the future residential (subsurface soil) exposure scenario is greater than 1E-04; the upper end of the target risk range. Arsenic (via ingestion of and dermal contact with soil) is the major COPC that contributed to this cancer risk. However, the RME estimate for the future residential receptor is probably overconservative because a central tendency calculation shows that cancer risks are more likely to be within the mid-range of the target acceptable risk range.



**CONCENTRATIONS ABOVE SCREENING LEVELS
SITE 27 - PROJECTILE REFRUBISHING**

FIGURE 17



The RME cancer risk associated with the future industrial (subsurface soil) exposure scenario was approximately 4E-05, within the target acceptable risk range. RME noncarcinogenic HIs associated with the future residential and future industrial (subsurface soil) exposure scenarios were below 1.0, the cutoff point below which adverse effects are not expected to occur.

Lead soil concentrations at the site were below EPA guidelines and are not expected to be associated with significant increases in blood-lead levels based on the results of the IEUBK Lead Model (v. 0.99).

Risk characterization results (total RME cancer risks and total RME noncarcinogenic HIs) are presented for all potential receptors at Site 27 in Table 119 for subsurface soil. Table 120 presents the relevant central tendency risk estimates associated with future residential receptors for subsurface soil.

The baseline risk assessment procedure resulted in the elimination of all COPCs with associated risk above target guideline limits. However, it must be noted that the objective of this study was not to perform a site-wide characterization. Samples taken in the RI (1995) were biased, based on previous sampling, toward the area of known contamination to delineate vertical migration for contaminants for remedial design considerations. The result of using only the 1995 RI data could have biased the human health risk assessment results high or low.

Ecological Risk Assessment

Ecotox threshold (ET) values were used for screening potential ecological risks from

contaminated sediments. Sediment ET values are presented in Table 121.

The site consists of a gravel-covered parking area in the vicinity of buildings, railroad tracks, and a paved road. Therefore, limited ecological habitat exists on the site. The wooded area to the east provides excellent upland habitat and is most likely used by a wide variety of upland receptors. Runoff from the site flows to the adjacent drainage ditch, though water in the ditch infiltrates and does not flow off-site. No significant surface water is present near the site, mitigating potential groundwater to surface water contaminant migration.

The results of 1993 SI and 1995 RI indicate that concentrations of metals are present in site soils and in the drainage ditch that pose significant potential risk to ecological receptors. However, these potential risks are mitigated by several factors. First of all, Site 27 is small, limiting significant receptor use. Second, the drainage ditch contains no standing water and no aquatic habitat. Only terrestrial receptors would come into contact with the ditch, but are not expected to significantly use the area since no habitat is present. Furthermore, water in the ditch, present only after heavy rainfall, tends to infiltrate rather than flow off-site, and no surface water is present near the site. Therefore, contaminant migration downstream or contaminant contributions to the watershed appear to be negligible. For these reasons, further ecological study at Site 27 appeared to be unwarranted, but removal of paint chips and associated soils, and limited removal of ditch sediments appeared to be appropriate.

1996 Remedial Action

Based on the results of the 1995 RI, a focused remedial action was performed at Site 27 to address specific areas of soil contamination. The results of this remedial action were summarized in a report entitled "Close-out Report - Removal Actions at Sites 22, 23, and 27" dated February 14, 1997.

The remedial action included excavation of contaminated soils in areas of known contamination. Figure 18 depicts the areas which were excavated.

An area with a perimeter of approximately 173 linear feet by 1 foot deep was excavated. Excavated soil was transported to R-3 Technologies (Morrisville, Pennsylvania) for disposal.

Approximately 54 tons of contaminated soil were excavated as part of this effort. At the completion of excavation activities and collection of confirmatory samples, the excavated areas were backfilled with clean fill to a level to match the surrounding grade, and re-vegetated.

Confirmatory samples were collected after soil excavation activities were complete. Eight confirmatory soil samples were collected, including 6 soil samples from the sidewall of the excavation and 2 samples from the bottom of the excavation (Figure 18).

Analytical results from the 8 initial confirmatory soil samples indicated contaminant levels that exceeded NJDEP Residential Direct Contact and Non-Residential Direct Contact soil cleanup criteria.

A second soil excavation, to remove additional soils based on the results of the first round of (eight) confirmatory soil samples, was performed (Figure 18 shows the areas of excavation). Table 122 shows the results of the second round of (2) confirmatory soil samples.

Since the contaminated surface soil was removed and replaced by clean fill as part of the Site 27 remediation, the Impact to Groundwater soil cleanup criteria were deemed applicable. None of the 10 confirmatory soil samples exceeded Impact to Groundwater soil cleanup criteria. Based on these results, no further action was taken at Site 27.


SITE 29 - PCB SPILL SITE

Site Background and Physical Setting

This site is located in a storage yard (north of Site 16/F) where an unknown quantity of PCBs spilled from a transformer in 1981. No record exists suggesting that PCB compounds flowed any significant distance overland or in a ditch. Within 5 days after the spill, all discolored soil (over 120 cubic feet) was disposed off-site. NWS Earle has constructed a one-story, brick building at the site that will function as the new hazardous waste storage facility. A railroad spur and wetlands are located east of the site, and Saipan Road is located along the western side. Figure 9 is a site map.

Geology and Hydrogeology

Regional mapping places Site 29 within the outcrop area of the Kirkwood Formation; upper colluvium may be present at the site. The upper colluvium has a maximum thickness of 10 feet, the Kirkwood Formation ranges between 60 to



navyrac\erlefig33

<p>U.S. Navy RAC NWS Earle, Colts Neck, NJ</p>
<p>FIGURE 18 Site 27 - Projectile Returbishing Site Area Remediated (Confirmatory Soil Sample Locations-Depicted)</p>
<p>FOSTER WHEELER ENVIRONMENTAL CORPORATION</p>

100 feet in thickness, and the soil borings installed for the two monitoring wells are no more than 42 feet deep. The lithology of the sediments encountered in the on-site borings generally agrees with the published description of the upper colluvium and the Kirkwood Formation. In general, the borings encountered fill material, olive gray and brown, silty, fine- to coarse-grained sand with gravel (possibly representative of the upland gravel) and yellowish-brown and olive, pebbly, silty, fine- to coarse-grained sand and sandy clay (probably representative of the Kirkwood Formation).

Based upon the boring log descriptions, well MW29-01 penetrated fill material and the Kirkwood Formation, and well MW29-02 penetrated the upland gravel and the Kirkwood Formation.

Groundwater in the Kirkwood aquifer beneath the site occurs under unconfined conditions. There are insufficient data points to contour the water table beneath Site 29; however, the elevational data from both August and October 1995 indicate a westward component to shallow groundwater at the site. There does not appear to be a significant seasonal variation in groundwater flow direction.

R m dial Investigations

IAS

The 1983 IAS, consisting of interviews and site observations, noted that there was a PCB spill. Reportedly, all visible evidence of the spill was removed in an immediate removal action. The site was not recommended for a confirmation study.

SI

During the 1992 SI field investigation, five soil samples (from 0.5 to 1.5 feet bgs) were collected from the area of the PCB spill at Site 29. Samples were obtained within the relatively small area labeled "approximate location of PCB spill" on Figure 9. Minor amounts of pesticides and PCBs were detected at concentrations below New Jersey clean-up standards. One sample contained high concentrations of TPH (28,000 mg/kg).

As part of the environmental site evaluation for the proposed hazardous waste storage facility, additional field work was performed at the site. To further evaluate the possible impacts from past activities and to assess subsurface soil conditions for foundation design, seven soil borings were completed at the site in mid-1993 (Haley & Aldrich, Incorporated, 1993). All 1993 soil borings and monitoring wells were installed within the area labeled "new hazardous waste storage facility under construction" shown on Figure 9. Soil borings were completed to depths ranging from 17 to 42 feet bgs and were sampled at 5 and 10 feet bgs. Six of the seven soil borings were converted to monitoring wells. Trace levels of VOCs, semivolatiles, pesticides, and PCBs were detected in the soils, all below New Jersey subsurface soil criteria. Groundwater samples indicated that trace to low levels of VOCs and semivolatiles were present, and no detectable concentrations of pesticides or PCBs were present. Elevated levels of benzene (30 ppb) and DCE (25 ppb) were reported in former well MW29-04. Total lead and total chromium were present in groundwater at levels above state criteria. The six wells installed in 1993 were destroyed by subsequent construction activities at the site.

Storage Building Construction

Soil was removed for construction of the new hazardous waste storage facility to a depth of approximately 8 feet below grade in the entire area labeled "new hazardous waste storage facility under construction" (Figure 9) before 1995 RI field activities were carried out. Due to dry conditions, no groundwater was encountered in the excavation. The excavated soil was stockpiled and composite soil samples were collected and analyzed prior to shipment of the soil off site. The results of these samples are summarized in Table 143.

Consequently, the original plan for RI activities at the site was not feasible (since the entire site had been removed), and therefore was modified in the field after consultation with EPA and NJDEP. The excavated site soils were stockpiled, sampled, analyzed to determine disposal options, and found to be non-hazardous.

The original removal action apparently was effective in removing spilled PCBs. However, low levels of various organics were found in groundwater and low levels of PCBs and organics were found in soil samples.

Construction activities for the new hazardous waste storage facility virtually removed the entire study area.

1995 Remedial Investigation

Based on previous investigations and removal actions, follow-up remedial investigation activities were developed to meet the following objectives:

- Investigate subsurface soil quality downgradient of the former site.

- Confirm groundwater quality downgradient of the former site.
- Perform risk analysis to determine if further action is required.

Between July and October 1995, B&R Environmental conducted the following field investigation activities at Site 29:

- Sampling and analysis of subsurface soil samples from two soil borings
- Drilling and installation of two shallow permanent monitoring wells
- Sampling and analysis of groundwater from the wells
- Measurement of static water levels in the monitoring wells


NATURE AND EXTENT OF CONTAMINATION

Subsurface Soils

Two site-related subsurface soil samples (29 SB 01-02 and 29 SB 02-02) were collected at Site 29 (Figure 9). Table 123 presents the occurrence and distribution of organic chemicals detected in site-related subsurface soil samples and compares them to background. Tables 124 and 125 present a comparison of detected compounds to ARARs and TBCs. Figure 19 shows sample locations.


Groundwater

Two site-related groundwater samples (29 GW 01 and 29 GW 02) were collected (Figure 9). Tables 126 and 127 present the occurrence and



**CONCENTRATIONS ABOVE SCREENING LEVELS
SITE 29 - PCB SPILL SITE**

FIGURE 19



Brown & Root Environmental

distribution of inorganic chemicals detected in site-related groundwater samples and compare them to background. Table 128 presents a comparison of detected compounds to ARARs and TBCs. Figure 19 shows sample locations and concentrations of compounds which exceed ARARs and TBCs.

SUMMARY OF SITE RISKS

As part of the 1995 RI, a human health risk assessment and ecological risk assessment were performed. Tables 129 and 130 provide the selected COPCs and representative concentrations of organics in site-related subsurface soil and inorganics and organics in site-related groundwater, respectively.

Human Health Risk Assessment

The result of the first level screening (baseline) human health risk assessment indicated a value of 1.0 for non-cancer risk; therefore, additional risk analysis was performed according to EPA guidance. The identified potential receptors have been evaluated on the basis of hypothetical future land use (residential and industrial receptors).

Estimated carcinogenic risks and noncarcinogenic HQs are summarized in Tables 131 through 140.

The RME cancer risks associated with the future residential and future industrial (subsurface soil and groundwater) exposure scenarios were within the 1E-04 to 1E-06 target acceptable risk range. Iron (via ingestion of groundwater) was the principal COPC that contributed to these carcinogenic risks.

The noncarcinogenic HQs associated with future industrial (groundwater) and future residential

(groundwater) exposure scenarios exceeded 1.0; the cutoff point below which adverse effects are not expected to occur. Iron (via ingestion of groundwater) was the COPC that exceeded 1.0 for these exposure scenarios. In addition, central tendency risk estimates for residential exposure to groundwater yielded HIs greater than 1.0 for the liver and digestive system as the target organs.

Lead concentrations at the site were below EPA guideline limits and are not expected to be associated with significant increases in blood-lead levels based on the results of the IEUBK Lead Model (v. 0.99).

The risk assessment procedure did not result in the elimination of all COPCs which had calculated risk above target guideline limits. Iron remained with HQs above 1.0 for groundwater ingestion by the future residential child receptor.

Risk characterization results (total RME cancer risks and total RME noncarcinogenic HIs) are presented for all potential receptors at Site 29 in Table 141 for subsurface soil and groundwater. Table 142 presents the relevant central tendency risk estimates associated with future residential receptors for groundwater.

Ecological Risk Assessment

Site 29 PCB spill area was remediated as part an immediate removal action at the time of the original spill. It contains little ecological habitat of value due to construction on the site, although forested wetland habitats are present near the site. Runoff of contaminants to the forested wetland areas is possible, but is inhibited by the developed areas around the site, and infrequent flow in the drainage swale. The spill area was small and was excavated within five days after the

spill, minimizing the probability of migration. In the SI, five soil samples were taken in the area where soils were removed. Trace levels of some organochlorine pesticides, PCBs, and TPH were detected, and one elevated concentration (28,000 mg/kg) of TPH was detected. For the most part, subsurface soil samples taken during 1995 RI activities contained low levels (below levels of concern) of the same compounds detected in the SI. A sediment sample, 16 SD 01 (and a duplicate), taken in the storm drain east of Site 29 and south of Site 16, represents the only potential overland runoff pathway to the wetlands east of Site 29. No PCBs were detected in 16 SD 01 or its duplicate. With the exception of a few slightly elevated detections for some metals, 1995 RI groundwater samples indicated that impacts to groundwater at the site were minimal, and no PCBs or organochlorines were detected. Any residual PCBs, or organochlorine pesticides and petroleum hydrocarbons, detected at the site are not expected to significantly migrate via overland runoff or infiltration due to their strong affinity for organic fractions in soils and sediments, nor is there evidence that they may have migrated before they were removed, because of the quick and apparently adequate removal response.

Since risk numbers would be mitigated by the factors mentioned above, quantitative ecological risk assessment at Site 29 was not applicable. For these reasons, potential ecological risks from site contaminants appear negligible, as is the potential for contaminant contributions to the Hockhockson Brook Watershed. Therefore, Site 29 was excluded from further consideration.

Based on the results of previous investigations and removal actions, no further action was taken at Site 29.

OU-4 SUMMARY

Based on available information, the Navy and EPA believe that, based on the information gathered to date, no further action is required for OU-4 sites.

The Navy solicits written comments from the community on the plan for no further action at the OU-4 sites. The Navy has set a public comment period from **Month/Day/Year** through **Month/Day/Year** to encourage public participation in the decision process for OU-4 sites.

The Navy will hold a public meeting during the comment period. At the public meeting, the Navy, along with EPA, will present the Proposed Plan, answer questions, and solicit both oral and written questions. **The public meeting is scheduled for 7:00 p.m. on Month/Day/Year and will be held at Building C-54 at NWS Earle.**

Comments received during the public comment period will be summarized and responses will be provided in the Responsiveness Summary section of the ROD. The ROD is the document that will present the Navy's decision for the OU-4 sites. To send written comments, or to obtain further information, contact

Commanding Officer
Naval Weapons Station Earle
Code 043
201 Highway 34 South
Colts Neck, New Jersey 07722-5014

For further information, contact John Kolicius,
Remedial Project Manager

Phone: (610) 595-0567 ext. 157

**Pl ase note that all comments must be
submitted and postmarked on or before**

TERMS USED IN THE PROPOSED PLAN

1,2-Dichloroethene (1,2-DCE): Common volatile organic solvent formerly used for cleaning, degreasing or other uses in commerce and industry.

Applicable or Relevant and Appropriate Requirements (ARARs): The federal and state requirements that a selected remedy must attain. These requirements may vary among sites and remedial activities.

Administrative Record: An official compilation of site-related documents, data, reports, and other information that are considered important to the status of and decisions made relative to a Superfund site. The public has access to this material.

Carcinogenic: A type of risk resulting from exposure to chemicals that may cause cancer in one or more organs.

Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA): A federal law passed in 1980 and modified in 1986 by the Superfund Amendments and Reauthorization Act (SARA). The Act created a trust fund, known as Superfund, to investigate and clean up abandoned or uncontrolled hazardous substance facilities.

EPTOX: Analytical procedure used before development of TCLP. Determined leachate toxicity in samples.

Feasibility Study (FS): Report identifying and evaluating alternatives for addressing the contamination present at a site or group of sites.

Groundwater Quality Standards (GWQS): New Jersey promulgated groundwater quality requirements, N.J.A.C. 7:9-6.

Hazard Index (HI): The sum of chemical-specific Hazard Quotients. A Hazard Index of greater than 1 is associated with an increased level of concern about adverse non-cancer health effects.

Hazard Quotient (HQ): A comparison of the level of exposure to a substance in contact with the body per unit time to a chemical-specific Reference Dose to evaluate potential non-cancer health effects. Exceedence of a Hazard Quotient of 1 is associated with an increased level of concern about adverse non-cancer health effects.

IEUBK Lead Model: Accounts for multi-media nature of lead exposure to determine the risk likely to occur at a site.

Initial Assessment Study (IAS): Preliminary investigation usually consisting of review of available data and information of a site, interviews, and a non-sampling site visit to observe areas of potential waste disposal and migration pathways.

Land Disposal Restrictions (LDRs): A set of EPA-prescribed limit concentrations with associated treatment standards regulating disposal in landfills.

Maximum Contaminant Level (MCL): EPA-published (promulgated as law) maximum concentration level for compounds found in water in a public water supply system.

Noncarcinogenic: A type of risk resulting from the exposure to chemicals that may cause systemic human health effects.

National Contingency Plan (NCP): The National Contingency Plan is the basis for the nationwide environmental restoration program known as Superfund and is administered by EPA under the direction of the U.S. Congress.

National Priorities List (NPL): EPA's list of the nation's top priority hazardous substance disposal facilities that may be eligible to receive federal money for response under CERCLA.

No Further Action (NFA): Determination for a site based on compliance with applicable regulatory guidelines for cleanup. If the results of remedial investigations and/or remedial actions determine that contamination levels are below regulatory guidelines, a NFA declaration is prepared.

Polychlorinated Biphenyls (PCBs): Class of chlorinated aromatic compounds (typically used as cooling fluids in electrical transformers) which are strongly adsorbed on solid particles.

Presumptive Remedy: Preferred technologies for common categories of sites based on historical patterns of remedy selection and EPA's scientific and engineering evaluation of performance data on technology implementation. Presumptive remedies ensure the consistent selection of remedial actions.

RCRA Subtitle D facility: Municipal-type waste disposal facility (landfill) regulated by the Resource Conservation and Recovery Act (RCRA).

Record of Decision (ROD): A legal document that describes the remedy selected for a Superfund facility, why the remedial actions were chosen and others not, how much they are expected to cost, and how the public responded.

Reference Dose (RD): An estimate with an uncertainty spanning an order of magnitude or greater of a daily exposure level for the human population, including sensitive subpopulations, that is likely to be without an appreciable risk of deleterious effects during a portion of a lifetime.

Remedial Action Objective (RAO): An objective selected in the FS, against which all potential remedial actions are judged.

Remedial Investigation (RI): Study that determines the nature and extent of contamination at a site.

Site Inspection (SI): Sampling investigation with the goal of identifying potential sources of contamination, types of contaminants, and potential migration of contaminants. The SI is conducted prior to the RI.

Semivolatile Organic Compounds (SVOCs): Organic chemicals [e.g., phthalates or polycyclic aromatic hydrocarbons (PAHs)] that do not readily evaporate under atmospheric conditions.

Target Compound List/Target Analyte List (TCL/TAL): List of routine organic compounds (TCL) or metals (TAL) included in the EPA Contract Laboratory Program.

Total Petroleum Hydrocarbons (TPH): Analysis to measure petroleum-related compounds in total, rather than as individual chemicals

Toxicity Characteristic Leaching Procedure

(TCLP): Analytical test prescribed by EPA to determine potential leachate toxicity in materials; commonly used to determine the suitability of a waste for disposal in a landfill.

Trichloroethene (TCE): Common volatile organic solvent formerly used for cleaning, degreasing or other uses in commerce and industry.

Volatile Organic Compounds (VOCs): Organic liquids [e.g., vinyl chloride or trichloroethylene (TCE)] that readily evaporate under atmospheric conditions.

FOR FURTHER INFORMATION

MAILING LIST

If you did not receive this Proposed Plan in the mail and wish to be placed on the mailing list for future information pertaining to this site, please fill out, detach, and mail this form to:

Commanding Officer
Naval Weapons Station Earle
Code 043
201 Highway 34 South
Colts Neck, New Jersey 07722-5014

Name: _____

Affiliation: _____

Address: _____

Phone: () _____

TABLES

TABLE 1
OCCURRENCE AND DISTRIBUTION OF INORGANICS IN SURFACE SOILS AT SITE 20
NWS EARLE, COLTS NECK, NEW JERSEY
(mg/kg)

SUBSTANCE	BACKGROUND			SITE-RELATED				
	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	2 X AVERAGE BKGD CONCENTRATION	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	AVERAGE CONCENTRATION	MEAN > 2 X BKGD	REPRESENTATIVE CONCENTRATION
ALUMINUM	4 / 4	1710 - 5310	6152.50	5 / 5	904 - 3670	2586.80	NO	3670
ANTIMONY	NOT DETECTED	-	-	2 / 5	1 - 2.4	0.85	YES	2.4
ARSENIC	4 / 4	1.35 - 14.4	13.43	5 / 5	1.3 - 5.4	2.55	NO	5.4
BARIUM	4 / 4	1.85 - 31	22.53	5 / 5	5.1 - 58	25.02	YES	58
BERYLLIUM	1 / 4	0.28	0.39	5 / 5	0.072 - 2.7	0.90	YES	2.7
CADMIUM*	1 / 4	0.57	0.67	4 / 5	0.11 - 0.26	0.14	NO	0.26
CALCIUM	4 / 4	40.1 - 519	551.80	5 / 5	118 - 2320	1091.40	YES	2320
CHROMIUM*	4 / 4	7.8 - 59.5	69.05	5 / 5	4.2 - 97.1	33.29	NO	97.1
C BALT	2 / 4	0.75 - 5	3.15	5 / 5	0.47 - 18.4	5.76	YES	18.40
COPPER	4 / 4	0.97 - 8.4	10.06	5 / 5	8.2 - 447	121.05	YES	300.24
IRON*	4 / 4	3745 - 62500	52402.50	5 / 5	1740 - 16500	7941.00	NO	16500
LEAD	4 / 4	1.8 - 39.4	37.30	5 / 5	3.6 - 252	86.42	YES	252
MAGNESIUM	4 / 4	71.7 - 619	578.85	5 / 5	53.5 - 1185	551.30	NO	1185
MANGANESE	4 / 4	3.45 - 214	128.33	5 / 5	6.4 - 126	51.90	NO	126
MERCURY	4 / 4	0.035 - 0.17	0.18	5 / 5	0.025 - 0.0455	0.03	NO	0.0427
NICKEL*	2 / 4	1.8 - 7.2	5.18	3 / 5	4.3 - 7.4	24.94	YES	7.4
POTASSIUM	4 / 4	95 - 792	912.50	5 / 5	72.2 - 410	249.84	NO	410
SELENIUM*	2 / 4	0.57 - 0.93	1.03	2 / 5	1.2 - 1.4	0.79	NO	1.4
SILVER*	2 / 4	0.37 - 0.67	0.69	1 / 5	0.83	0.24	NO	0.83
SODIUM	4 / 4	17.5 - 86.2	78.30	5 / 5	19.1 - 206	125.98	YES	206
THALLIUM	2 / 4	0.7 - 1.9	1.64	2 / 5	0.75 - 1	0.58	NO	1
VANADIUM	4 / 4	11.05 - 64	70.13	5 / 5	5.4 - 23.8	13.63	NO	23.8
ZINC	3 / 4	1.1 - 27.6	22.80	5 / 5	4.2 - 972	294.13	YES	972

Note: Selected COPCs are indicated in boldface type.
* - Indicates COPCs eliminated based on amended risk assessment.

TABLE 2
OCCURRENCE AND DISTRIBUTION OF ORGANICS IN SURFACE SOIL AT SITE 20
NWS EARLE, COLTS NECK, NEW JERSEY
 (ug/kg)

SUBSTANCE	BACKGROUND			SITE-RELATED		
	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	REPRESENTATIVE CONCENTRATION	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	REPRESENTATIVE CONCENTRATION
ANTHRACENE	NOT DETECTED	-	-	1 / 5	63.5	63.5
BENZO(A)ANTHRACENE	NOT DETECTED	-	-	3 / 5	41 - 500	500
BENZO(A)PYRENE	NOT DETECTED	-	-	1 / 5	315	261.42
BENZO(B)FLUORANTHENE	NOT DETECTED	-	-	2 / 5	80 - 500	374.14
BENZO(G,H,I)PERYLENE	NOT DETECTED	-	-	1 / 5	235	211.47
BENZO(K)FLUORANTHENE	NOT DETECTED	-	-	1 / 5	205	193.86
BUTYLBENZYLPHTHALATE	1 / 4	220	220	1 / 5	66	66
CARBAZOLE	NOT DETECTED	-	-	1 / 5	54	54
CHRYSENE	NOT DETECTED	-	-	3 / 5	57 - 490	490
DIBENZOFURAN	NOT DETECTED	-	-	1 / 5	45	45
FLUORANTHENE	2 / 4	40 - 84	-	3 / 5	78 - 750	525.57
INDENO(1,2,3-CD)PYRENE	NOT DETECTED	-	-	1 / 5	245	217.69
PHENANTHRENE	NOT DETECTED	-	-	3 / 5	39 - 520	520
PYRENE	1 / 4	46	46	3 / 5	96 - 810	562.13

TABLE 3

COMPARISON OF SURFACE SOIL ANALYTICAL DATA TO ARARS AND TBCs - SITE 20
NWS EARLE, COLTS NECK, NEW JERSEY

SAMPLE NUMBER: LOCATION: DATA SOURCE:	20SS01	20SS02	20SS02-DUP	20SS03	20SS04	20SS05	ARARS & TBCs		
	20SS01	20SS02	20SS02	20SS03	20SS04	20SS05	NJDEP Soil Residential Direct Contact Cleanup Criteria	NJDEP Soil Non-Residential Direct Contact Cleanup Criteria	NJDEP Soil Impact to Groundwater Cleanup Criteria
	1995 RI								
INORGANICS	mg/kg	mg/kg	mg/kg						
aluminum	2000	3520	3720	3670	2740	904	-	-	-
antimony	0.57 U	0.55 U	0.55 U	2.4	1.0	0.58 U	14.0	340	-
arsenic	1.5	2.5	2.8	5.4	1.9	1.3	20.0	20.0	-
barium	5.1	14.1	15.3	58.0	39.4	7.9	700	47000	-
beryllium	0.072	0.21	0.23	2.7 E	1.4 E	0.085	1.00	1.00	-
cadmium	0.081 U	0.11	0.11	0.26	0.19	0.11	1.00	100	-
calcium	209	2400	2240	1690	1120	118	-	-	-
chromium, total	7.6 J	13.0 J	13.9 J	97.1 J	44.1 J	4.2 J	-	500	-
cobalt	0.47	2.3	2.5	18.4	6.9	0.63	-	-	-
copper	8.2	20.9	20.4	447	119	10.4	600	600	-
iron	4850	7480	7990	16500	8880	1740	-	-	-
lead	3.6	16.1	16.9	252	115	45.0	400	600	-
magnesium	188	1200	1170	806	524	53.5	-	-	-
manganese	6.4	57.4	58.4	126	57.9	11.3	-	-	-
mercury	0.025	0.044	0.047	0.030	0.025	0.034	14.0	270	-
nickel	4.3	7.4	8.2 R	162 R	54.8 R	4.6	250	2400	-
potassium	163	225	253	410	365	72.2	-	-	-
selenium	1.2 J	0.89 UJ	0.89 UJ	1.4 J	0.89 UJ	0.94 UJ	63.0	3100	-
silver	0.20 U	0.19 U	0.19 U	0.83	0.19 U	0.20 U	110	4100	-
sodium	75.8	206	206	206	123	19.1	-	-	-
thallium	0.76 U	0.75	0.73 U	1.0	0.73 U	0.77 U	2.00	2.00	-
vanadium	8.5	15.2	16.3	23.8	14.7	5.4	370	7100	-
zinc	4.2	42.0 J	52.9 J	972 J	402 J	45.0 J	1500	1500	-
SEMIVOLATILES	ug/kg	ug/kg	ug/kg						
anthracene	350 U	47.0 J	80.0 J	340 U	330 U	350 U	10000000	10000000	100000
benzo(a)anthracene	350 U	320 J	500	55.0 J	41.0 J	350 U	900	4000	500000
benzo(a)pyrene	350 U	240 J	390 J	340 U	330 U	350 U	660	660	100000
benzo(b)fluoranthene	350 U	500	780 J	340 U	80.0 J	350 U	900	4000	50000

TABLE 3

COMPARISON OF SURFACE SOIL ANALYTICAL DATA TO ARARS AND TBCs - SITE 20
NWS EARLE, COLTS NECK, NEW JERSEY

SAMPLE NUMBER:	20SS01		20SS02		20SS02-DUP		20SS03		20SS04		20SS05		ARARS & TBCs		
	LOCATION:	20SS01		20SS02		20SS02		20SS03		20SS04		20SS05		NJDEP Soil Residential Direct Contact Cleanup Criteria	NJDEP Soil Non-Residential Direct Contact Cleanup Criteria
DATA SOURCE:	1995 RI		1995 RI		1995 RI		1995 RI		1995 RI		1995 RI				
SEMIVOLATILES	ug/kg		ug/kg		ug/kg		ug/kg		ug/kg		ug/kg		ug/kg	ug/kg	ug/kg
benzo(g,h,i)perylene	350	U	170	J	300	J	340	UJ	330	U	350	U	-	-	-
benzo(k)fluoranthene	350	U	160	J	250	J	340	U	330	U	350	U	900	4000	500000
butylbenzylphthalate	350	U	330	U	340	U	340	U	66.0	J	350	U	1100000	10000000	100000
carbazole	350	U	330	U	54.0	J	340	U	330	U	350	U	-	-	-
chrysene	350	U	380		600		71.0	J	57.0	J	350	U	9000	40000	500000
dibenzofuran	350	U	330	U	45.0	J	340	U	330	U	350	U	-	-	-
fluoranthene	350	U	670		830		140	J	78.0	J	350	U	2300000	10000000	100000
indeno(1,2,3-cd)pyrene	350	U	190	J	300	J	340	U	330	U	350	U	900	4000	500000
phenanthrene	350	U	380		660		100	J	39.0	J	350	U	-	-	-
pyrene	350	U	620		1000		120	J	96.0	J	350	U	1700000	10000000	100000

Footnotes to sample results:

- U - Compound or element was not detected. Value is the detection limit (inorganics) or quantitation limit (organics).
- UJ - Not detected. Detection limit or quantitation limit shown is considered estimated due to exceedance of data validation quality control criteria.
- No Value - Constituent was not analyzed for in this sample.
- UR - Nondetected result is considered rejected based on exceedance of data validation quality control criteria.
- J - Value is estimated because concentration is below the quantitation limit or because of exceedance of data validation quality control criteria.
- R - Positive result is considered rejected based on exceedance of data validation quality control criteria.
- N - Compound is considered to be tentatively identified based on exceedance of QC criteria for compound identification.
- E - Result exceeds one or more of the selected ARARs.

Footnotes to soil criteria:

- No standard is available for this chemical in this classification.

TABLE 4

COMPARISON OF SURFACE SOIL MISCELLANEOUS PARAMETERS DATA TO ARARS AND TBCs - SITE 20

NWS EARLE, COLTS NECK, NEW JERSEY

SAMPLE NUMBER:	20SS03	20SS04	---	---	---	---	ARARS & TBCs			
	LOCATION:	20SS03	20SS04	---	---	---	---	NJDEP Soil Residential Direct Contact Cleanup Criteria	NJDEP Soil Non-Residential Direct Contact Cleanup Criteria	NJDEP Soil Impact to Groundwater Cleanup Criteria
DATA SOURCE:	1995 RI	1995 RI								
MISCELLANEOUS	mg/kg	mg/kg					mg/kg	mg/kg	mg/kg	
total organic carbon	2100	1900								

Footnotes to sample results:

- U - Compound or element was not detected. Value is the detection limit (inorganics) or quantitation limit (organics).
- UJ - Not detected. Detection limit or quantitation limit shown is considered estimated due to exceedance of data validation quality control criteria.
- No Value - Constituent was not analyzed for in this sample.
- UR - Nondetected result is considered rejected based on exceedance of data validation quality control criteria.
- J - Value is estimated because concentration is below the quantitation limit or because of exceedance of data validation quality control criteria.
- R - Positive result is considered rejected based on exceedance of data validation quality control criteria.
- N - Compound is considered to be tentatively identified based on exceedance of QC criteria for compound identification.
- E - Result exceeds one or more of the selected ARARs.

Footnotes to soil criteria:

- No standard is available for this chemical in this classification.
- @ - Value is New Jersey guideline for maximum total concentration of all organic compounds in soil (including VOCs, SVOCs, and TPH).

TABLE 5

**OCCURRENCE AND DISTRIBUTION OF INORGANICS IN SUBSURFACE SOILS AT SITE 20
NWS EARLE, COLTS NECK, NEW JERSEY
(mg/kg)**

SUBSTANCE	BACKGROUND			SITE-RELATED				
	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	2 X AVERAGE BKGD CONCENTRATION	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	AVERAGE CONCENTRATION	MEAN > 2 X BKGD	REPRESENTATIVE CONCENTRATION
ALUMINUM	8 / 8	675 - 5310	5370.00	3 / 3	1730 - 4560	3023.33	NO	4560
ARSENIC	8 / 8	1.35 - 14.4	13.29	2 / 3	2.9 - 5.1	2.77	NO	5.1
BARIUM	8 / 8	0.92 - 31	17.92	3 / 3	9.2 - 47.5	24.83	YES	47.5
CALCIUM	8 / 8	28.6 - 799	577.55	3 / 3	84.8 - 810	391.27	NO	810
CHROMIUM	8 / 8	4.7 - 59.5	54.73	3 / 3	3.7 - 11.1	8.23	NO	11.1
COBALT	4 / 8	0.75 - 5	2.77	1 / 3	1	0.56	NO	1
COPPER	8 / 8	0.97 - 8.6	8.66	3 / 3	1.7 - 8.1	5.43	NO	8.1
IRON	8 / 8	3745 - 62500	40871.25	3 / 3	1690 - 10500	6820.00	NO	10500
LEAD	8 / 8	1.4 - 39.4	24.33	3 / 3	4.4 - 14	9.50	NO	14
MAGNESIUM	8 / 8	18.5 - 619	504.05	3 / 3	55.1 - 287	154.37	NO	287
MANGANESE	8 / 8	2.6 - 214	92.51	3 / 3	9.2 - 16.2	12.53	NO	16.2
MERCURY	8 / 8	0.03 - 0.17	0.13	3 / 3	0.052 - 0.14	0.10	NO	0.14
NICKEL	4 / 8	1.8 - 7.2	4.75	2 / 3	1.7 - 2.6	1.68	NO	2.6
POTASSIUM	7 / 8	95 - 792	793.35	3 / 3	136 - 391	249.67	NO	391
SELENIUM	2 / 8	0.57 - 0.93	0.79	2 / 3	1.3 - 1.4	1.00	YES	1.4
SODIUM	8 / 8	17.5 - 94.8	79.35	3 / 3	40.7 - 127	76.40	NO	127
VANADIUM	8 / 8	11.05 - 64	64.71	3 / 3	3.7 - 13.5	9.27	NO	13.5
ZINC	6 / 8	1.1 - 50.7	31.35	3 / 3	1.3 - 4.1	2.23	NO	4.1

Note: Selected COPCs are indicated in boldface type.

TABLE 6
OCCURRENCE AND DISTRIBUTION OF ORGANICS IN SUBSURFACE SOIL AT SITE 20
NWS EARLE, COLTS NECK, NEW JERSEY
 (ug/kg)

SUBSTANCE	BACKGROUND			SITE-RELATED		
	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	REPRESENTATIVE CONCENTRATION	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	REPRESENTATIVE CONCENTRATION
1,2-DICHLOROETHENE (TOTAL)	NOT DETECTED	-	-	2 / 3	8 - 15	15
2-BUTANONE	NOT DETECTED	-	-	2 / 3	38 - 71	71
4-METHYLPHENOL	NOT DETECTED	-	-	1 / 3	72	72
ETHYLBENZENE	NOT DETECTED	-	-	1 / 3	5	5
TOLUENE	NOT DETECTED	-	-	3 / 3	1 - 13	13

TABLE 7

COMPARISON OF SUBSURFACE SOIL ANALYTICAL DATA TO ARARS AND TBCs - SITE 20
NWS EARLE, COLTS NECK, NEW JERSEY

SAMPLE NUMBER:	20SB01-03	20SB02-03	20SB03-03	---	---	---	ARARS & TBCs			
	LOCATION:	20SB01	20SB02	20SB03	---	---	---	NJDEP Soil Residential Direct Contact Cleanup Criteria	NJDEP Soil Non-Residential Direct Contact Cleanup Criteria	NJDEP Soil Impact to Groundwater Cleanup Criteria
DATA SOURCE:	1995 RI	1995 RI	1995 RI							
INORGANICS	mg/kg	mg/kg	mg/kg				mg/kg	mg/kg	mg/kg	
aluminum	1730	4560	2780				-	-	-	
arsenic	0.59 U	5.1	2.9				20.0	20.0	-	
barium	9.2	47.5	17.8				700	47000	-	
calcium	84.8	810	279				-	-	-	
chromium, total	3.7	11.1	9.9				-	500	-	
cobalt	0.64 U	1.0	0.71 U				-	-	-	
copper	1.7	8.1	6.5				600	600	-	
iron	1690	10500	8270				-	-	-	
lead	4.4	14.0	10.1				400	600	-	
magnesium	55.1	287	121				-	-	-	
manganese	9.2 J	16.2 J	12.2 J				-	-	-	
mercury	0.052 J	0.14 J	0.10 J				14.0	270	-	
nickel	1.5 U	2.6	1.7				250	2400	-	
potassium	136	391	222				-	-	-	
selenium	0.59 U	1.4 J	1.3 J				63.0	3100	-	
sodium	61.5	127	40.7				-	-	-	
vanadium	3.7	13.5	10.6				370	7100	-	
zinc	1.3 J	4.1 J	1.3 J				1500	1500	-	
SEMIVOLATILES	ug/kg	ug/kg	ug/kg				ug/kg	ug/kg	ug/kg	
4-methylphenol	390 U	72.0 J	430 U				2800000	10000000	-	
VOLATILES	ug/kg	ug/kg	ug/kg				ug/kg	ug/kg	ug/kg	
1,2-dichloroethene (total)	12.0 U	15.0 J	8.0 J				79000	1000000	1000	
2-butanone	12.0 U	71.0	38.0				1000000	1000000	50000	
ethylbenzene	12.0 U	5.0 J	13.0 U				1000000	1000000	100000	
toluene	1.0 J	13.0 J	6.0 J				1000000	1000000	500000	

TABLE 7
COMPARISON OF SUBSURFACE SOIL ANALYTICAL DATA TO ARARS AND TBCS - SITE 20
NWS EARLE, COLTS NECK, NEW JERSEY

FINAL
PAGE 2

Footnotes to sample results:

- U** - Compound or element was not detected. Value is the detection limit (inorganics) or quantitation limit (organics).
- UJ** - Not detected. Detection limit or quantitation limit shown is considered estimated due to exceedance of data validation quality control criteria.
- No Value** - Constituent was not analyzed for in this sample.
- UR** - Nondetected result is considered rejected based on exceedance of data validation quality control criteria.
- J** - Value is estimated because concentration is below the quantitation limit or because of exceedance of data validation quality control criteria.
- R** - Positive result is considered rejected based on exceedance of data validation quality control criteria.
- N** - Compound is considered to be tentatively identified based on exceedance of QC criteria for compound identification.
- E** - Result exceeds one or more of the selected ARARs.

Footnotes to soil criteria:

- No standard is available for this chemical in this classification.

TABLE 8
OCCURRENCE AND DISTRIBUTION OF INORGANICS IN SEDIMENT AT SITE 20
NWS EARLE, COLTS NECK, NEW JERSEY
(mg/kg)

SUBSTANCE	BACKGROUND				SITE-RELATED				
	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	2 X AVERAGE BKGD CONCENTRATION	REPRESENTATIVE CONCENTRATION	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	AVERAGE CONCENTRATION	MEAN > 2 X BKGD	REPRESENTATIVE CONCENTRATION
ALUMINUM	3 / 3	839 - 3940	5492.67	3940	1 / 1	1720	1720	NO	1720
ARSENIC	2 / 3	2.4 - 6.2	5.95	6.2	1 / 1	2.6	2.6	NO	2.6
BARIUM	3 / 3	3.9 - 10.6	14.07	10.6	1 / 1	12.3	12.3	NO	12.3
BERYLLIUM	1 / 3	0.57	0.67	0.57	1 / 1	0.1	0.1	NO	0.1
CADMIUM	NOT DETECTED	-	-	-	1 / 1	0.14	0.14	YES	0.14
CALCIUM	3 / 3	179 - 518	685.33	518	1 / 1	878	878	YES	878
CHROMIUM	3 / 3	4.3 - 56	43.13	56	1 / 1	6.1	6.1	NO	6.1
COBALT	1 / 3	2.1	3.30	2.1	1 / 1	0.26	0.26	NO	0.26
COPPER	3 / 3	1.5 - 13	12.47	13	1 / 1	5	5	NO	5
IRON	3 / 3	228 - 7650	6578.67	7650	1 / 1	2960	2960	NO	2960
LEAD	3 / 3	4.6 - 34.3	30.60	34.3	1 / 1	9.2	9.2	NO	9.2
MAGNESIUM	3 / 3	60.7 - 256	306.47	256	1 / 1	227	227	NO	227
MANGANESE	3 / 3	4.6 - 9.2	13.80	9.2	1 / 1	9.9	9.9	NO	9.9
MERCURY	1 / 3	0.068	0.05	0.068	1 / 1	0.046	0.046	NO	0.046
NICKEL	2 / 3	2.1 - 6	7.93	6	1 / 1	2.2	2.2	NO	2.2
POTASSIUM	2 / 3	86.1 - 681	589.40	681	1 / 1	155	155	NO	155
SODIUM	3 / 3	26.6 - 116	115.27	116	1 / 1	35.5	35.5	NO	35.5
VANADIUM	3 / 3	5.9 - 42.7	36.93	42.7	1 / 1	7.2	7.2	NO	7.2
ZINC	3 / 3	14.2 - 26.9	37.33	26.9	1 / 1	11.7	11.7	NO	11.7

Note: Selected COPCs are indicated in boldface type.

TABLE 9
OCCURRENCE AND DISTRIBUTION OF ORGANICS IN SEDIMENT AT SITE 20
NWS EARLE, COLTS NECK, NEW JERSEY
 (ug/kg)

SUBSTANCE	BACKGROUND			SITE-RELATED		
	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	REPRESENTATIVE CONCENTRATION	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	REPRESENTATIVE CONCENTRATION
BENZO(A)ANTHRACENE	2 / 3	140 - 560	560	1 / 1	90	90
BENZO(A)PYRENE	2 / 3	160 - 590	590	1 / 1	100	100
BENZO(B)FLUORANTHENE	2 / 3	150 - 490	490	1 / 1	160	160
BENZO(G,H,I)PERYLENE	2 / 3	130 - 380	380	1 / 1	54	54
BENZO(K)FLUORANTHENE	2 / 3	150 - 470	470	1 / 1	50	50
CHRYSENE	2 / 3	250 - 940	940	1 / 1	130	130
FLUORANTHENE	2 / 3	300 - 1800	1800	1 / 1	150	150
PHENANTHRENE	2 / 3	200 - 1900	1900	1 / 1	120	120
PYRENE	2 / 3	350 - 1900	1900	1 / 1	230	230

TABLE 10

COMPARISON OF SEDIMENT ANALYTICAL DATA TO ARARS AND TBCs - SITE 20
NWS EARLE, COLTS NECK, NEW JERSEY

SAMPLE NUMBER:	20SD01	---	---	---	---	---	---	ARARS & TBCs
								Sediment Ecological Toxicity Threshold Values
LOCATION:	20SD01	---	---	---	---	---	---	
DATA SOURCE:	1995 RI							
INORGANICS	mg/kg							mg/kg
aluminum	1720							-
arsenic	2.6							8.20 L
barium	12.3							40.0 B
beryllium	0.10							-
cadmium	0.14							1.20 L
calcium	878							-
chromium, total	6.1	J						81.0 L
cobalt	0.26							50.0 T
copper	5.0							34.0 L
iron	2960							-
lead	9.2							47.0 L
magnesium	227							-
manganese	9.9							460 O
mercury	0.046							0.150 L
nickel	2.2							21.0 L
potassium	155							-
sodium	35.5							-
vanadium	7.2							-
zinc	11.7	J						150 L
SEMIVOLATILES	ug/kg							ug/kg
benzo(a)anthracene	90.0	J						330 F
benzo(a)pyrene	100	J						430 L
benzo(b)fluoranthene	160	J						330 F
benzo(g,h,i)perylene	54.0	J						330 F
benzo(k)fluoranthene	50.0	J						330 F
chrysene	130	J						330 F
fluoranthene	150	J						2900 Q
phenanthrene	120	J						850 Q

07/15/96

TABLE 10

**COMPARISON OF SEDIMENT ANALYTICAL DATA TO ARARS AND TBCs - SITE 20
NWS EARLE, COLTS NECK, NEW JERSEY**

SAMPLE NUMBER:	20SD01	---	---	---	---	---	---	ARARS & TBCs Sediment Ecological Toxicity Threshold Values
LOCATION:	20SD01	---	---	---	---	---	---	
DATA SOURCE:	1995 RI							
SEMIVOLATILES	ug/kg							ug/kg
pyrene	230 J							660 L

TABLE 10
COMPARISON OF SEDIMENT ANALYTICAL DATA TO ARARS AND TBCS - SITE 20
NWS EARLE, COLTS NECK, NEW JERSEY

FINAL
PAGE 3

Footnotes to sample results:

- U - Compound or element was not detected. Value is the detection limit (inorganics) or quantitation limit (organics).
- UJ - Not detected. Detection limit or quantitation limit shown is considered estimated due to exceedance of data validation quality control criteria.
- No Value - Constituent was not analyzed for in this sample.
- UR - Nondetected result is considered rejected based on exceedance of data validation quality control criteria.
- J - Value is estimated because concentration is below the quantitation limit or because of exceedance of data validation quality control criteria.
- R - Positive result is considered rejected based on exceedance of data validation quality control criteria.
- N - Compound is considered to be tentatively identified based on exceedance of QC criteria for compound identification.
- E - Result exceeds one or more of the selected ARARs.

Footnotes to sediment ecological toxicity criteria:

- - No standard is available for this chemical in this classification.
- B - Source: Baudo, R., J. Geisy and H. Muntau. eds. 1990. Sediments: Chemistry and Toxicity of In-Place Pollutants. Lewis Publishers, Inc. Ann Arbor, MI.
- F - Source: USEPA. 1994c. Draft Region IV Waste Management Division Sediment Screening Values for Hazardous Waste Sites. 2/16/94 Revision.
- L - Effects Range-Low. Source: Long E.R., D.D. MacDonald, S.L. Smith, and F.D. Calder. 1995. Incidence of Adverse Biological Effects within Ranges of Chemical Concentrations in Marine and Estuarine Sediments. Environmental Management. 19:81-97.
- M - Effects Range-Low. Source: Long, E. R. and L. G. Morgan. 1991. The Potential for Biological Effects of Sediment-Sorbed Contaminants Tested in the National Status and Trends Program. NOAA Technical Memorandum NOS OMA 52, National Oceanic and Atmospheric Administration, Seattle, WA.
- O - Ontario screening level. Source: Ontario Ministry of the Environment (OME). 1992. Guidelines for the Protection and Management of the Aquatic Sediment Quality in Ontario. Log 92-2309-067, PIBS 1992.
- P - Sediment quality benchmark using equipartition. Source: USEPA. 1996. ECO Update. Volume 3: Number 2. EPA 540/F-95/038.
- Q - Sediment quality criterion. Source: USEPA. 1996. ECO Update. Volume 3: Number 2. EPA 540/F-95/038.
- S - Sediment screening benchmark. Source: Suter, G. W., and J. B. Mabrey. 1994. Toxicological Benchmarks for Screening Potential Contaminants of Concern for Effects on Aquatic Biota. Oak Ridge National Laboratory, Oak Ridge, TN.
- T - Threshold for soils. Source: Direction des Substances Dangereuses. 1988. Contaminated Sites Rehabilitation Policy. Gouvernement du Quebec. Ministere de L'Environnement. Sainte-Foy, Quebec, Canada. In: R.L. Siegrist. 1989. International Review of Approaches for Establishing Cleanup Goals for Hazardous Waste Contaminated Land. Institute for Georesearch and Pollution Research. Norway.
- W - Screening value for wet soil. Source: Will, M.E., and G.W. Suter. 1994. Toxicological Benchmarks for Screening Potential Contaminants of Concern for Effects on Terrestrial Plants: 1994 Revision. Oak Ridge National Laboratory.

06/18/96

TABLE 11

**COMPARISON OF SEDIMENT MISCELLANEOUS PARAMETERS DATA TO ARARS AND TBCs - SITE 20
NWS EARLE, COLTS NECK, NEW JERSEY**

SAMPLE NUMBER:	20SD01	---	---	---	---	---	---	ARARS & TBCs Sediment Ecological Toxicity Threshold Values
LOCATION:	20SD01	---	---	---	---	---	---	
DATA SOURCE:	1995 RI							
MISCELLANEOUS	mg/kg							mg/kg
total organic carbon	5200							

TABLE 11
COMPARISON OF SEDIMENT MISCELLANEOUS PARAMETERS DATA TO ARARS AND TBCS - SITE 20
NWS EARLE, COLTS NECK, NEW JERSEY

FINAL
PAGE 2

Footnotes to sample results:

- U - Compound or element was not detected. Value is the detection limit (inorganics) or quantitation limit (organics).
- UJ - Not detected. Detection limit or quantitation limit shown is considered estimated due to exceedance of data validation quality control criteria.
- No Value - Constituent was not analyzed for in this sample.
- UR - Nondetected result is considered rejected based on exceedance of data validation quality control criteria.
- J - Value is estimated because concentration is below the quantitation limit or because of exceedance of data validation quality control criteria.
- R - Positive result is considered rejected based on exceedance of data validation quality control criteria.
- N - Compound is considered to be tentatively identified based on exceedance of QC criteria for compound identification.
- E - Result exceeds one or more of the selected ARARs.

Footnotes to sediment ecological toxicity criteria:

- - No standard is available for this chemical in this classification.
- B - Source: Baudo, R., J. Geisy and H. Muntau. eds. 1990. Sediments: Chemistry and Toxicity of In-Place Pollutants. Lewis Publishers, Inc. Ann Arbor, MI.
- F - Source: USEPA. 1994c. Draft Region IV Waste Management Division Sediment Screening Values for Hazardous Waste Sites. 2/16/94 Revision.
- L - Effects Range-Low. Source: Long E.R., D.D. MacDonald, S.L. Smith, and F.D. Calder. 1995. Incidence of Adverse Biological Effects within Ranges of Chemical Concentrations in Marine and Estuarine Sediments. Environmental Management. 19:81-97.
- M - Effects Range-Low. Source: Long, E. R. and L. G. Morgan. 1991. The Potential for Biological Effects of Sediment-Sorbed Contaminants Tested in the National Status and Trends Program. NOAA Technical Memorandum NOS OMA 52, National Oceanic and Atmospheric Administration, Seattle, WA.
- O - Ontario screening level. Source: Ontario Ministry of the Environment (OME). 1992. Guidelines for the Protection and Management of the Aquatic Sediment Quality in Ontario. Log 92-2309-067, PIBS 1962.
- P - Sediment quality benchmark using equipartition. Source: USEPA. 1996. ECO Update. Volume 3: Number 2. EPA 540/F-95/038.
- Q - Sediment quality criterion. Source: USEPA. 1996. ECO Update. Volume 3: Number 2. EPA 540/F-95/038.
- S - Sediment screening benchmark. Source: Suter, G. W., and J. B. Mabrey. 1994. Toxicological Benchmarks for Screening Potential Contaminants of Concern for Effects on Aquatic Biota. Oak Ridge National Laboratory, Oak Ridge, TN.
- T - Threshold for soils. Source: Direction des Substances Dangereuses. 1988. Contaminated Sites Rehabilitation Policy. Gouvernement du Quebec. Ministere de L'Environnement. Sainte-Foy, Quebec, Canada. In: R.L. Siegrist. 1989. International Review of Approaches for Establishing Cleanup Goals for Hazardous Waste Contaminated Land. Institute for Georesearch and Pollution Research. Norway.
- W - Screening value for wet soil. Source: Will, M.E., and G.W. Suter. 1994. Toxicological Benchmarks for Screening Potential Contaminants of Concern for Effects on Terrestrial Plants: 1994 Revision. Oak Ridge National Laboratory.

TABLE A-c
ANALYTICAL RESULTS FOR AQUEOUS WASTE SAMPLES
NWS EARLE, COLTS NECK, NEW JERSEY

SAMPLE NUMBER:	20AQW-01	26AQWCT	---	---	---	---	---	---	---
LOCATION:	20AQW-01	26AQWCT	---	---	---	---	---	---	---
DATA SOURCE:	1995 RI	1995 RI, Dec.							
SEMIVOLATILES	ug/L	ug/L							
2,2'-oxybis(1-chloropropane)	10.0	U							
2,4,5-trichlorophenol	25.0	U							
2,4,6-trichlorophenol	10.0	U							
2,4-dichlorophenol	6.0	J							
2,4-dimethylphenol	10.0	U							
2,4-dinitrophenol	25.0	U							
2,4-dinitrotoluene	10.0	U							
2,6-dinitrotoluene	10.0	U							
2-chloronaphthalene	10.0	U							
2-chlorophenol	10.0	U							
2-methylnaphthalene	10.0	U							
2-methylphenol	2.0	J							
2-nitroaniline	25.0	U							
2-nitrophenol	10.0	U							
3,3'-dichlorobenzidine	10.0	U							
3-nitroaniline	25.0	U							
4,6-dinitro-2-methylphenol	25.0	U							
4-bromophenyl-phenylether	10.0	U							
4-chloro-3-methylphenol	10.0	U							
4-chloroaniline	10.0	U							
4-chlorophenyl-phenylether	10.0	U							
4-methylphenol	160								
4-nitroaniline	25.0	U							
4-nitrophenol	25.0	U							
N-nitroso-di-n-propylamine	10.0	U							
N-nitrosodiphenylamine (1)	10.0	U							
acenaphthene	10.0	U							
acenaphthylene	10.0	U							

03/21/96

TABLE A-c

ANALYTICAL RESULTS FOR AQUEOUS WASTE SAMPLES
NWS EARLE, COLTS NECK, NEW JERSEY

DRAFT

Page 3

SAMPLE NUMBER:	20AQW-01	26AQWCT	---	---	---	---	---	---	---
LOCATION:	20AQW-01	26AQWCT	---	---	---	---	---	---	---
DATA SOURCE:	1995 RI	1995 RI, Dec.							
SEMIVOLATILES	ug/L	ug/L							
anthracene	10.0	U							
benzo(a)anthracene	10.0	U							
benzo(a)pyrene	10.0	U							
benzo(b)fluoranthene	10.0	U							
benzo(g,h,i)perylene	10.0	U							
benzo(k)fluoranthene	10.0	U							
bis(2-chloroethoxy)methane	10.0	U							
bis(2-chloroethyl)ether	10.0	U							
bis(2-ethylhexyl)phthalate	10.0	U							
butylbenzylphthalate	10.0	U							
carbazole	10.0	U							
chrysene	10.0	U							
di-n-butylphthalate	10.0	U							
di-n-octylphthalate	10.0	U							
dibenz(a,h)anthracene	10.0	U							
dibenzofuran	10.0	U							
diethylphthalate	10.0	U							
dimethylphthalate	10.0	U							
fluoranthene	10.0	U							
fluorene	10.0	U							
hexachlorobenzene	10.0	U							
hexachlorobutadiene	10.0	U							
hexachlorocyclopentadiene	10.0	U							
hexachloroethane	10.0	U							
indeno(1,2,3-cd)pyrene	10.0	U							
isophorone	10.0	U							
naphthalene	10.0	U							
nitrobenzene	10.0	U							

ANALYTICAL RESULTS FOR AQUEOUS WASTE SAMPLES

NWS EARLE, COLTS NECK, NEW JERSEY

SAMPLE NUMBER:	20AQW-01	26AQWCT	---	---	---	---	---	---	---
LOCATION:	20AQW-01	26AQWCT	---	---	---	---	---	---	---
DATA SOURCE:	1995 RI	1995 RI, Dec.							
SEMIVOLATILES	ug/L	ug/L							
pentachlorophenol	25.0 U								
phenanthrene	10.0 U								
phenol	75.0								
pyrene	10.0 U								
VOLATILES	ug/L	ug/L							
1,1,1-trichloroethane	10.0 U	10.0 U							
1,1,2,2-tetrachloroethane	10.0 U	10.0 U							
1,1,2-trichloroethane	10.0 U	10.0 U							
1,1-dichloroethane	10.0 U	10.0 U							
1,1-dichloroethene	10.0 U	10.0 U							
1,2-dichloroethane	10.0 U	10.0 U							
1,2-dichloroethene (total)	10.0 U	990							
1,2-dichloropropane	10.0 U	10.0 U							
2-butanone	10.0 U	10.0 U							
2-hexanone	10.0 UJ	10.0 U							
4-methyl-2-pentanone	10.0 U	10.0 U							
acetone	14.0 UJ	10.0 U							
benzene	10.0 U	10.0 U							
bromodichloromethane	10.0 U	10.0 U							
bromoform	10.0 U	10.0 U							
bromomethane	10.0 U	10.0 U							
carbon disulfide	2.0 J	10.0 U							
carbon tetrachloride	10.0 U	10.0 U							
chlorobenzene	1.0 J	10.0 U							
chloroethane	10.0 U	10.0 U							
chloroform	5.0 J	10.0 U							
chloromethane	10.0 U	10.0 U							
cis-1,3-dichloropropene	10.0 U	10.0 U							

03/21/96

TABLE A-c
ANALYTICAL RESULTS FOR AQUEOUS WASTE SAMPLES
NWS EARLE, COLTS NECK, NEW JERSEY

DRAFT
Page 5

SAMPLE NUMBER:	20AQW-01	26AQWCT	---	---	---	---	---	---	---
LOCATION:	20AQW-01	26AQWCT	---	---	---	---	---	---	---
DATA SOURCE:	1995 RI	1995 RI, Dec.	---	---	---	---	---	---	---
VOLATILES	ug/L	ug/L							
dibromochloromethane	10.0 U	10.0 U							
ethylbenzene	10.0 U	10.0 U							
methylene chloride	10.0 U	3.0 J							
styrene	10.0 U	10.0 U							
tetrachloroethene	10.0 U	10.0 U							
toluene	38.0	10.0 U							
trans-1,3-dichloropropene	10.0 U	10.0 U							
trichloroethene	10.0 U	780							
vinyl chloride	10.0 U	10.0 U							
xylene (total)	10.0 U	10.0 U							

TABLE 12
REPRESENTATIVE CONCENTRATION AND STATISTICAL DISTRIBUTION OF COPCS
SURFACE SOIL - SITE 20
NWS EARLE, COLTS NECK, NEW JERSEY

CHEMICAL OF CONCERN	REPRESENTATIVE CONCENTRATION (mg/kg)	STATISTICAL DISTRIBUTION
ARSENIC	5.4	NONPARAMETRIC
BARIUM	58	NONPARAMETRIC
BERYLLIUM	2.7	NONPARAMETRIC
CADMIUM	0.26	NONPARAMETRIC
CHROMIUM	97.1	NONPARAMETRIC
COBALT	18.40	NONPARAMETRIC
COPPER	300.24	NORMAL
IRON	16500	NONPARAMETRIC
LEAD	252	NONPARAMETRIC
NICKEL	7.4	NORMAL
SELENIUM	1.4	LOGNORMAL
SILVER	0.83	NORMAL
ZINC	972	NONPARAMETRIC
ANTHRACENE*	63.5	LOGNORMAL
BENZO(A)ANTHRACENE*	500	NONPARAMETRIC
BENZO(A)PYRENE*	261.42	NORMAL
BENZO(B)FLUORANTHENE*	374.14	NORMAL
BENZO(G,H,I)PERYLENE*	211.47	NORMAL
BENZO(K)FLUORANTHENE*	193.86	NONPARAMETRIC
BUTYLBENZYLPHTHALATE*	66	LOGNORMAL
CARBAZOLE*	54	LOGNORMAL
CHRYSENE*	490	NONPARAMETRIC
DIBENZOFURAN*	45	LOGNORMAL
FLUORANTHENE*	525.57	NORMAL
INDENO(1,2,3-CD)PYRENE*	217.69	NORMAL
PHENANTHRENE*	520	NONPARAMETRIC
PYRENE*	562.13	NORMAL

* - UNITS FOR ORGANIC CHEMICALS ARE IN ug/kg

TABLE 13
REPRESENTATIVE CONCENTRATION AND STATISTICAL DISTRIBUTION OF COPCS
SUBSURFACE SOIL - SITE 20
NWS EARLE, COLTS NECK, NEW JERSEY

CHEMICAL OF CONCERN	REPRESENTATIVE CONCENTRATION (mg/kg)	STATISTICAL DISTRIBUTION
ARSENIC	5.1	NONPARAMETRIC
BARIUM	47.5	NONPARAMETRIC
CHROMIUM	11.1	NONPARAMETRIC
LEAD	14	NONPARAMETRIC
SELENIUM	1.4	NONPARAMETRIC
1,2-DICHLOROETHENE (TOTAL)*	15	NONPARAMETRIC
2-BUTANONE*	71	NONPARAMETRIC
4-METHYLPHENOL*	72	NONPARAMETRIC
ETHYLBENZENE*	5	NONPARAMETRIC
TOLUENE*	13	NONPARAMETRIC

* - UNITS FOR ORGANIC CHEMICALS ARE IN ug/kg

TABLE 14
REPRESENTATIVE CONCENTRATION AND STATISTICAL DISTRIBUTION OF COPCS
SEDIMENT - SITE 20
NWS EARLE, COLTS NECK, NEW JERSEY

CHEMICAL OF CONCERN	REPRESENTATIVE CONCENTRATION (mg/kg)	STATISTICAL DISTRIBUTION
ARSENIC	2.6	NONPARAMETRIC
BARIUM	12.3	NONPARAMETRIC
BERYLLIUM	0.1	NONPARAMETRIC
CADMIUM	0.14	NONPARAMETRIC
LEAD	9.2	NONPARAMETRIC
MANGANESE	9.9	NONPARAMETRIC
BENZO(A)ANTHRACENE*	90	NONPARAMETRIC
BENZO(A)PYRENE*	100	NONPARAMETRIC
BENZO(B)FLUORANTHENE*	160	NONPARAMETRIC
BENZO(G,H,I)PERYLENE*	54	NONPARAMETRIC
BENZO(K)FLUORANTHENE*	50	NONPARAMETRIC
CHRYSENE*	130	NONPARAMETRIC
FLUORANTHENE*	150	NONPARAMETRIC
PHENANTHRENE*	120	NONPARAMETRIC
PYRENE*	230	NONPARAMETRIC

* - UNITS FOR ORGANIC CHEMICALS ARE IN ug/kg

TABLE 15

**RME CARCINOGENIC RISK TO CURRENT INDUSTRIAL RECEPTORS - SITE 20
SURFACE SOIL, AMENDED RISK
NWS EARLE, COLTS NECK, NEW JERSEY**

SUBSTANCE	SURFACE SOIL INGESTION	SURFACE SOIL DERMAL CONTACT	INHALATION OF COPCS IN FUGITIVE DUST
ANTHRACENE	N/A	N/A	N/A
BENZO(A)ANTHRACENE	1.3E-07	N/A	2.8E-11
BENZO(A)PYRENE	6.7E-07	N/A	1.4E-10
BENZO(B)FLUORANTHENE	9.5E-08	N/A	2.1E-11
BENZO(G,H,I)PERYLENE	N/A	N/A	N/A
BENZO(K)FLUORANTHENE	4.9E-09	N/A	1.1E-12
BUTYLBENZYLPHthalate	N/A	N/A	N/A
CARBAZOLE	3.8E-10	N/A	7.0E-14
CHRYSENE	1.3E-09	N/A	2.7E-13
DIBENZOFURAN	N/A	N/A	N/A
FLUORANTHENE	N/A	N/A	N/A
INDENO(1,2,3-CD)PYRENE	5.6E-08	N/A	1.2E-11
PHENANTHRENE	N/A	N/A	N/A
PYRENE	N/A	N/A	N/A
ARSENIC	7.5E-06	7.4E-06	4.2E-09
BARIUM	N/A	N/A	N/A
BERYLLIUM	4.2E-07	N/A	7.8E-11
COBALT	N/A	N/A	N/A
COPPER	N/A	N/A	N/A
LEAD	N/A	N/A	N/A
ZINC	N/A	N/A	N/A
TOTAL RISK	8.9E-06	7.4E-06	4.5E-09

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL
* CANCER RISK FOR PAHS NOT ESTIMATED FOR DERMAL EXPOSURE

TABLE 16
RME NONCARCINOGENIC HQS, CURRENT INDUSTRIAL RECEPTORS - SITE 20
SURFACE SOIL, AMENDED RISK
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SURFACE SOIL INGESTION	SURFACE SOIL DERMAL CONTACT	INHALATION OF COPCS IN FUGITIVE DUST
ANTHRACENE	2.1E-07	N/A	3.8E-11
BENZO(A)ANTHRACENE	N/A	N/A	N/A
BENZO(A)PYRENE	N/A	N/A	N/A
BENZO(B)FLUORANTHENE	N/A	N/A	N/A
BENZO(G,H,I)PERYLENE	N/A	N/A	N/A
BENZO(K)FLUORANTHENE	N/A	N/A	N/A
BUTYLBENZYLPHTHALATE	3.2E-07	N/A	6.0E-11
CARBAZOLE	N/A	N/A	N/A
CHRYSENE	N/A	N/A	N/A
DIBENZOFURAN	1.1E-05	N/A	2.0E-09
FLUORANTHENE	1.3E-05	N/A	2.4E-09
INDENO(1,2,3-CD)PYRENE	N/A	N/A	N/A
PHENANTHRENE	N/A	N/A	N/A
PYRENE	1.8E-05	N/A	3.4E-09
ARSENIC	4.7E-02	4.6E-02	8.7E-06
BARIUM	4.3E-04	N/A	7.9E-06
BERYLLIUM	5.5E-05	N/A	1.0E-08
COBALT	7.0E-05	N/A	1.3E-08
COPPER	2.1E-04	N/A	3.8E-08
LEAD	N/A	N/A	N/A
ZINC	9.0E-05	N/A	1.7E-08

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 17
RME CARCINOGENIC RISK TO FUTURE INDUSTRIAL RECEPTORS - SITE 20
SUBSURFACE SOIL
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SUBSURFACE SOIL INGESTION	SUBSURFACE SOIL DERMAL CONTACT	INHALATION OF COPCS IN FUGITIVE DUST
1,2-DICHLOROETHENE (TOTAL)	N/A	N/A	N/A
2-BUTANONE	N/A	N/A	N/A
4-METHYLPHENOL	N/A	N/A	N/A
ETHYLBENZENE	N/A	N/A	N/A
TOLUENE	N/A	N/A	N/A
ARSENIC	2.7E-06	8.8E-07	1.5E-09
BARIUM	N/A	N/A	N/A
CHROMIUM	N/A	N/A	6.0E-09
LEAD	N/A	N/A	N/A
SELENIUM	N/A	N/A	N/A
TOTAL RISK	2.7E-06	8.8E-07	7.5E-09

* CANCER RISK FOR PAHS NOT ESTIMATED FOR DERMAL EXPOSURE

TABLE 18

RME NONCARCINOGENIC HQS, FUTURE INDUSTRIAL RECEPTORS - SITE 20

SUBSURFACE SOIL

NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SUBSURFACE SOIL INGESTION	SUBSURFACE SOIL DERMAL CONTACT	INHALATION OF COPCS IN FUGITIVE DUST
1,2-DICHLOROETHENE (TOTAL)	1.6E-06	5.1E-06	3.0E-10
2-BUTANONE	1.2E-07	3.6E-07	3.0E-11
4-METHYLPHENOL	1.4E-05	7.3E-05	2.6E-09
ETHYLBENZENE	4.9E-08	1.9E-07	9.7E-12
TOLUENE	6.4E-08	2.0E-07	1.6E-11
ARSENIC	1.7E-02	5.5E-03	3.1E-06
BARIIUM	6.6E-04	5.2E-03	1.2E-05
CHROMIUM	2.2E-03	3.4E-02	4.0E-07
LEAD	N/A	N/A	N/A
SELENIUM	2.7E-04	1.1E-04	5.1E-08

TABLE 19
RME CARCINOGENIC RISK TO FUTURE RESIDENTIAL RECEPTORS - SITE 20
SURFACE SOIL, AMENDED RISK
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SURFACE SOIL INGESTION - LIFETIME	SURFACE SOIL DERMAL CONTACT - LIFETIME	INHALATION OF COPCS IN FUGITIVE DUST - LIFETIME
ANTHRACENE	N/A	N/A	N/A
BENZO(A)ANTHRACENE	5.7E-07	N/A	1.7E-11
BENZO(A)PYRENE	3.0E-06	N/A	8.9E-11
BENZO(B)FLUORANTHENE	4.3E-07	N/A	1.3E-11
BENZO(G,H,I)PERYLENE	N/A	N/A	N/A
BENZO(K)FLUORANTHENE	2.2E-08	N/A	6.6E-13
BUTYLBENZYLPHTHALATE	N/A	N/A	N/A
CARBAZOLE	1.7E-09	N/A	4.3E-14
CHRYSENE	5.6E-09	N/A	1.7E-13
DIBENZOFURAN	N/A	N/A	N/A
FLUORANTHENE	N/A	N/A	N/A
INDENO(1,2,3-CD)PYRENE	2.5E-07	N/A	7.4E-12
PHENANTHRENE	N/A	N/A	N/A
PYRENE	N/A	N/A	N/A
ARSENIC	3.4E-05	2.5E-05	2.6E-09
BARIUM	N/A	N/A	N/A
BERYLLIUM	1.9E-06	N/A	4.8E-11
COBALT	N/A	N/A	N/A
COPPER	N/A	N/A	N/A
LEAD	N/A	N/A	N/A
ZINC	N/A	N/A	N/A
TOTAL RISK	4.0E-05	2.5E-05	2.8E-09

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

* CANCER RISK FOR PAHS NOT ESTIMATED FOR DERMAL EXPOSURE

TABLE 20
RME NONCARCINOGENIC HQS, FUTURE RESIDENTIAL RECEPTORS - SITE 20
SURFACE SOIL, AMENDED RISK
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SURFACE SOIL INGESTION - CHILD	SURFACE SOIL INGESTION BY TARGET ORGAN								
		CARDIO- VASCULAR SYSTEM	SKIN	KIDNEY	LIVER	DIGESTIVE SYSTEM	CENTRAL NERVOUS SYSTEM	SKELETAL MUSCLE	REPRO- DUCTIVE SYSTEM	THYROID
ANTHRACENE	2.7E-06									
BENZO(A)ANTHRACENE	N/A									
BENZO(A)PYRENE	N/A									
BENZO(B)FLUORANTHENE	N/A									
BENZO(G,H,I)PERYLENE	N/A									
BENZO(K)FLUORANTHENE	N/A									
BUTYLBENZYLPHTHALATE	4.2E-06									
CARBAZOLE	N/A									
CHRYSENE	N/A									
DIBENZOFURAN	1.4E-04									
FLUORANTHENE	1.7E-04	1.7E-04		1.7E-04	1.7E-04					
INDENO(1,2,3-CD)PYRENE	N/A									
PHENANTHRENE	N/A									
PYRENE	2.4E-04			2.4E-04						
ARSENIC	6.1E-01		6.1E-01							
BARIUM	5.7E-03	5.7E-03				5.7E-03		5.7E-03	5.7E-03	
BERYLLIUM	7.2E-04									
COBALT	9.1E-04	9.1E-04								9.1E-04
COPPER	2.7E-03	2.7E-03		2.7E-03	2.7E-03					
LEAD	N/A	N/A					N/A			
ZINC	1.2E-03	1.2E-03								
	HI BY TARGET ORGAN	1.1E-02	6.1E-01	3.1E-03	2.9E-03	5.7E-03		6.7E-03	5.7E-03	9.1E-04

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 20

**RME NONCARCIN GENIC HQS, FUTURE RESIDENTIAL RECEPTORS - SITE 20
SURFACE SOIL, AMENDED RISK
NWS EARLE, COLTS NECK, NEW JERSEY**

SUBSTANCE	SURFACE SOIL DERMAL CONTACT - CHILD	INHALATION OF COPCS IN FUGITIVE DUST - CHILD
ANTHRACENE	N/A	4.1E-11
BENZO(A)ANTHRACENE	N/A	N/A
BENZO(A)PYRENE	N/A	N/A
BENZO(B)FLUORANTHENE	N/A	N/A
BENZO(G,H,I)PERYLENE	N/A	N/A
BENZO(K)FLUORANTHENE	N/A	N/A
BUTYLBENZYLPHTHALATE	N/A	6.3E-11
CARBAZOLE	N/A	N/A
CHRYSENE	N/A	N/A
DIBENZOFURAN	N/A	2.2E-09
FLUORANTHENE	N/A	2.5E-09
INDENO(1,2,3-CD)PYRENE	N/A	N/A
PHENANTHRENE	N/A	N/A
PYRENE	N/A	3.6E-09
ARSENIC	3.8E-01	9.2E-06
BARIUM	N/A	8.4E-06
BERYLLIUM	N/A	1.1E-08
COBALT	N/A	1.4E-08
COPPER	N/A	4.0E-08
LEAD	N/A	N/A
ZINC	N/A	1.8E-08

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 21

RME CARCINOGENIC RISK TO FUTURE RESIDENTIAL RECEPTORS - SITE 20
SUBSURFACE SOIL
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SUBSURFACE SOIL INGESTION - LIFETIME	SUBSURFACE SOIL DERMAL CONTACT - LIFETIME	INHALATION OF COPCS IN FUGITIVE DUST - LIFETIME
1,2-DICHLOROETHENE (TOTAL)	N/A	N/A	N/A
2-BUTANONE	N/A	N/A	N/A
4-METHYLPHENOL	N/A	N/A	N/A
ETHYLBENZENE	N/A	N/A	N/A
TOLUENE	N/A	N/A	N/A
ARSENIC	1.2E-05	2.9E-06	9.2E-10
BARIUM	N/A	N/A	N/A
CHROMIUM	N/A	N/A	3.7E-09
LEAD	N/A	N/A	N/A
SELENIUM	N/A	N/A	N/A
TOTAL RISK	1.2E-05	2.9E-06	4.6E-09

N/A = NOT APPLICABLE, NO TOXICITY VALUES ARE ESTABLISHED FOR THIS CHEMICAL

* CANCER RISK FOR PAHS NOT ESTIMATED FOR DERMAL EXPOSURE

TABLE 22

RME NONCARCINOGENIC HQS, FUTURE RESIDENTIAL RECEPTORS - SITE 20
SUBSURFACE SOIL
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SUBSURFACE SOIL INGESTION - LIFETIME	SUBSURFACE SOIL DERMAL CONTACT - LIFETIME	INHALATION OF COPCS IN FUGITIVE DUST - LIFETIME
1,2-DICHLOROETHENE (TOTAL)	2.1E-05	4.2E-05	3.2E-10
2-BUTANONE	1.5E-06	3.0E-06	3.2E-11
4-METHYLPHENOL	1.8E-04	6.0E-04	2.8E-09
ETHYLBENZENE	6.4E-07	1.6E-06	1.0E-11
TOLUENE	8.3E-07	1.6E-06	1.7E-11
ARSENIC	2.2E-01	4.5E-02	3.3E-06
BARIUM	8.7E-03	4.2E-02	1.3E-05
CHROMIUM	2.8E-02	2.8E-01	4.2E-07
LEAD	N/A	N/A	N/A
SELENIUM	3.6E-03	8.7E-04	5.4E-08

TABLE 23

RME CARCINOGENIC RISK, WADING, FUTURE RECREATIONAL RECEPTORS - SITE 20
SEDIMENT
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SEDIMENT INGESTION	SEDIMENT DERMAL CONTACT
BENZO(A)ANTHRACENE	7.2E-10	2.9E-10
BENZO(A)PYRENE	8.0E-09	1.1E-08
BENZO(B)FLUORANTHENE	1.3E-09	5.1E-10
BENZO(G,H,I)PERYLENE	N/A	N/A
BENZO(K)FLUORANTHENE	4.0E-11	1.6E-11
CHRYSENE	1.0E-11	4.1E-12
FLUORANTHENE	N/A	N/A
PHENANTHRENE	N/A	N/A
PYRENE	N/A	N/A
ARSENIC	4.3E-08	1.8E-09
BARIUM	N/A	N/A
BERYLLIUM	4.7E-09	1.9E-08
CADMIUM	N/A	N/A
LEAD	N/A	N/A
MANGANESE	N/A	N/A
TOTAL RISK	5.8E-08	3.2E-08

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL
* CANCER RISK FOR PAHS NOT ESTIMATED FOR DERMAL EXPOSURE

TABLE 24

RME NONCARCINOGENIC HQS, WADING, FUTURE RECREATIONAL RECEPTORS - SITE 20
SEDIMENT
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SEDIMENT INGESTION	SEDIMENT DERMAL CONTACT
BENZO(A)ANTHRACENE	NA	NA
BENZO(A)PYRENE	NA	NA
BENZO(B)FLUORANTHENE	NA	NA
BENZO(G,H,I)PERYLENE	NA	NA
BENZO(K)FLUORANTHENE	NA	NA
CHRYSENE	NA	NA
FLUORANTHENE	4.8E-07	1.9E-07
PHENANTHRENE	NA	NA
PYRENE	9.8E-07	3.9E-07
ARSENIC	1.1E-03	4.6E-05
BARIUM	2.2E-05	2.2E-05
BERYLLIUM	2.6E-06	1.0E-05
CADMIUM	3.6E-05	2.8E-05
LEAD	NA	NA
MANGANESE	2.5E-04	3.3E-04

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 25

**SUMMARY OF ESTIMATED RME CANCER RISKS AND NONCARCINOGENIC HAZARD INDICIES - SITE 20
NWS EARLE, COLTS NECK, NEW JERSEY**

Medium	Exposure Routes	Estimated Incremental Cancer Risk					Estimated Hazard Index**					
		Current Industrial Employee	Future Industrial Employee	Future Lifetime Resident	Future Lifetime Resident	Future Recreational Child	Current Industrial Employee	Future Industrial Employee	Future Resident			Future Recreational Child
									Child	Child	Adult	
Surface Soil	Incidental Ingestion	8.9E-06^	N/A	N/S	4.0E-05^	N/A	4.8E-02^	N/A	N/S	6.1E-01@	N/A	N/A
	Dermal Contact	7.4E-06^	N/A	N/S	2.5E-05^	N/A	4.6E-02^	N/A	N/S	3.8E-01^	N/A	N/A
	Inhalation of Fugitive Dust	4.5E-09^	N/A	N/S	2.8E-09^	N/A	1.7E-05^	N/A	N/S	1.8E-05^	N/A	N/A
Subsurface Soil	Incidental Ingestion	N/A	2.7E-06	1.2E-05	N/S	N/A	N/A	2.0E-02	2.6E-01	N/S	N/A	N/A
	Dermal Contact	N/A	8.8E-07	2.9E-06	N/S	N/A	N/A	4.5E-02	3.7E-01	N/S	N/A	N/A
	Inhalation of Fugitive Dust	N/A	7.5E-09	4.6E-09	N/S	N/A	N/A	1.6E-05	1.7E-05	N/S	N/A	N/A
Sediment	Incidental Ingestion	N/A	N/A	N/A	N/A	5.8E-08	N/A	N/A	N/A	N/A	N/A	1.4E-03
	Dermal Contact	N/A	N/A	N/A	N/A	3.2E-08	N/A	N/A	N/A	N/A	N/A	4.4E-04
Groundwater	Ingestion	N/A	N/S	N/S	N/S	N/A	N/A	N/S	N/S	N/S	N/A	N/A
	Dermal Contact	N/A	N/S	N/S	N/S	N/A	N/A	N/S	N/S	N/S	N/A	N/A
	Inhalation of Volatiles*	N/A	N/S	N/S	N/S	N/A	N/A	N/S	N/S	N/S	N/A	N/A
Surface Water	Incidental Ingestion	N/A	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/A	N/S
	Dermal Contact	N/A	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/A	N/S
TOTAL		1.6E-05	3.6E-06	1.5E-05	6.5E-05	9.0E-08	9.4E-02	6.5E-02	6.3E-01	9.89E-01	-	1.9E-03

N/A = Not applicable because this media is not associated with this potential receptor

N/S = Not sampled

* = During Showering, Adult Residents Only

** = Hazard Indices (i.e., summation of hazard quotients) are used only for comparison purposes and do not reflect actual additive noncarcinogenic effects

^ - Value from amended risk assessment.

@ - Amended result is maximum HI for individual target organs.

TABLE 26

**OCCURRENCE AND DISTRIBUTION OF INORGANICS IN SUBSURFACE SOIL AT SITE 22
NWS EARLE, COLTS NECK, NEW JERSEY
(mg/kg)**

SUBSTANCE	BACKGROUND			SITE-RELATED				
	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	2 X AVERAGE BKGD CONCENTRATION	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	AVERAGE CONCENTRATION	MEAN > 2 X BKGD?	REPRESENTATIVE CONCENTRATION
ALUMINUM*	8 / 8	675 - 5310	5370.00	3 / 3	1370 - 4350	2930.00	NO	4350
ARSENIC	8 / 8	1.35 - 14.4	13.29	3 / 3	1.9 - 3.3	2.63	NO	3.3
BARIUM*	8 / 8	0.92 - 31	17.92	3 / 3	5.3 - 9.6	7.37	NO	9.6
BERYLLIUM*	2 / 8	0.12 - 0.28	0.28	3 / 3	0.22 - 0.45	0.32	YES	0.45
CALCIUM	8 / 8	28.6 - 799	577.55	3 / 3	9.7 - 55.2	34.77	NO	55.20
CHROMIUM*	8 / 8	4.7 - 59.5	54.73	3 / 3	17.1 - 48.2	37.37	NO	48.2
COPPER	8 / 8	0.97 - 8.6	8.66	3 / 3	2.5 - 17.2	8.13	YES	17.20
IRON*	8 / 8	3745 - 62500	40871.25	3 / 3	5520 - 9480	7780.00	NO	9480
LEAD*	8 / 8	1.4 - 39.4	24.33	3 / 3	6.3 - 29.8	14.70	NO	29.80
MAGNESIUM	8 / 8	18.5 - 619	504.05	3 / 3	131 - 661	414.67	NO	661
MANGANESE*	8 / 8	2.6 - 214	92.51	3 / 3	5 - 11.2	7.40	NO	11
NICKEL	4 / 8	1.8 - 7.2	4.75	1 / 3	2.8	1.22	NO	2.8
POTASSIUM	7 / 8	95 - 792	793.35	3 / 3	530 - 2270	1503.33	YES	2270
SELENIUM*	2 / 8	0.57 - 0.93	0.79	1 / 3	0.35	0.22	NO	0.35
SODIUM	8 / 8	17.5 - 94.8	79.35	3 / 3	21.7 - 97.4	50.30	NO	97
VANADIUM*	8 / 8	11.05 - 64	64.71	3 / 3	12.6 - 36.1	24.83	NO	36.10
ZINC	6 / 8	1.1 - 50.7	31.35	3 / 3	5.3 - 33.3	14.733333	NO	33.30

Note: Selected COPCs are indicated in boldface type.
* - Indicates COPCs eliminated based on amended risk assessment.

TABLE 27
OCCURRENCE AND DISTRIBUTION OF ORGANICS IN SUBSURFACE SOIL AT SITE 22
NWS EARLE, COLTS NECK, NEW JERSEY
 (ug/kg)

SUBSTANCE	BACKGROUND			SITE-RELATED		
	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	REPRESENTATIVE CONCENTRATION	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	REPRESENTATIVE CONCENTRATION
1,1,1-TRICHLOROETHANE	NOT DETECTED	-	-	1 / 3	2	2
4,4'-DDT	NOT DETECTED	-	-	2 / 3	4 - 5.2	5
ANTHRACENE	NOT DETECTED	-	-	1 / 2	82	82
BENZO(A)ANTHRACENE	NOT DETECTED	-	-	1 / 2	172	172
BENZO(A)PYRENE	NOT DETECTED	-	-	1 / 2	210	210
BENZO(B)FLUORANTHENE	NOT DETECTED	-	-	1 / 2	161	161
BENZO(G,H,I)PERYLENE	NOT DETECTED	-	-	1 / 2	100	100
BENZO(K)FLUORANTHENE	NOT DETECTED	-	-	1 / 2	130	130
BIS(2-ETHYLHEXYL)PHTHALAT	NOT DETECTED	-	-	1 / 2	97	97
CHRYSENE	NOT DETECTED	-	-	1 / 2	171.5	172
DI-N-BUTYLPHTHALATE	3 / 3	48 - 48	48	2 / 2	60 - 71	71
FLUORANTHENE	NOT DETECTED	-	-	1 / 2	580	580
INDENO(1,2,3-CD)PYRENE	NOT DETECTED	-	-	1 / 2	97	97
PHENANTHRENE	NOT DETECTED	-	-	1 / 2	155.5	155.50
PYRENE	NOT DETECTED	-	-	1 / 2	570	570

06/17/96

TABLE 28

COMPARISON OF SUBSURFACE SOIL ANALYTICAL DATA TO ARARS AND TBCs - SITE 22
NWS EARLE, COLTS NECK, NEW JERSEY

FINAL
Page 1

SAMPLE NUMBER: LOCATION: DATA SOURCE:	22-007-S001	22-007-S002	22-008-S001	22-008-S001-DU	22-008-S002	22-009-S001	ARARS & TBCs		
	22-007-S001	22-007-S002	22-008-S001	22-008-S001	22-008-S002	22-009-S001	NJDEP Soil Residential Direct Contact Cleanup Criteria	NJDEP Soil Non-Residential Direct Contact Cleanup Criteria	NJDEP Soil Impact to Groundwater Cleanup Criteria
	1992 RI/FS	1992 RI/FS	1992 RI/FS	1992 RI/FS	1992 RI/FS	1992 RI/FS			
INORGANICS	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
aluminum	1370	n/a	3070	n/a	n/a	4350	-	-	-
arsenic	3.3	n/a	2.7	n/a	n/a	1.9	20.0	20.0	-
barium	7.2	n/a	5.3	n/a	n/a	9.6	700	47000	-
beryllium	0.22	n/a	0.45	n/a	n/a	0.30	1.00	1.00	-
calcium	55.2	n/a	39.4	n/a	n/a	9.7	-	-	-
chromium, total	17.1	n/a	48.2	n/a	n/a	46.8	-	500	-
copper	4.7	n/a	17.2	n/a	n/a	2.5	600	600	-
iron	8340	n/a	9480	n/a	n/a	5520	-	-	-
lead	29.8	n/a	6.3	n/a	n/a	8.0	400	600	-
magnesium	131	n/a	661	n/a	n/a	452	-	-	-
manganese	11.2	n/a	6.0	n/a	n/a	5.0	-	-	-
nickel	0.80 U	n/a	2.8	n/a	n/a	0.89 U	250	2400	-
potassium	530	n/a	2270	n/a	n/a	1710	-	-	-
selenium	0.31 U	n/a	0.30 U	n/a	n/a	0.35	63.0	3100	-
sodium	97.4	n/a	31.8	n/a	n/a	21.7	-	-	-
vanadium	12.6	n/a	36.1	n/a	n/a	25.8	370	7100	-
zinc	5.6	n/a	33.3	n/a	n/a	5.3	1500	1500	-
SEMIVOLATILES	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
anthracene	440 U	n/a	82.0 J	440 U	n/a	480 U	10000000	10000000	100000
benzo(a)anthracene	440 U	n/a	280 J	64.0 J	n/a	480 U	900	4000	500000
benzo(a)pyrene	440 U	n/a	210 J	440 U	n/a	480 U	660	660	100000
benzo(b)fluoranthene	71.0 J	n/a	260 J	62.0 J	n/a	480 U	900	4000	50000
benzo(g,h,i)perylene	440 U	n/a	100 J	440 U	n/a	480 U	-	-	-
benzo(k)fluoranthene	52.0 J	n/a	200 J	60.0 J	n/a	480 U	900	4000	500000
benzoic acid	2200 U	n/a	54.0 J	2200 U	n/a	2400 U	-	-	-
bis(2-ethylhexyl)phthalate	440 U	n/a	450 U	97.0 J	n/a	480 U	49000	210000	100000
chrysene	440 U	n/a	270 J	73.0 J	n/a	480 U	9000	40000	500000
di-n-butylphthalate	58.0 J	n/a	450 U	71.0 J	n/a	60.0 J	5700000	10000000	100000

TABLE 28

COMPARISON OF SUBSURFACE SOIL ANALYTICAL DATA TO ARARS AND TBCs - SITE 22

NWS EARLE, COLTS NECK, NEW JERSEY

SAMPLE NUMBER:	22-007-S001	22-007-S002	22-008-S001	22-008-S001-DU	22-008-S002	22-009-S001	ARARS & TBCs			
	LOCATION:	22-007-S001	22-007-S002	22-008-S001	22-008-S001	22-008-S002	22-009-S001	NJDEP Soil Residential Direct Contact Cleanup Criteria	NJDEP Soil Non-Residential Direct Contact Cleanup Criteria	NJDEP Soil Impact to Groundwater Cleanup Criteria
DATA SOURCE:	1992 RI/FS	1992 RI/FS	1992 RI/FS	1992 RI/FS	1992 RI/FS	1992 RI/FS	1992 RI/FS			
SEMIVOLATILES	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
fluoranthene	110 J	n/a	580	190 J	n/a	480 U	2300000	10000000	100000	
indeno(1,2,3-cd)pyrene	440 U	n/a	97.0 J	440 U	n/a	480 U	900	4000	500000	
phenanthrene	440 U	n/a	230 J	81.0 J	n/a	480 U				
pyrene	74.0 J	n/a	570	120 J	n/a	480 U	1700000	10000000	100000	
VOLATILES	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	
1,1,1-trichloroethane	n/a	6.0 U	n/a	n/a	6.0 U	n/a	210000	1000000	50000	
PESTICIDES	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	
4,4'-DDT	4.0 J	n/a	20.0 U	19.0 U	n/a	5.2 J	2000	9000	500000	

TABLE 28

COMPARISON OF SUBSURFACE SOIL ANALYTICAL DATA TO ARARS AND TBCs - SITE 22

NWS EARLE, COLTS NECK, NEW JERSEY

SAMPLE NUMBER:	22-009-S002	22-009-S002-DU	---	---	---	---	ARARS & TBCs			
	LOCATION:	22-009-S002	22-009-S002	---	---	---	---	NJDEP Soil Residential Direct Contact Cleanup Criteria	NJDEP Soil Non-Residential Direct Contact Cleanup Criteria	NJDEP Soil Impact to Groundwater Cleanup Criteria
DATA SOURCE:	1992 RI/FS	1992 RI/FS								
INORGANICS	mg/kg	mg/kg					mg/kg	mg/kg	mg/kg	
aluminum	n/a	n/a					-	-	-	
arsenic	n/a	n/a					20.0	20.0	-	
barium	n/a	n/a					700	47000	-	
beryllium	n/a	n/a					1.00	1.00	-	
calcium	n/a	n/a					-	-	-	
chromium, total	n/a	n/a					-	500	-	
copper	n/a	n/a					600	600	-	
iron	n/a	n/a					-	-	-	
lead	n/a	n/a					400	600	-	
magnesium	n/a	n/a					-	-	-	
manganese	n/a	n/a					-	-	-	
nickel	n/a	n/a					250	2400	-	
potassium	n/a	n/a					-	-	-	
selenium	n/a	n/a					63.0	3100	-	
sodium	n/a	n/a					-	-	-	
vanadium	n/a	n/a					370	7100	-	
zinc	n/a	n/a					1500	1500	-	
SEMIVOLATILES	ug/kg	ug/kg					ug/kg	ug/kg	ug/kg	
anthracene	n/a	n/a					10000000	10000000	100000	
benzo(a)anthracene	n/a	n/a					900	4000	500000	
benzo(a)pyrene	n/a	n/a					660	660	100000	
benzo(b)fluoranthene	n/a	n/a					900	4000	50000	
benzo(g,h,i)perylene	n/a	n/a					-	-	-	
benzo(k)fluoranthene	n/a	n/a					900	4000	500000	
benzoic acid	n/a	n/a					-	-	-	
bis(2-ethylhexyl)phthalate	n/a	n/a					49000	210000	100000	
chrysene	n/a	n/a					9000	40000	500000	
di-n-butylphthalate	n/a	n/a					5700000	10000000	100000	

TABLE 28

COMPARISON OF SUBSURFACE SOIL ANALYTICAL DATA TO ARARS AND TBCs - SITE 22

NWS EARLE, COLTS NECK, NEW JERSEY

SAMPLE NUMBER:	22-009-S002	22-009-S002-DU	---	---	---	---	ARARS & TBCs		
							NJDEP Soil Residential Direct Contact Cleanup Criteria	NJDEP Soil Non-Residential Direct Contact Cleanup Criteria	NJDEP Soil Impact to Groundwater Cleanup Criteria
LOCATION:	22-009-S002	22-009-S002	---	---	---	---			
DATA SOURCE:	1992 RI/FS	1992 RI/FS							
SEMIVOLATILES	ug/kg	ug/kg					ug/kg	ug/kg	ug/kg
fluoranthene	n/a	n/a					2300000	10000000	100000
indeno(1,2,3-cd)pyrene	n/a	n/a					900	4000	500000
phenanthrene	n/a	n/a							
pyrene	n/a	n/a					1700000	10000000	100000
VOLATILES	ug/kg	ug/kg					ug/kg	ug/kg	ug/kg
1,1,1-trichloroethane	2.0 J	6.0 U					210000	1000000	50000
PESTICIDES	ug/kg	ug/kg					ug/kg	ug/kg	ug/kg
4,4'-DDT	n/a	n/a					2000	9000	500000

TABLE 28

**COMPARISON OF SUBSURFACE SOIL ANALYTICAL DATA TO ARARS AND TBCS - SITE 22
NWS EARLE, COLTS NECK, NEW JERSEY**

**FINAL
PAGE 5**

Footnotes to sample results:

- U** - Compound or element was not detected. Value is the detection limit (inorganics) or quantitation limit (organics).
- UJ** - Not detected. Detection limit or quantitation limit shown is considered estimated due to exceedance of data validation quality control criteria.
- No Value** - Constituent was not analyzed for in this sample.
- UR** - Nondetected result is considered rejected based on exceedance of data validation quality control criteria.
- J** - Value is estimated because concentration is below the quantitation limit or because of exceedance of data validation quality control criteria.
- R** - Positive result is considered rejected based on exceedance of data validation quality control criteria.
- N** - Compound is considered to be tentatively identified based on exceedance of QC criteria for compound identification.
- E** - Result exceeds one or more of the selected ARARs.

Footnotes to soil criteria:

- No standard is available for this chemical in this classification.

TABLE 29
OCCURRENCE AND DISTRIBUTION OF INORGANICS IN SEDIMENT AT SITE 22
NWS EARLE, COLTS NECK, NEW JERSEY
 (mg/kg)

SUBSTANCE	BACKGROUND			SITE-RELATED				
	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	2 X AVERAGE BKGD CONCENTRATION	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	AVERAGE CONCENTRATION	MEAN > 2 X BKGD	REPRESENTATIVE CONCENTRATION
ALUMINUM	3 / 3	839 - 3940	5492.67	5 / 5	1180 - 3930	2328.00	NO	3930
ARSENIC	2 / 3	2.4 - 6.2	5.95	5 / 5	0.94 - 2.9	2.07	NO	2.9
BARIUM	3 / 3	3.9 - 10.6	14.07	5 / 5	1.1 - 16.5	8.28	NO	16.5
BERYLLIUM	1 / 3	0.57	0.67	5 / 5	0.13 - 0.36	0.24	NO	0.36
CADMIUM	NOT DETECTED	-	-	3 / 5	0.93 - 2.7	1.25	YES	2.70
CALCIUM	3 / 3	179 - 518	685.33	5 / 5	56.6 - 1260	576.33	YES	1260
CHROMIUM	3 / 3	4.3 - 56	43.13	5 / 5	11.6 - 31.8	19.06	NO	31.80
COBALT	1 / 3	2.1	3.30	2 / 5	1.1 - 5.2	1.52	NO	3.50
COPPER	3 / 3	1.5 - 13	12.47	5 / 5	0.77 - 18.3	6.59	NO	18.30
IRON	3 / 3	228 - 7650	6578.67	5 / 5	1505 - 13400	5703.01	NO	13400
LEAD	3 / 3	4.6 - 34.3	30.60	5 / 5	5.957 - 106	37.63	YES	106
MAGNESIUM	3 / 3	60.7 - 256	306.47	5 / 5	171 - 641	378.11	YES	641
MANGANESE	3 / 3	4.6 - 9.2	13.80	5 / 5	2.4 - 155	39.78	YES	101.64
NICKEL	2 / 3	2.1 - 6	7.93	1 / 5	8.6	2.09	NO	5.56
POTASSIUM	2 / 3	86.1 - 681	589.40	5 / 5	342 - 678	522.60	NO	678
SELENIUM	NOT DETECTED	-	-	2 / 5	0.37 - 0.38	0.25	YES	0.36
SODIUM	3 / 3	26.6 - 116	115.27	5 / 5	10.3 - 67.1	38.64	NO	67.10
VANADIUM	3 / 3	5.9 - 42.7	36.93	5 / 5	9.5 - 29	16.50	NO	29
ZINC	3 / 3	14.2 - 26.9	37.33	5 / 5	4 - 119	39.58	YES	119

Note: Selected COPCs are indicated in boldface type.

TABLE 30
OCCURRENCE AND DISTRIBUTION OF ORGANICS IN SEDIMENT AT SITE 22
NWS EARLE, COLTS NECK, NEW JERSEY
 (ug/kg)

SUBSTANCE	BACKGROUND			SITE-RELATED		
	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	REPRESENTATIVE CONCENTRATION	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	REPRESENTATIVE CONCENTRATION
4,4'-DDT	1 / 3	19	19	1 / 2	13	13
ACENAPHTHENE	NOT DETECTED	-	-	1 / 3	300	300
ANTHRACENE	NOT DETECTED	-	-	2 / 3	71 - 880	880
BENZO(A)ANTHRACENE	2 / 3	140 - 560	560	2 / 3	490 - 1800	1800
BENZO(A)PYRENE	2 / 3	160 - 590	590	2 / 3	460 - 970	970
BENZO(B)FLUORANTHENE	2 / 3	150 - 490	490	3 / 3	71 - 1200	1200
BENZO(G,H,I)PERYLENE	2 / 3	130 - 380	380	2 / 3	440 - 830	830
BENZO(K)FLUORANTHENE	2 / 3	150 - 470	470	3 / 3	52 - 1200	1200
BIS(2-ETHYLHEXYL)PHTHALAT	NOT DETECTED	-	-	1 / 3	77	77
CHRYSENE	2 / 3	250 - 940	940	2 / 3	730 - 1700	1700
DI-N-BUTYLPHthalate	NOT DETECTED	-	-	3 / 3	58 - 69	69
DIBENZ(A,H)ANTHRACENE	NOT DETECTED	-	-	2 / 3	64 - 220	220
FLUORANTHENE	2 / 3	300 - 1800	1800	3 / 3	110 - 5000	5000
FLUORENE	1 / 3	190	190	1 / 3	150	150
INDENO(1,2,3-CD)PYRENE	2 / 3	110 - 310	310	2 / 3	390 - 780	780
PHENANTHRENE	2 / 3	200 - 1900	1900	2 / 3	610 - 6300	6300
PYRENE	2 / 3	350 - 1900	1900	3 / 3	74 - 3300	3300

TABLE 31

COMPARISON OF SEDIMENT ANALYTICAL DATA TO ARARS AND TBCs - SITE 22

NWS EARLE, COLTS NECK, NEW JERSEY

SAMPLE NUMBER:	22-001-D001	22-003-D001	22-004-D001	22-005-D001	22-006-D001	22-006-D001-DU	---	ARARS & TBCs Sediment Ecological Toxicity Threshold Values
LOCATION:	22-001-D001	22-003-D001	22-004-D001	22-005-D001	22-006-D001	22-006-D001	---	
DATA SOURCE:	1992 RI/FS							
INORGANICS	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg		mg/kg
aluminum	3930	2220	3010	1300	2360	0.031		-
arsenic	2.9	2.5	2.8	1.2	0.94	18.0	U	8.20 L
barium	16.5	8.0	9.2	1.1	6.6	4.0	U	40.0 B
beryllium	0.26	0.27	0.16	0.13	0.22	0.50		-
cadmium	2.7 E	0.90 U	1.8 E	0.75 U	0.93	0.34	U	1.20 L
calcium	1260	422	671	56.6	944	0.10		-
chromium, total	14.3	31.8	24.0	11.6	13.6	6.3	U	81.0 L
cobalt	5.2	1.1	0.93 U	0.75 U	0.93 U	3.4	U	50.0 T
copper	18.3	4.6	5.3	0.77	4.0	n/a		34.0 L
iron	13400	7090	3970	2550	3010	0.051		-
lead	42.9	106 E	26.9	6.4	11.9	0.014		47.0 L
magnesium	641	558	318	171	405	0.058		-
manganese	155	23.7	9.5	2.4	8.3	0.90	U	460 O
nickel	8.6	0.94 U	1.0 U	0.79 U	1.0 U	3.6	U	21.0 L
potassium	342	678	678	450	465	142	U	-
selenium	0.38	0.34 U	0.37	0.31 U	0.35 U	1.3	U	-
sodium	67.1	36.6	57.6	10.3	42.9	0.26		-
vanadium	21.4	29.0	12.5	9.5	10.1	2.6	U	-
zinc	119	20.9	35.6	4.0	36.8	0.0048		150 L
SEMIVOLATILES	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg		ug/kg
acenaphthene	n/a	500 U	n/a	n/a	300 J	n/a		620 Q
anthracene	n/a	71.0 J	n/a	n/a	880 E	n/a		330 F
benzo(a)anthracene	n/a	490 E J	n/a	n/a	1800 E	n/a		330 F
benzo(a)pyrene	n/a	460 E J	n/a	n/a	970 E	n/a		430 L
benzo(b)fluoranthene	n/a	630 E	n/a	n/a	1200 E	n/a		330 F
benzo(g,h,i)perylene	n/a	440 E J	n/a	n/a	830 E	n/a		330 F
benzo(k)fluoranthene	n/a	550 E	n/a	n/a	1200 E	n/a		330 F
bis(2-ethylhexyl)phthalate	n/a	500 U	n/a	n/a	77.0 J	n/a		89000000 S

TABLE 31

07/15/96

COMPARISON OF SEDIMENT ANALYTICAL DATA TO ARARS AND TBCs - SITE 22

FINAL

Page 2

NWS EARLE, COLTS NECK, NEW JERSEY

SAMPLE NUMBER:	22-001-D001	22-003-D001	22-004-D001	22-005-D001	22-006-D001	22-006-D001-DU	---	ARARS & TBCs
LOCATION:	22-001-D001	22-003-D001	22-004-D001	22-005-D001	22-006-D001	22-006-D001	---	Sediment
DATA SOURCE:	1992 RI/FS		Ecological Toxicity Threshold Values					
SEMIVOLATILES	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg		ug/kg
chrysene	n/a	730 E	n/a	n/a	1700 E	n/a		330 F
di-n-butylphthalate	n/a	69.0 J	n/a	n/a	68.0 J	n/a		11000 P
dibenz(a,h)anthracene	n/a	64.0 J	n/a	n/a	220 J	n/a		330 F
fluoranthene	n/a	1500	n/a	n/a	5000 E	n/a		2900 Q
fluorene	n/a	500 U	n/a	n/a	150 J	n/a		540 P
indeno(1,2,3-cd)pyrene	n/a	390 E J	n/a	n/a	780 E	n/a		330 F
phenanthrene	n/a	610	n/a	n/a	6300 E	n/a		850 Q
pyrene	n/a	1100 E	n/a	n/a	3300 E	n/a		660 L
PESTICIDES	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg		ug/kg
4,4'-DDT	n/a	13.0 E J	n/a	n/a	110 U	n/a		1.60 L

COMPARISON OF SEDIMENT MISCELLANEOUS PARAMETERS DATA TO ARARS AND TBCs - SITE 22

NWS EARLE, COLTS NECK, NEW JERSEY

SAMPLE NUMBER:	22-001-D001	22-002-D001	22-003-D001	22-004-D001	22-005-D001	22-006-D001	---	ARARS & TBCs
LOCATION:	22-001-D001	22-002-D001	22-003-D001	22-004-D001	22-005-D001	22-006-D001	---	Sediment
DATA SOURCE:	1992 RI/FS		Ecological Toxicity Threshold Values					
MISCELLANEOUS	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg		mg/kg
petroleum hydrocarbons	27.0	5.9	12.0	15.0	13.0	48.0		-

TABLE 31

COMPARISON OF SEDIMENT ANALYTICAL DATA TO ARARS AND TBCS - SITE 22 NWS EARLE, COLTS NECK, NEW JERSEY

FINAL
PAGE 3

Footnotes to sample results:

- U - Compound or element was not detected. Value is the detection limit (inorganics) or quantitation limit (organics).
- UJ - Not detected. Detection limit or quantitation limit shown is considered estimated due to exceedance of data validation quality control criteria.
- No Value - Constituent was not analyzed for in this sample.
- UR - Nondetected result is considered rejected based on exceedance of data validation quality control criteria.
- J - Value is estimated because concentration is below the quantitation limit or because of exceedance of data validation quality control criteria.
- R - Positive result is considered rejected based on exceedance of data validation quality control criteria.
- N - Compound is considered to be tentatively identified based on exceedance of QC criteria for compound identification.
- E - Result exceeds one or more of the selected ARARs.

Footnotes to sediment ecological toxicity criteria:

- - No standard is available for this chemical in this classification.
- B - Source: Baudo, R., J. Geisy and H. Muntau. eds. 1990. Sediments: Chemistry and Toxicity of In-Place Pollutants. Lewis Publishers, Inc. Ann Arbor, MI.
- F - Source: USEPA. 1994c. Draft Region IV Waste Management Division Sediment Screening Values for Hazardous Waste Sites. 2/16/94 Revision.
- L - Effects Range-Low. Source: Long E.R., D.D. MacDonald, S.L. Smith, and F.D. Calder. 1995. Incidence of Adverse Biological Effects within Ranges of Chemical Concentrations in Marine and Estuarine Sediments. Environmental Management. 19:81-97.
- M - Effects Range-Low. Source: Long, E. R. and L. G. Morgan. 1991. The Potential for Biological Effects of Sediment-Sorbed Contaminants Tested in the National Status and Trends Program. NOAA Technical Memorandum NOS OMA 52, National Oceanic and Atmospheric Administration, Seattle, WA.
- O - Ontario screening level. Source: Ontario Ministry of the Environment (OME). 1992. Guidelines for the Protection and Management of the Aquatic Sediment Quality in Ontario. Log 92-2309-067, PIBS 1962.
- P - Sediment quality benchmark using equipartition. Source: USEPA. 1996. ECO Update. Volume 3: Number 2. EPA 540/F-95/038.
- Q - Sediment quality criterion. Source: USEPA. 1996. ECO Update. Volume 3: Number 2. EPA 540/F-95/038.
- S - Sediment screening benchmark. Source: Suter, G. W., and J. B. Mabrey. 1994. Toxicological Benchmarks for Screening Potential Contaminants of Concern for Effects on Aquatic Biota. Oak Ridge National Laboratory, Oak Ridge, TN.
- T - Threshold for soils. Source: Direction des Substances Dangereuses. 1988. Contaminated Sites Rehabilitation Policy. Gouvernement du Quebec. Ministere de L'Environnement. Sainte-Foy, Quebec, Canada. In: R.L. Siegrist. 1989. International Review of Approaches for Establishing Cleanup Goals for Hazardous Waste Contaminated Land. Institute for Georesearch and Pollution Research. Norway.
- W - Screening value for wet soil. Source: Will, M.E., and G.W. Suter. 1994. Toxicological Benchmarks for Screening Potential Contaminants of Concern for Effects on Terrestrial Plants: 1994 Revision. Oak Ridge National Laboratory.

TABLE 32
REPRESENTATIVE CONCENTRATION AND STATISTICAL DISTRIBUTION OF COPCS
SUBSURFACE SOIL - SITE 22
NWS EARLE, COLTS NECK, NEW JERSEY
(mg/kg)

SUBSTANCE	REPRESENTATIVE CONCENTRATION	STATISTICAL DISTRIBUTION
ALUMINUM	4350	NONPARAMETRIC
ARSENIC	3.3	NONPARAMETRIC
BARIIUM	9.6	NONPARAMETRIC
BERYLLIUM	0.45	NONPARAMETRIC
CHROMIUM	48.2	NONPARAMETRIC
COPPER	17.20	NONPARAMETRIC
IRON	9480	NONPARAMETRIC
LEAD	29.80	NONPARAMETRIC
MAGNESIUM	661	NONPARAMETRIC
MANGANESE	11.20	NONPARAMETRIC
POTASSIUM	2270	NONPARAMETRIC
SELENIUM	0.35	NONPARAMETRIC
VANADIUM	36.10	NONPARAMETRIC
ZINC	33.30	NORMAL
1,1,1-TRICHLOROETHANE	2	LOGNORMAL
4,4'-DDT	5.2	NONPARAMETRIC
ANTHRACENE	82	NONPARAMETRIC
BENZO(A)ANTHRACENE	172	NONPARAMETRIC
BENZO(A)PYRENE	210	NONPARAMETRIC
BENZO(B)FLUORANTHENE	161	NONPARAMETRIC
BENZO(G,H,I)PERYLENE	100	NONPARAMETRIC
BENZO(K)FLUORANTHENE	130	NONPARAMETRIC
BIS(2-ETHYLHEXYL)PHTHALAT	97	NONPARAMETRIC
CHRYSENE	171.5	NONPARAMETRIC
DI-N-BUTYLPHTHALATE	71	NONPARAMETRIC
FLUDRANTHENE	580	NONPARAMETRIC
INDENO(1,2,3-CD)PYRENE	97	NONPARAMETRIC
PHENANTHRENE	155.5	NONPARAMETRIC
PYRENE	570	NONPARAMETRIC

*Organics are in ug/kg

TABLE 33
REPRESENTATIVE CONCENTRATION AND STATISTICAL DISTRIBUTION OF COPCS
SEDIMENT - SITE 22
NWS EARLE, COLTS NECK, NEW JERSEY
(mg/kg)

SUBSTANCE	REPRESENTATIVE CONCENTRATION	STATISTICAL DISTRIBUTION
ALUMINUM	3930	NONPARAMETRIC
ARSENIC	2.9	NONPARAMETRIC
BARIUM	16.5	NONPARAMETRIC
BERYLLIUM	0.36	NONPARAMETRIC
CADMIUM	2.70	NONPARAMETRIC
CHROMIUM	31.80	NONPARAMETRIC
COBALT	3.50	NORMAL
COPPER	18.30	NONPARAMETRIC
IRON	13400	NONPARAMETRIC
LEAD	106	NONPARAMETRIC
MANGANESE	101.64	NORMAL
NICKEL	5.56	NORMAL
SELENIUM	0.36	NORMAL
SODIUM	67.10	NONPARAMETRIC
VANADIUM	29	NONPARAMETRIC
ZINC	119	NONPARAMETRIC
4,4'-DDT	13	NONPARAMETRIC
ACENAPHTHENE	300	NONPARAMETRIC
ANTHRACENE	880	NONPARAMETRIC
BENZO(A)ANTHRACENE	1800	NONPARAMETRIC
BENZO(A)PYRENE	970	NONPARAMETRIC
BENZO(B)FLUORANTHENE	1200	NONPARAMETRIC
BENZO(G,H,I)PERYLENE	830	NONPARAMETRIC
BENZO(K)FLUORANTHENE	1200	NONPARAMETRIC
BIS(2-ETHYLHEXYL)PHTHALATE	77	NONPARAMETRIC
CHRYSENE	1700	NONPARAMETRIC
DI-N-BUTYLPHTHALATE	69	NONPARAMETRIC
DIBENZ(A,H)ANTHRACENE	220	LOGNORMAL
FLUORANTHENE	5000	NONPARAMETRIC
FLUORENE	150	NONPARAMETRIC
INDENO(1,2,3-CD)PYRENE	780	NONPARAMETRIC
PHENANTHRENE	6300	NONPARAMETRIC
PYRENE	3300	NONPARAMETRIC

*Organics are in ug/kg

TABLE 34
RME CARCINOGENIC RISK TO FUTURE INDUSTRIAL RECEPTORS - SITE 22
SUBSURFACE SOIL, AMENDED RISK
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SUBSURFACE SOIL INGESTION	SUBSURFACE SOIL DERMAL CONTACT	INHALATION OF COPCS IN FUGITIVE DUST
1,1,1-TRICHLOROETHANE	N/A	N/A	N/A
4,4'-DDT	5.9E-10	N/A	1.3E-13
ANTHRACENE	N/A	N/A	N/A
BENZO(A)ANTHRACENE	4.4E-08	N/A	9.5E-12
BENZO(A)PYRENE	5.4E-07	N/A	1.2E-10
BENZO(B)FLUORANTHENE	4.1E-08	N/A	8.9E-12
BENZO(G,H,I)PERYLENE	N/A	N/A	N/A
BENZO(K)FLUORANTHENE	3.3E-09	N/A	7.2E-13
BIS(2-ETHYLHEXYL)PHTHALATE	4.7E-10	N/A	8.8E-14
CHRYSENE	4.4E-10	N/A	9.5E-14
DI-N-BUTYLPHTHALATE	N/A	N/A	N/A
FLUORANTHENE	N/A	N/A	N/A
INDENO(1,2,3-CD)PYRENE	2.5E-08	N/A	5.3E-12
PHENANTHRENE	N/A	N/A	N/A
PYRENE	N/A	N/A	N/A
ARSENIC	1.7E-05	1.7E-05	3.8E-09
COPPER	N/A	N/A	N/A
TOTAL RISK	1.8E-05	1.7E-05	4.0E-09

* CANCER RISK FOR PAHS NOT ESTIMATED FOR DERMAL EXPOSURE

TABLE 35

RME NONCARCINOGENIC HQS, FUTURE INDUSTRIAL RECEPTORS - SITE 22
SUBSURFACE SOIL, AMENDED RISK
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SUBSURFACE SOIL INGESTION	SUBSURFACE SOIL DERMAL CONTACT	INHALATION OF COPCS IN FUGITIVE DUST
1,1,1-TRICHLOROETHANE	2.2E-08	N/A	4.3E-12
4,4'-DDT	9.8E-06	N/A	1.8E-09
ANTHRACENE	2.7E-07	N/A	5.0E-11
BENZO(A)ANTHRACENE	N/A	N/A	N/A
BENZO(A)PYRENE	N/A	N/A	N/A
BENZO(B)FLUORANTHENE	N/A	N/A	N/A
BENZO(G,H,I)PERYLENE	N/A	N/A	N/A
BENZO(K)FLUORANTHENE	N/A	N/A	N/A
BIS(2-ETHYLHEXYL)PHTHALATE	4.7E-06	N/A	8.8E-10
CHRYSENE	N/A	N/A	N/A
DI-N-BUTYLPHTHALATE	6.9E-07	N/A	1.3E-10
FLUORANTHENE	1.4E-05	N/A	2.6E-09
INDENO(1,2,3-CD)PYRENE	N/A	N/A	N/A
PHENANTHRENE	N/A	N/A	N/A
PYRENE	1.9E-05	N/A	3.4E-09
ARSENIC	1.1E-02	1.1E-02	2.0E-06
COPPER	4.2E-04	N/A	7.8E-08

TABLE 36

**RME CARCINOGENIC RISK TO FUTURE RESIDENTIAL RECEPTORS - SITE 22
 SUBSURFACE SOIL, AMENDED RISK
 NWS EARLE, COLTS NECK, NEW JERSEY**

SUBSTANCE	SUBSURFACE SOIL INGESTION - LIFETIME	SUBSURFACE SOIL DERMAL CONTACT - LIFETIME	INHALATION OF COPCS IN FUGITIVE DUST - LIFETIME
1,1,1-TRICHLOROETHANE	N/A	N/A	N/A
4,4'-DDT	2.7E-09	N/A	8.1E-14
ANTHRACENE	N/A	N/A	N/A
BENZO(A)ANTHRACENE	2.0E-07	N/A	5.8E-12
BENZO(A)PYRENE	2.4E-06	N/A	7.1E-11
BENZO(B)FLUORANTHENE	1.8E-07	N/A	5.5E-12
BENZO(G,H,I)PERYLENE	N/A	N/A	N/A
BENZO(K)FLUORANTHENE	1.5E-08	N/A	4.4E-13
BIS(2-ETHYLHEXYL)PHTHALATE	2.1E-09	N/A	5.4E-14
CHRYSENE	2.0E-09	N/A	5.8E-14
DI-N-BUTYLPHTHALATE	N/A	N/A	N/A
FLUORANTHENE	N/A	N/A	N/A
INDENO(1,2,3-CD)PYRENE	1.1E-07	N/A	3.3E-12
PHENANTHRENE	N/A	N/A	N/A
PYRENE	N/A	N/A	N/A
ARSENIC	7.7E-05	5.6E-05	2.4E-09
COPPER	N/A	N/A	N/A
TOTAL RISK	8.0E-05	5.6E-05	2.4E-09

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL
 * CANCER RISK FOR PAHS NOT ESTIMATED FOR DERMAL EXPOSURE

TABLE 37

**CENTRAL TENDENCY CARCINOGENIC RISK TO FUTURE RESIDENTIAL RECEPTORS - SITE 22
 SUBSURFACE SOIL, AMENDED RISK
 NWS EARLE, COLTS NECK, NEW JERSEY**

SUBSTANCE	SUBSURFACE SOIL INGESTION - LIFETIME	SUBSURFACE SOIL DERMAL CONTACT - LIFETIME	INHALATION OF COPCS IN FUGITIVE DUST - LIFETIME
1,1,1-TRICHLOROETHANE	N/A	N/A	N/A
4,4'-DDT	4.3E-10	N/A	2.5E-14
ANTHRACENE	N/A	N/A	N/A
BENZO(A)ANTHRACENE	3.2E-08	N/A	1.8E-12
BENZO(A)PYRENE	3.9E-07	N/A	2.2E-11
BENZO(B)FLUORANTHENE	3.0E-08	N/A	1.7E-12
BENZO(G,H,I)PERYLENE	N/A	N/A	N/A
BENZO(K)FLUORANTHENE	2.4E-09	N/A	1.4E-13
BIS(2-ETHYLHEXYL)PHTHALATE	3.4E-10	N/A	1.7E-14
CHRYSENE	3.1E-10	N/A	1.8E-14
DI-N-BUTYLPHTHALATE	N/A	N/A	N/A
FLUORANTHENE	N/A	N/A	N/A
INDENO(1,2,3-CD)PYRENE	1.8E-08	N/A	1.0E-12
PHENANTHRENE	N/A	N/A	N/A
PYRENE	N/A	N/A	N/A
ARSENIC	9.9E-06	1.4E-05	5.8E-10
COPPER	N/A	N/A	N/A
TOTAL RISK	1.0E-05	1.4E-05	6.1E-10

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

* CANCER RISK FOR PAHS NOT ESTIMATED FOR DERMAL EXPOSURE

TABLE 38

RME NONCARCINOGENIC HQS, FUTURE RESIDENTIAL RECEPTORS - SITE 22
SUBSURFACE SOIL, AMENDED RISK
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SUBSURFACE SOIL INGESTION - CHILD	SUBSURFACE SOIL DERMAL CONTACT - CHILD	INHALATION OF COPCS IN FUGITIVE DUST - CHILD
1,1,1-TRICHLOROETHANE	2.8E-07	N/A	4.5E-12
4,4'-DDT	1.3E-04	N/A	1.9E-09
ANTHRACENE	3.5E-06	N/A	5.2E-11
BENZO(A)ANTHRACENE	N/A	N/A	N/A
BENZO(A)PYRENE	N/A	N/A	N/A
BENZO(B)FLUORANTHENE	N/A	N/A	N/A
BENZO(G,H,I)PERYLENE	N/A	N/A	N/A
BENZO(K)FLUORANTHENE	N/A	N/A	N/A
BIS(2-ETHYLHEXYL)PHTHALATE	6.2E-05	N/A	9.3E-10
CHRYSENE	N/A	N/A	N/A
DI-N-BUTYLPHTHALATE	9.1E-06	N/A	1.4E-10
FLUORANTHENE	1.9E-04	N/A	2.8E-09
INDENO(1,2,3-CD)PYRENE	N/A	N/A	N/A
PHENANTHRENE	N/A	N/A	N/A
PYRENE	2.4E-04	N/A	3.6E-09
ARSENIC	1.4E-01	8.7E-02	2.1E-06
COPPER	5.5E-03	N/A	8.2E-08

TABLE 39

**RME CARCINOGENIC RISK, WADING, FUTURE RECREATIONAL RECEPTORS - SITE 22
 SEDIMENT
 NWS EARLE, COLTS NECK, NEW JERSEY**

SUBSTANCE	SEDIMENT INGESTION	SEDIMENT DERMAL CONTACT
4,4'-DDT	4.8E-11	1.2E-11
ACENAPHTHENE	N/A	N/A
ANTHRACENE	N/A	N/A
BENZO(A)ANTHRACENE	1.4E-08	5.7E-09
BENZO(A)PYRENE	7.8E-08	1.0E-07
BENZO(B)FLUORANTHENE	9.6E-09	3.8E-09
BENZO(G,H,I)PERYLENE	N/A	N/A
BENZO(K)FLUORANTHENE	9.6E-10	3.8E-10
BIS(2-ETHYLHEXYL)PHTHALATE	1.2E-11	4.7E-12
CHRYSENE	1.4E-10	5.4E-11
DI-N-BUTYLPHTHALATE	N/A	N/A
DIBENZ(A,H)ANTHRACENE	1.8E-08	3.5E-08
FLUORANTHENE	N/A	N/A
FLUORENE	N/A	N/A
INDENO(1,2,3-CD)PYRENE	6.2E-09	2.5E-09
PHENANTHRENE	N/A	N/A
PYRENE	N/A	N/A
ALUMINUM	N/A	N/A
ARSENIC	4.8E-08	2.0E-09
BARIUM	N/A	N/A
BERYLLIUM	1.7E-08	6.7E-08
CADMIUM	N/A	N/A
CHROMIUM	N/A	N/A
COBALT	N/A	N/A
COPPER	N/A	N/A
IRON	N/A	N/A
LEAD	N/A	N/A
MANGANESE	N/A	N/A
NICKEL	N/A	N/A
SELENIUM	N/A	N/A
VANADIUM	N/A	N/A
ZINC	N/A	N/A
TOTAL RISK	1.9E-07	2.2E-07

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL
 * CANCER RISK FOR PAHS NOT ESTIMATED FOR DERMAL EXPOSURE

TABLE 40

RME NONCARCINOGENIC HQS, WADING, FUTURE RECREATIONAL RECEPTORS - SITE 22

SEDIMENT

NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SEDIMENT INGESTION	SEDIMENT DERMAL CONTACT
4,4'-DDT	3.3E-06	8.2E-07
ACENAPHTHENE	6.4E-07	2.5E-07
ANTHRACENE	3.8E-07	1.5E-07
BENZO(A)ANTHRACENE	NA	NA
BENZO(A)PYRENE	NA	NA
BENZO(B)FLUORANTHENE	NA	NA
BENZO(G,H,I)PERYLENE	NA	NA
BENZO(K)FLUORANTHENE	NA	NA
BIS(2-ETHYLHEXYL)PHTHALATE	4.9E-07	1.9E-07
CHRYSENE	NA	NA
DI-N-BUTYLPHTHALATE	8.8E-08	1.9E-08
DIBENZ(A,H)ANTHRACENE	NA	NA
FLUORANTHENE	1.6E-05	6.3E-06
FLUORENE	4.8E-07	1.9E-07
INDENO(1,2,3-CD)PYRENE	NA	NA
PHENANTHRENE	NA	NA
PYRENE	1.4E-05	5.6E-06
ALUMINUM	5.0E-04	4.0E-04
ARSENIC	1.2E-03	5.2E-05
BARIUM	3.0E-05	3.0E-05
BERYLLIUM	9.2E-06	3.6E-05
CADMIUM	6.9E-04	5.5E-04
CHROMIUM	8.1E-04	1.6E-03
COBALT	7.5E-06	5.9E-06
COPPER	5.8E-05	3.9E-06
IRON	5.7E-03	4.5E-03
LEAD	NA	NA
MANGANESE	2.6E-03	3.4E-03
NICKEL	3.6E-05	9.4E-06
SELENIUM	9.2E-06	4.5E-07
VANADIUM	5.3E-04	2.1E-03
ZINC	5.1E-05	8.0E-06

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 41

**SUMMARY OF ESTIMATED RME CANCER RISKS AND NONCARCINOGENIC HAZARD INDICIES - SITE 22
NWS EARLE, COLTS NECK, NEW JERSEY**

Medium	Exposure Routes	Estimated Incremental Cancer Risk					Estimated Hazard Index**							
		Current Industrial Employee	Future Industrial Employee	Future Lifetime Resident	Future Lifetime Resident	Future Recreational Child	Current Industrial Employee	Future Industrial Employee	Future Resident				Future Recreational Child	
									Child	Adult	Child	Adult		
Surface Soil	Incidental Ingestion	N/S	N/A	N/S	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A	N/A
	Dermal Contact	N/S	N/A	N/S	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A	N/A
	Inhalation of Fugitive Dust	N/S	N/A	N/S	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A	N/A
Subsurface Soil	Incidental Ingestion	N/A	1.8E-05^	8.0E-05^	N/A	N/A	N/A	1.1E-02^	1.5E-01^	N/A	N/A	N/A	N/A	N/A
	Dermal Contact	N/A	1.7E-05^	5.6E-05^	N/A	N/A	N/A	1.1E-02^	8.7E-02^	N/A	N/A	N/A	N/A	N/A
	Inhalation of Fugitive Dust	N/A	4.0E-09^	2.4E-09^	N/A	N/A	N/A	2.1E-06^	2.2E-06^	N/A	N/A	N/A	N/A	N/A
Sediment	Incidental Ingestion	N/A	N/A	N/A	N/A	1.9E-07	N/A	N/A	N/A	N/A	N/A	N/A	N/A	1.2E-02
	Dermal Contact	N/A	N/A	N/A	N/A	2.2E-07	N/A	N/A	N/A	N/A	N/A	N/A	N/A	1.3E-02
Groundwater	Ingestion	N/A	N/S	N/S	N/S	N/A	N/A	N/S	N/S	N/S	N/S	N/S	N/A	N/A
	Dermal Contact	N/A	N/S	N/S	N/S	N/A	N/A	N/S	N/S	N/S	N/S	N/S	N/A	N/A
	Inhalation of Volatiles*	N/A	N/S	N/S	N/S	N/A	N/A	N/S	N/S	N/S	N/S	N/S	N/A	N/A
Surface Water	Incidental Ingestion	N/A	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/S
	Dermal Contact	N/A	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/S
TOTAL		-	3.5E-05	1.4E-04	-	4.1E-07	-	2.2E-02	2.3E-01	-	-	-	-	2.5E-02

N/A = Not applicable because this media is not associated with this potential receptor

N/S = Not sampled

* = During Showering, Adult Residents Only

** = Hazard Indices (i.e., summation of hazard quotients) are used only for comparison purposes and do not reflect actual additive noncarcinogenic effects

^ - Value from amended risk assessment.

TABLE 42

**SUMMARY OF CENTRAL TENDENCY CANCER RISKS AND NONCARCINOGENIC HAZARD INDICIES - SITE 22
NWS EARLE, COLTS NECK, NEW JERSEY**

Medium	Exposure Routes	Estimated Incremental Cancer Risk					Estimated Hazard Index**							
		Current Industrial Employee	Future Industrial Employee	Future Lifetime Resident	Future Lifetime Resident	Future Recreational Child	Current Industrial Employee	Future Industrial Employee	Future Resident				Future Recreational Child	
									Child	Adult	Child	Adult		
Surface Soil	Incidental Ingestion	N/S	N/A	N/S	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A	N/A
	Dermal Contact	N/S	N/A	N/S	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A	N/A
	Inhalation of Fugitive Dust	N/S	N/A	N/S	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A	N/A
Subsurface Soil	Incidental Ingestion	N/A	N/R	1.0E-05 [^]	N/A	N/A	N/A	N/R	N/R	N/A	N/A	N/A	N/A	N/A
	Dermal Contact	N/A	N/R	1.4E-05 [^]	N/A	N/A	N/A	N/R	N/R	N/A	N/A	N/A	N/A	N/A
	Inhalation of Fugitive Dust	N/A	N/R	6.1E-10 [^]	N/A	N/A	N/A	N/R	N/R	N/A	N/A	N/A	N/A	N/A
Sediment	Incidental Ingestion	N/A	N/A	N/A	N/A	N/R	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/R
	Dermal Contact	N/A	N/A	N/A	N/A	N/R	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/R
Groundwater	Ingestion	N/A	N/S	N/S	N/S	N/A	N/A	N/S	N/S	N/S	N/S	N/A	N/A	N/A
	Dermal Contact	N/A	N/S	N/S	N/S	N/A	N/A	N/S	N/S	N/S	N/S	N/A	N/A	N/A
	Inhalation of Volatiles*	N/A	N/S	N/S	N/S	N/A	N/A	N/S	N/S	N/S	N/A	N/S	N/A	N/A
Surface Water	Incidental Ingestion	N/A	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/S
	Dermal Contact	N/A	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/S
TOTAL				2.4E-05										

N/A = Not applicable because this media is not associated with this potential receptor

N/R - Central Tendency calculation not required

N/S = Not sampled

* = During Showering, Adult Residents Only

** = Hazard Indices (i.e., summation of hazard quotients) are used only for comparison purposes and do not reflect actual additive noncarcinogenic effects

[^] - Value from amended risk assessment.

TABLE 43
SEDIMENT CONTAMINANTS OF POTENTIAL CONCERN - SITE 22
NWS EARLE, COLTS NECK, NEW JERSEY

Contaminant of Potential Concern (COPC)	Frequency of Detection	Background Concentration (mg/kg)	Maximum Concentration (mg/kg)	Ecotox Threshold (mg/kg) ¹	Hazard Quotient	Reason for Retention or Elimination as Final COPC ²
Inorganics						
Aluminum	5/5	3940	3930.0	NA		Retained-No suitable threshold available
Arsenic	5/5	6.2	2.90	8.2	0.35	Eliminated-Does not exceed threshold
Barium	5/5	10.6	16.5	40.00	0.41	Eliminated-Does not exceed threshold
Beryllium	5/5	0.57	0.36	NA		Retained-No suitable threshold available
Cadmium	3/5	ND	2.7	1.2/9.6	2.25/0.28	Retained-HQ > 1
Chromium	5/5	56	31.8	81	0.39	Eliminated-Does not exceed threshold
Cobalt	2/5	2.1	5.2	50.00	0.10	Eliminated-Does not exceed threshold
Copper	5/5	13	18.3	34	0.54	Eliminated-Does not exceed threshold
Lead	5/5	34.3	106.0	47/218	2.25/0.49	Retained-HQ > 1
Manganese	5/5	9.2	155	460.00	0.34	Eliminated-Does not exceed threshold
Nickel	1/5	6	5.56	21	0.26	Eliminated-Does not exceed threshold
Selenium	2/5	ND	0.38	NA		Retained-No suitable threshold available
Vanadium	5/5	42.7	29.0	NA		Retained-No suitable threshold available
Zinc	5/5	26.9	119.0	150.0	0.79	Eliminated-Does not exceed threshold
Organics³						
4,4'-DDT	1/2	19.0	13.0	1.6/46	8.13/0.28	Retained-HQ > 1
Acenaphthene	1/3	ND	300.0	620.00	0.48	Eliminated-Does not exceed threshold
Anthracene	2/3	ND	880.0	330.00/1700.0	2.67/0.52	Retained-HQ > 1
Benzo(a)anthracene	2/3	560.0	1800.0	330.00/1600.0	5.45/1.13	Retained-HQ > 1
Benzo(a)pyrene	2/3	590.0	970.0	430/1600	2.25/0.61	Retained-HQ > 1
Benzo(b)fluoranthene	3/3	490.0	1200.0	330.00/1700.0	3.64/0.71	Retained-HQ > 1
Benzo(g,h,i)perylene	2/3	380.0	830.0	330.00/1700.0	2.52/0.49	Retained-HQ > 1
Benzo(k)fluoranthene	3/3	470.0	1200.0	330.00/1700.0	3.64/0.71	Retained-HQ > 1
Bis(2-ethylhexyl)phthalate	1/3	ND	77.0	8.90E+08	0.00	Eliminated-Does not exceed threshold
Chrysene	2/3	940.0	1700.0	330.00/2800.0	5.15/0.61	Retained-HQ > 1

**TABLE 43,
 SEDIMENT CONTAMINANTS OF POTENTIAL CONCERN - SITE 22
 NWS EARLE, COLTS NECK, NEW JERSEY**

Contaminant of Potential Concern (COPC)	Frequency of Detection	Background Concentration (mg/kg)	Maximum Concentration (mg/kg)	Ecotox Threshold (mg/kg) ¹	Hazard Quotient	Reason for Retention or Elimination as Final COPC ²
Di-n-butylphthalate	2/3	ND	69.0	11,000.0	0.01	Eliminated-Does not exceed threshold
Dibenzo(a,h)anthracene	2/3	ND	220.0	330.00	0.67	Eliminated-Does not exceed threshold
Fluoranthene	3/3	1800.0	5000.0	2900.00	1.72	Retained-HQ > 1
Fluorene	1/3	190.0	150.0	540.00	0.28	Eliminated-Does not exceed threshold
Indeno(1,2,3-cd)pyrene	2/3	310.0	780.0	330.00/1700.0	2.36/0.46	Retained-HQ > 1
Phenanthrene	2/3	1900.0	6300.0	850/1500	7.41/4.2	Retained-HQ > 1
Pyrene	3/3	1900.0	3300.0	660/2600	5.0/1.27	Retained-HQ > 1

ND = None detected

NA = No suitable threshold was available

1 When two values are presented, the left value is the most conservative available and the right value is a less conservative value, if available. In these instances, two HQ values are presented.

2 Contaminants were retained as final COPCs if the most conservative ET value available was exceeded.

3 All organic values are in ug/kg

TABLE 44
SURFACE SOIL CONTAMINANTS OF POTENTIAL CONCERN - SITE 22
NWS EARLE, COLTS NECK, NEW JERSEY

Contaminant of Potential Concern (COPC)	Frequency of Detection	Background Concentration (mg/kg)	Maximum Concentration (mg/kg)	Ecotox Threshold (mg/kg)	Hazard Quotient	Reason for Retention or Elimination as Final COPC
Inorganics						
Aluminum	3/3	5310	4350.0	600	7.25	Retained-HQ > 1
Arsenic	3/3	14.4	3.30	60	0.06	Eliminated-Does not exceed threshold
Barium	3/3	15.8	9.60	3000	0.00	Eliminated-Does not exceed threshold
Beryllium	3/3	0.28	0.45	NA		Retained-No suitable threshold available
Chromium	3/3	59.5	48.2	0.4	120.0	Retained-HQ > 1
Copper	3/3	6.6	17.2	50	0.17	Eliminated-Does not exceed threshold
Lead	3/3	39.4	29.8	500	0.06	Eliminated-Does not exceed threshold
Manganese	3/3	93.9	11.2	100	0.11	Eliminated-Does not exceed threshold
Nickel	1/3	4.0	2.8	200	0.01	Eliminated-Does not exceed threshold
Selenium	1/3	0.56	0.35	70	0.00	Eliminated-Does not exceed threshold
Vanadium	3/3	61.6	36.1	20	1.8	Retained-HQ > 1
Zinc	3/3	50.7	33.3	200	0.17	Eliminated-Does not exceed threshold
Organics						
1,1,1-Trichloroethane	1/3	ND	2.0	300	0.01	Eliminated-Does not exceed threshold
4,4'-DDT	2/3	ND	5.0	100	0.05	Eliminated-Does not exceed threshold
Anthracene	1/2	ND	82.0	100	0.82	Eliminated-Does not exceed threshold
Benzo(a)anthracene	1/2	ND	172.0	100	1.72	Retained-HQ > 1
Benzo(a)pyrene	1/2	ND	210.0	100	2.1	Retained-HQ > 1
Benzo(b)fluoranthene	1/2	ND	161.0	100	1.61	Retained-HQ > 1
Benzo(g,h,i)perylene	1/2	ND	100.0	100	1.0	Retained-HQ > 1
Benzo(k)fluoranthene	1/2	ND	130.0	100	1.30	Retained-HQ > 1
Bis(2-ethylhexyl)phthalate	1/2	ND	97.0	NA		Retained-No suitable threshold available
Chrysene	1/2	ND	172.0	100	1.72	Retained-HQ > 1
Di-n-butylphthalate	2/2	48	71.0	NA		Retained-No suitable threshold available
Fluoranthene	1/2	84	580.0	100	5.80	Retained-HQ > 1
Indeno(1,2,3-cd)pyrene	1/2	ND	97.0	100	0.97	Eliminated-Does not exceed threshold

TABLE 44**SURFACE SOIL CONTAMINANTS OF POTENTIAL CONCERN - SITE 22
NWS EARLE, COLTS NECK, NEW JERSEY**

Contaminant of Potential Concern (COPC)	Frequency of Detection	Background Concentration (mg/kg)	Maximum Concentration (mg/kg)	Ecotox Threshold (mg/kg)	Hazard Quotient	Reason for Retention or Elimination as Final COPC
Phenanthrene	1/2	ND	155.5	100	1.56	Retained-HQ > 1
Pyrene	1/2	ND	570.0	100	5.70	Retained-HQ > 1

ND = None Detected

NA = No suitable threshold was available

* all organic values are in ug/kg

TABLE 45
ANALYTICAL RESULTS
CONFIRMATORY SOIL SAMPLES
SITE 22
NWS EARLE
COLTS NECK, NJ

Analyte/Compound	22-CS01	22-CS02	22-CS03	22-CS04	22-CS05	22-CS06	22-CS07	22-CS08	Residential	Non-Residential	Impact to
	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	Dir. Contact (mg/kg) (1)	Dir. Contact (mg/kg) (1)	Groundwater (mg/kg) (1)
Cyanide	<0.57	<0.58	<0.61	<0.66	<0.57	<0.57	<0.59	<0.59	1,100	21,000	NS
Silver	<0.23	<0.23	<0.24	<0.26	<0.23	<0.23	<0.24	<0.24	110	4,100	NS
Aluminum	5,540.0	322.0	2,150.0	3,110.0	3,380.0	4,520.0	4,200.0	5,820.0	NS	NS	NS
Arsenic	<1.7	<1.3	<1.8	<2.0	<1.7	<1.7	<1.8	<1.8	20	20	NS
Barium	4.8	3.2	5.0	10.7	7.5	6.9	8.9	8.7	700	47,000	NS
Beryllium	0.58	<0.05	0.06	0.15	0.71	0.82	0.50	0.90	1	1	NS
Calcium	296.0	232.0	227.0	227.0	255.0	213.0	297.0	256.0	NS	NS	NS
Cadmium	<0.17	<0.17	<0.18	<0.20	<0.17	<0.17	<0.18	<0.18	1	100	NS
Cobalt	0.59	0.27	0.49	0.14	0.54	0.59	0.84	<0.12	NS	NS	NS
Chromium	69.9	1.6	12.9	32.7	64.2	74.7	46.6	86.1	NS	NS	NS
Copper	2.1	0.65	3.1	4.0	1.9	1.7	2.0	1.9	600	600	NS
Iron	15,700.0	273.0	2,970.0	3,740.0	12,800.0	15,200.0	10,200.0	14,700.0	NS	NS	NS
Mercury	0.05	0.02	0.04	0.07	<0.01	<0.01	0.02	0.01	14	270	NS
Potassium	2,920.0	62.1	351.0	869.0	3,370.0	4,640.0	2,850.0	4,370.0	NS	NS	NS
Magnesium	1,240.0	58.9	178.0	338.0	1,120.0	1,640.0	1,090.0	1,610.0	NS	NS	NS
Manganese	4.9	6.6	9	4.2	3	7.9	11.5	4.6	NS	NS	NS
Sodium	29.7	17.9	28.9	39.8	44.4	26.0	34.1	37.9	NS	NS	NS
Nickel	1.3	<1.2	<1.2	<1.3	1.3	<1.1	<1.2	1.4	250	2,400	NS
Lead	5.0	4.8	6.2	7.9	6.7	6.5	19.1	5.5	400	600	NS
Antimony	<2.3	<2.3	<2.4	<2.6	<2.3	<1.2	<1.3	2.7	14	340	NS
Selenium	3.1	<2.9	<3.0	<3.3	<2.3	8.6	<3.0	<3.0	63	3,100	NS
Thallium	<1.7	<1.7	<1.8	<2.0	<1.7	<1.7	<1.8	<1.8	2	2	NS
Vanadium	42.6	1.2	8	14.6	63.6	67.1	39.4	70.3	370	7,100	NS
Zinc	13.9	3.0	2.4	3	8.9	13.4	13.9	11.3	1,500	1,500	NS
Benzo(b)fluoranthene	<330	<330	<330	<330	<330	<330	<330	<330	0.9	4	50
Fluoranthene	<330	<330	<330	<330	<330	<330	<330	<330	2,300	10,000	100
Pyrene	<330	<330	<330	<330	<330	<330	<330	<330	1,700	10,000	100

(1) 7/11/96 CRITERIA

NS = NO STANDARD

Exceedance

Note: Organic compounds (Benzo(b)fluoranthene, Fluoranthene, and Pyrene) are reported in ug/kg.

TABLE 46

**OCCURRENCE AND DISTRIBUTION OF INORGANICS IN SUBSURFACE SOIL AT SITE 23
NWS EARLE, COLTS NECK, NEW JERSEY
(mg/kg)**

SUBSTANCE	BACKGROUND			SITE-RELATED				
	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	2 X AVERAGE BKGD CONCENTRATION	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	AVERAGE CONCENTRATION	MEAN > 2 X BKGD	REPRESENTATIVE CONCENTRATION
ALUMINUM	8 / 8	675 - 5310	5370.00	4 / 4	2450 - 3040	2697.5	NO	3040
ARSENIC	8 / 8	1.35 - 14.4	13.29	4 / 4	6.7 - 16.2	10.48	NO	16.2
BARIUM	8 / 8	0.92 - 31	17.92	4 / 4	0.66 - 6.1	2.49	NO	6.1
BERYLLIUM*	2 / 8	0.12 - 0.28	0.28	4 / 4	0.26 - 0.69	0.46	YES	0.69
CADMIUM	1 / 8	0.57	0.58	4 / 4	0.85 - 1.5	1.02	YES	1.40
CALCIUM	8 / 8	28.6 - 799	577.55	4 / 4	60.3 - 718	319.58	NO	718
CHROMIUM	8 / 8	4.7 - 59.5	54.73	4 / 4	53.8 - 91.2	70.55	YES	91.2
COPPER	8 / 8	0.97 - 8.6	8.66	1 / 4	1.6	0.80	NO	1.6
IRON	8 / 8	3745 - 62500	40871.25	4 / 4	10900 - 22300	14025	NO	20524
LEAD*	8 / 8	1.4 - 39.4	24.33	4 / 4	2.4 - 9.8	6.30	NO	9.8
MAGNESIUM	8 / 8	18.5 - 619	504.05	4 / 4	516 - 1080	759	YES	1080
MANGANESE	8 / 8	2.6 - 214	92.51	1 / 4	1.3	0.57	NO	1.14
MERCURY	8 / 8	0.03 - 0.17	0.13	2 / 4	0.008 - 0.012	0.01	NO	0.012
NICKEL	4 / 8	1.8 - 7.2	4.75	2 / 4	1.1 - 1.8	0.98	NO	1.8
POTASSIUM	7 / 8	95 - 792	793.35	4 / 4	1510 - 3210	2275	YES	3210
SODIUM	8 / 8	17.5 - 94.8	79.35	4 / 4	21.1 - 28.1	23.98	NO	28.1
THALLIUM	4 / 8	0.7 - 1.9	1.38	4 / 4	0.9 - 1.6	1.23	NO	1.6
VANADIUM*	8 / 8	11.05 - 64	64.71	4 / 4	79.8 - 178	115.95	YES	178
ZINC	6 / 8	1.1 - 50.7	31.35	4 / 4	6.8 - 10.7	8.58	NO	10.7

Note: Selected COPCs are indicated in boldface type.

* - Indicates COPCs eliminated based on amended risk assessment.

TABLE 47
OCCURRENCE AND DISTRIBUTION OF ORGANICS IN SUBSURFACE SOIL AT SITE 23
NWS EARLE, COLTS NECK, NEW JERSEY
 (ug/kg)

SUBSTANCE	BACKGROUND			SITE-RELATED		
	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	REPRESENTATIVE CONCENTRATION	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	REPRESENTATIVE CONCENTRATION
ACENAPHTHENE	NOT DETECTED	-	-	1 / 7	2700	1243.91
BENZO(A)ANTHRACENE	NOT DETECTED	-	-	1 / 7	19000	8097.30
BENZO(A)PYRENE	NOT DETECTED	-	-	1 / 7	13000	5574.57
BENZO(B)FLUORANTHENE	NOT DETECTED	-	-	1 / 7	14000	5995.03
BENZO(G,H,I)PERYLENE	NOT DETECTED	-	-	1 / 7	6800	2967.76
BENZO(K)FLUORANTHENE	NOT DETECTED	-	-	1 / 7	5000	2210.94
BIS(2-ETHYLHEXYL)PHTHALATE	NOT DETECTED	-	-	2 / 7	380 - 590	387.53
CARBAZOLE	NOT DETECTED	-	-	1 / 7	2800	1285.95
CHRYSENE	NOT DETECTED	-	-	1 / 7	19000	8097.30
DIBENZ(A,H)ANTHRACENE	NOT DETECTED	-	-	1 / 7	2100	991.64
DIBENZOFURAN	NOT DETECTED	-	-	1 / 7	1500	739.38
FLUORANTHENE	2 / 8	40 - 84	84	1 / 7	38000	16085.93
FLUORENE	NOT DETECTED	-	-	1 / 7	2900	1328.00
GAMMA-BHC (LINDANE)	NOT DETECTED	-	-	1 / 7	0.039	0.039
INDENO(1,2,3-CD)PYRENE	NOT DETECTED	-	-	1 / 7	5600	2463.22
PHENANTHRENE	NOT DETECTED	-	-	1 / 7	20000	8517.75
PYRENE	1 / 8	46	46	1 / 7	32000	13563.20

TABLE 48

COMPARISON OF SUBSURFACE SOIL ANALYTICAL DATA TO ARARS AND TBCs - SITE 23

NWS EARLE, COLTS NECK, NEW JERSEY

SAMPLE NUMBER:	23SB01-04	23SB01-16	23SB02-02	23SB02-16	23SB03-06	23SB03-14	ARARS & TBCs		
							NJDEP Soil Residential Direct Contact Cleanup Criteria	NJDEP Soil Non-Residential Direct Contact Cleanup Criteria	NJDEP Soil Impact to Groundwater Cleanup Criteria
LOCATION:	23SB01	23SB01	23SB02	23SB02	23SB03	23SB03			
DATA SOURCE:	1995 RI								
INORGANICS	mg/kg	mg/kg	mg/kg						
aluminum	2450	3040	1430	1270	2790	2510	-	-	-
arsenic	6.7	16.2	2.2	10.4	7.9	11.1	20.0	20.0	-
barium	6.1	0.66	2.5	2.3	1.3	1.9	700	47000	-
beryllium	0.26	0.69	0.049	0.17	0.51	0.39	1.00	1.00	-
cadmium	0.87	1.5 E	0.35	1.1 E	0.86	0.85	1.00	100	-
calcium	718	424	68.1	31.9	76.0	60.3	-	-	-
chromium, total	53.8	91.2	13.1	45.7	67.3	69.9	-	500	-
copper	1.6	1.1 U	5.6	1.0 U	1.0 U	1.1 U	600	600	-
iron	10900	22300	3620	15200	11400	11500	-	-	-
lead	8.7 J	9.8 J	4.8 J	4.5 J	2.4	4.3 J	400	600	-
magnesium	734	1080	75.5	230	706	516	-	-	-
manganese	1.3	0.65 U	3.7	0.64 U	0.63 U	0.66 U	-	-	-
mercury	0.012 J	0.0068 UJ	0.019 J	0.0069 UJ	0.0067 UJ	0.0080 J	14.0	270	-
nickel	1.0 U	1.8	1.0 U	1.0 U	1.1	1.0 U	250	2400	-
potassium	1510	3210	298	880	2530	1850	-	-	-
sodium	28.1	24.2	26.9	18.2	22.5	21.1	-	-	-
thallium	1.6 J	1.2 J	1.9 J	0.91 J	0.90 J	1.2 J	2.00	2.00	-
vanadium	79.8	178	13.9	86.5	103	103	370	7100	-
zinc	8.8 J	10.7 J	23.8 J	8.1 J	6.8 J	8.0 J	1500	1500	-
SEMIVOLATILES	ug/kg	ug/kg	ug/kg						
acenaphthene	390 U	370 U	390 U	360 U	360 U	380 U	3400000	10000000	100000
anthracene	390 U	370 U	390 U	360 U	360 U	380 U	10000000	10000000	100000
benzo(a)anthracene	390 U	370 U	390 U	360 U	360 U	380 U	900	4000	500000
benzo(a)pyrene	390 U	370 U	390 U	360 U	360 U	380 U	660	660	100000
benzo(b)fluoranthene	390 U	370 U	390 U	360 U	360 U	380 U	900	4000	50000
benzo(g,h,i)perylene	390 U	370 U	390 U	360 U	360 U	380 U	-	-	-
benzo(k)fluoranthene	390 U	370 U	390 U	360 U	360 U	380 U	900	4000	500000
bis(2-ethylhexyl)phthalate	590	370 U	390 U	360 U	360 U	380 U	49000	210000	100000

TABLE 48

06/17/96

**COMPARISON OF SUBSURFACE SOIL ANALYTICAL DATA TO ARARS AND TBCs - SITE 23
NWS EARLE, COLTS NECK, NEW JERSEY**

FINAL
Page 2

SAMPLE NUMBER:	23SB01-04	23SB01-16	23SB02-02	23SB02-16	23SB03-06	23SB03-14	ARARS & TBCs		
	LOCATION: 23SB01	23SB01	23SB02	23SB02	23SB03	23SB03	NJDEP Soil Residential Direct Contact Cleanup Criteria	NJDEP Soil Non-Residential Direct Contact Cleanup Criteria	NJDEP Soil Impact to Groundwater Cleanup Criteria
DATA SOURCE:	1995 RI	1995 RI	1995 RI	1995 RI	1995 RI	1995 RI			
SEMIVOLATILES	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
carbazole	390 U	370 U	390 U	360 U	360 U	380 U	-	-	-
chrysene	390 U	370 U	390 U	360 U	360 U	380 U	9000	40000	500000
dibenz(a,h)anthracene	390 U	370 U	390 U	360 U	360 U	380 U	660	660	100000
dibenzofuran	390 U	370 U	390 U	360 U	360 U	380 U	-	-	-
fluoranthene	390 U	370 U	390 U	360 U	360 U	380 U	2300000	10000000	100000
fluorene	390 U	370 U	390 U	360 U	360 U	380 U	2300000	10000000	100000
indeno(1,2,3-cd)pyrene	390 U	370 U	390 U	360 U	360 U	380 U	900	4000	500000
phenanthrene	390 U	370 U	390 U	360 U	360 U	380 U	-	-	-
pyrene	390 U	370 U	390 U	360 U	360 U	380 U	1700000	10000000	100000
PESTICIDES	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
gamma-BHC (Lindane)	2.0 U	1.9 U	0.039 JN	1.9 U	1.8 U	1.9 U	520	2200	50000

TABLE 48

COMPARISON OF SUBSURFACE SOIL ANALYTICAL DATA TO ARARS AND TBCs - SITE 23

NWS EARLE, COLTS NECK, NEW JERSEY

SAMPLE NUMBER:	23SB04-02	---	---	---	---	---	ARARS & TBCs		
							NJDEP Soil Residential Direct Contact Cleanup Criteria	NJDEP Soil Non-Residential Direct Contact Cleanup Criteria	NJDEP Soil Impact to Groundwater Cleanup Criteria
LOCATION:	23SB04	---	---	---	---	---	mg/kg	mg/kg	mg/kg
DATA SOURCE:	1995 RI								
INORGANICS	mg/kg						mg/kg	mg/kg	mg/kg
aluminum	1300						-	-	-
arsenic	5.3						20.0	20.0	-
barium	4.0						700	47000	-
beryllium	0.20 U						1.00	1.00	-
cadmium	0.57 U						1.00	100	-
calcium	243						-	-	-
chromium, total	152						-	500	-
copper	.12						600	600	-
iron	3420						-	-	-
lead	12.0						400	600	-
magnesium	77.9						-	-	-
manganese	3.6						-	-	-
mercury	0.0022 U						14.0	270	-
nickel	1.3 U						250	2400	-
potassium	237						-	-	-
sodium	28.0						-	-	-
thallium	0.79 UJ						2.00	2.00	-
vanadium	16.4						370	7100	-
zinc	42.0						1500	1500	-
SEMIVOLATILES	ug/kg						ug/kg	ug/kg	ug/kg
acenaphthene	2700 J						3400000	10000000	100000
anthracene	5400						10000000	10000000	100000
benzo(a)anthracene	19000 E						900	4000	500000
benzo(a)pyrene	13000 E						660	660	100000
benzo(b)fluoranthene	14000 E						900	4000	50000
benzo(g,h,i)perylene	6800								
benzo(k)fluoranthene	5000 E						900	4000	500000
bis(2-ethylhexyl)phthalate	380 J						49000	210000	100000

06/17/96

TABLE 48

COMPARISON OF SUBSURFACE SOIL ANALYTICAL DATA TO ARARS AND TBCs - SITE 23

NWS EARLE, COLTS NECK, NEW JERSEY

FINAL

Page 4

SAMPLE NUMBER:	23SB04-02	---	---	---	---	---	ARARS & TBCs		
							NJDEP Soil Residential Direct Contact Cleanup Criteria	NJDEP Soil Non-Residential Direct Contact Cleanup Criteria	NJDEP Soil Impact to Groundwater Cleanup Criteria
LOCATION:	23SB04	---	---	---	---	---			
DATA SOURCE:	1995 RI								
SEMIVOLATILES	ug/kg						ug/kg	ug/kg	ug/kg
carbazole	2800 J						-	-	-
chrysene	19000 E						9000	40000	500000
dibenz(a,h)anthracene	2100 E J						660	660	100000
dibenzofuran	1500 J						-	-	-
fluoranthene	38000						2300000	10000000	100000
fluorene	2900 J						2300000	10000000	100000
indeno(1,2,3-cd)pyrene	5600 E						900	4000	500000
phenanthrene	20000						-	-	-
pyrene	32000 J						1700000	10000000	100000
PESTICIDES	ug/kg						ug/kg	ug/kg	ug/kg
gamma-BHC (Lindane)	1.9 U						520	2200	50000

TABLE 48
COMPARISON OF SUBSURFACE SOIL ANALYTICAL DATA TO ARARS AND TBCS - SITE 23
NWS EARLE, COLTS NECK, NEW JERSEY

FINAL
PAGE 5

Footnotes to sample results:

- U - Compound or element was not detected. Value is the detection limit (inorganics) or quantitation limit (organics).
- UJ - Not detected. Detection limit or quantitation limit shown is considered estimated due to exceedance of data validation quality control criteria.
- No Value - Constituent was not analyzed for in this sample.
- UR - Nondetected result is considered rejected based on exceedance of data validation quality control criteria.
- J - Value is estimated because concentration is below the quantitation limit or because of exceedance of data validation quality control criteria.
- R - Positive result is considered rejected based on exceedance of data validation quality control criteria.
- N - Compound is considered to be tentatively identified based on exceedance of QC criteria for compound identification.
- E - Result exceeds one or more of the selected ARARs.

Footnotes to soil criteria:

- No standard is available for this chemical in this classification.

06/18/96

TABLE 49

**COMPARISON OF SUBSURFACE SOIL MISCELLANEOUS PARAMETERS DATA TO ARARS AND TBCs - SITE 23
NWS EARLE, COLTS NECK, NEW JERSEY**

SAMPLE NUMBER:	23SB01-04	23SB01-16	23SB02-02	23SB02-16	23SB03-06	ARARS & TBCs			
	LOCATION:	23SB01	23SB01	23SB02	23SB02	23SB03	NJDEP Soil Residential Direct Contact Cleanup Criteria	NJDEP Soil Non-Residential Direct Contact Cleanup Criteria	NJDEP Soil Impact to Groundwater Cleanup Criteria
DATA SOURCE:	1995 RI								
MISCELLANEOUS									
moisture %	15.2	11.0	15.1	9.0	8.1	-	-	-	
pH	7.0	6.9	4.7	4.0	4.3	-	-	-	

06/18/96

TABLE 49

COMPARISON OF SUBSURFACE SOIL MISCELLANEOUS PARAMETERS DATA TO ARARS AND TBCs - SITE 23

NWS EARLE, COLTS NECK, NEW JERSEY

FINAL

Page 2

SAMPLE NUMBER:	23SB03-14	23SB04-02	---	---	---	ARARS & TBCs		
						NJDEP Soil Residential Direct Contact Cleanup Criteria	NJDEP Soil Non-Residential Direct Contact Cleanup Criteria	NJDEP Soil Impact to Groundwater Cleanup Criteria
LOCATION:	23SB03	23SB04	---	---	---			
DATA SOURCE:	1995 RI	1995 RI						
MISCELLANEOUS								
moisture %	12.2	n/a				-	-	-
pH	4.2	n/a				-	-	-

TABLE 49

COMPARISON OF SUBSURFACE SOIL MISCELLANEOUS PARAMETERS DATA TO ARARS AND TBCS - SITE 23 NWS EARLE, COLTS NECK, NEW JERSEY

FINAL
PAGE 3

Footnotes to sample results:

- U - Compound or element was not detected. Value is the detection limit (inorganics) or quantitation limit (organics).
- UJ - Not detected. Detection limit or quantitation limit shown is considered estimated due to exceedance of data validation quality control criteria.
- No Value - Constituent was not analyzed for in this sample.
- UR - Nondetected result is considered rejected based on exceedance of data validation quality control criteria.
- J - Value is estimated because concentration is below the quantitation limit or because of exceedance of data validation quality control criteria.
- R - Positive result is considered rejected based on exceedance of data validation quality control criteria.
- N - Compound is considered to be tentatively identified based on exceedance of QC criteria for compound identification.
- E - Result exceeds one or more of the selected ARARs.

Footnotes to soil criteria:

- No standard is available for this chemical in this classification.
- @ - Value is New Jersey guideline for maximum total concentration of all organic compounds in soil (including VOCs, SVOCs, and TPH).

TABLE 50

**OCCURRENCE AND DISTRIBUTION OF INORGANICS IN SEDIMENT AT SITE 23
NWS EARLE, COLTS NECK, NEW JERSEY
(mg/kg)**

SUBSTANCE	BACKGROUND			SITE-RELATED				
	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	2 X AVERAGE BKGD CONCENTRATION	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	AVERAGE CONCENTRATION	MEAN > 2 X BKGD	REPRESENTATIVE CONCENTRATION
ALUMINUM	3 / 3	839 - 3940	5492.67	5 / 5	1260 - 2660	2089.00	NO	2660.00
ARSENIC	2 / 3	2.4 - 6.2	5.95	5 / 5	1.6 - 4.7	2.63	NO	4.70
BARIUM	3 / 3	3.9 - 10.6	14.07	5 / 5	4.1 - 16.7	8.92	NO	16.70
CADMIUM	NOT DETECTED	-	-	2 / 5	0.71 - 1.2	0.59	YES	1.20
CALCIUM	3 / 3	179 - 518	685.33	5 / 5	187 - 410	265.70	NO	397.16
CHROMIUM	3 / 3	4.3 - 56	43.13	5 / 5	14.05 - 120	37.19	NO	81.36
COPPER	3 / 3	1.5 - 13	12.47	5 / 5	2.2 - 6.7	4.37	NO	6.70
IRON	3 / 3	228 - 7650	6578.67	5 / 5	5400 - 13200	8642.00	YES	12957.55
LEAD	3 / 3	4.6 - 34.3	30.60	5 / 5	4.1 - 72.5	21.28	NO	48.87
MAGNESIUM	3 / 3	60.7 - 256	306.47	5 / 5	115 - 269.5	179.50	NO	269.50
MANGANESE	3 / 3	4.6 - 9.2	13.80	5 / 5	3.7 - 9.95	6.85	NO	9.95
MERCURY	1 / 3	0.068	0.05	3 / 5	0.0041 - 0.057	0.02	NO	0.04
NICKEL	2 / 3	2.1 - 6	7.93	4 / 5	1.4 - 4.5	2.63	NO	4.50
POTASSIUM	2 / 3	86.1 - 681	589.40	5 / 5	207 - 458	319.40	NO	458.00
SODIUM	3 / 3	26.6 - 116	115.27	5 / 5	24.9 - 40.7	31.79	NO	39.77
VANADIUM	3 / 3	5.9 - 42.7	36.93	5 / 5	12 - 20.8	16.70	NO	20.80
ZINC	3 / 3	14.2 - 26.9	37.33	5 / 5	9.7 - 71.3	31.10	NO	71.30

Note: Selected COPCs are indicated in boldface type.

TABLE 51
OCCURRENCE AND DISTRIBUTION OF ORGANICS IN SEDIMENT AT SITE 23
NWS EARLE, COLTS NECK, NEW JERSEY
 (ug/kg)

SUBSTANCE	BACKGROUND			SITE-RELATED		
	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	REPRESENTATIVE CONCENTRATION	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	REPRESENTATIVE CONCENTRATION
1,2,4-TRICHLOROBENZENE	NOT DETECTED	-	-	1 / 5	75	75
4,4'-DDD	2 / 3	4.9 - 21	21	3 / 5	0.38 - 4.85	4.85
4,4'-DDT	1 / 3	19	19	1 / 5	6.75	5.16
ALPHA-CHLORDANE	NOT DETECTED	-	-	2 / 5	0.37 - 0.55	0.55
ANTHRACENE	NOT DETECTED	-	-	1 / 5	65	65
BENZO(A)ANTHRACENE	2 / 3	140 - 560	560	2 / 5	110 - 590	590
BENZO(A)PYRENE	2 / 3	160 - 590	590	2 / 5	110 - 480	480
BENZO(B)FLUORANTHENE	2 / 3	150 - 490	490	2 / 5	220 - 895	652.44
BENZO(G,H,I)PERYLENE	2 / 3	130 - 380	380	2 / 5	99 - 165	165
BENZO(K)FLUORANTHENE	2 / 3	150 - 470	470	2 / 5	71 - 150	150
BIS(2-ETHYLHEXYL)PHTHALATE	NOT DETECTED	-	-	5 / 5	50 - 400	270.61
CHRYSENE	2 / 3	250 - 940	940	2 / 5	180 - 630	630
DIBENZ(A,H)ANTHRACENE	NOT DETECTED	-	-	1 / 5	54	54
DIETHYLPHTHALATE	1 / 3	44	44	1 / 5	180	180
FLUORANTHENE	2 / 3	300 - 1800	1800	2 / 5	240 - 1000	719.57
FLUORENE	1 / 3	190	190	1 / 5	50	50
GAMMA-CHLORDANE	1 / 3	0.095	0.095	1 / 5	0.38	0.38
INDENO(1,2,3-CD)PYRENE	2 / 3	110 - 310	310	2 / 5	99 - 200	200
PHENANTHRENE	2 / 3	200 - 1900	1900	2 / 5	180 - 725	544.48
PYRENE	2 / 3	350 - 1900	1900	2 / 5	350 - 770	770

07/15/96

TABLE 52

COMPARISON OF SEDIMENT ANALYTICAL DATA TO ARARS AND TBCs - SITE 23

FINAL

Page 1

NWS EARLE, COLTS NECK, NEW JERSEY

SAMPLE NUMBER: LOCATION: DATA SOURCE:	23SD01	23SD02	23SD03	23SD04	23SD05	23SD05-DUP	---	ARARS & TBCs
	23SD01	23SD02	23SD03	23SD04	23SD05	23SD05	---	Sediment Ecological Toxicity Threshold Values
	1995 RI	1995 RI	1995 RI	1995 RI	1995 RI	1995 RI		
	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg		mg/kg
INORGANICS								
aluminum	1970	2660	2590	1260	1950	1980		8.20 L
arsenic	4.7	3.1	1.6	2.0	1.8	1.7		40.0 B
barium	11.1	6.4	16.7	6.3	4.6	3.6		1.20 L
cadmium	1.2 J	0.60 U	0.77 U	0.71 J	0.68 U	0.71 U		-
calcium	410	187	191	269	249	294		81.0 L
chromium, total	15.6	18.1	120 E	18.2	15.7	12.4		34.0 L
copper	4.9	6.7	2.2	2.4	5.9	5.4		-
iron	8130	5400	8940	13200	7830	7250		47.0 L
lead	11.3	13.8	72.5 E	4.1	5.0	4.4		-
magnesium	172	115	138	203	257	282		460 O
manganese	8.5	5.5	3.7	6.6	10.5	9.4		0.150 L
mercury	0.018 J	0.057 J	0.0028 U	0.0027 U	0.0041 J	0.0025 U		21.0 L
nickel	4.0	1.4	4.5	1.6 U	2.5	2.4		-
potassium	351	207	348	458	321	145		-
sodium	36.3	24.9	40.7	28.6	24.6	32.3		-
vanadium	20.1	16.5	14.1	20.8	12.8	11.2		-
zinc	35.0	15.9 J	71.3	9.7 J	17.7 J	23.6		150 L
SEMIVOLATILES	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg		ug/kg
1,2,4-trichlorobenzene	600 U	380 U	75.0 J	450 U	430 U	440 U		9200
anthracene	600 U	380 U	490 U	450 U	54.0 J	76.0 J		330 F
benzo(a)anthracene	600 U	380 U	490 U	110 J	320 J	590 E		330 F
benzo(a)pyrene	600 U	380 U	490 U	110 J	320 J	480 E		430 L
benzo(b)fluoranthene	600 U	380 U	490 U	220 J	590 E	1200 E		330 F
benzo(g,h,i)perylene	600 U	380 U	490 U	99.0 J	220 J	110 J		330 F
benzo(k)fluoranthene	600 U	380 U	490 U	71.0 J	150 J	440 U		330 F
bis(2-ethylhexyl)phthalate	62.0 J	52.0 J	400 J	50.0 J	50.0 J	440 U		890000000 S
chrysene	600 U	380 U	490 U	180 J	460 E	800 E		330 F
dibenz(a,h)anthracene	600 U	380 U	490 U	450 U	54.0 J	440 U		330 F

TABLE 52

COMPARISON OF SEDIMENT ANALYTICAL DATA TO ARARS AND TBCs - SITE 23

NWS EARLE, COLTS NECK, NEW JERSEY

SAMPLE NUMBER:	23SD01	23SD02	23SD03	23SD04	23SD05	23SD05-DUP	---	ARARS & TBCs
LOCATION:	23SD01	23SD02	23SD03	23SD04	23SD05	23SD05	---	Sediment
DATA SOURCE:	1995 RI		Ecological Toxicity Threshold Values					
SEMIVOLATILES	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg		ug/kg
diethylphthalate	600 U	380 U	490 U	450 U	180 J	440 U		630000 P
fluoranthene	600 U	380 U	490 U	240 J	700	1300		2900 Q
fluorene	600 U	380 U	490 U	450 U	50.0 J	440 U		540 P
indeno(1,2,3-cd)pyrene	600 U	380 U	490 U	99.0 J	230 J	170 J		330 F
phenanthrene	600 U	380 U	490 U	180 J	540	910 E		850 Q
pyrene	600 U	380 U	490 U	350 J	770 E	950 E J		660 L
PESTICIDES	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg		ug/kg
4,4'-DDD	0.80 J	3.8 U	0.20 R	0.38 JN	4.8 E	4.9 E		1.60 L
4,4'-DDE	6.0 U	3.8 U	4.9 U	4.5 U	2.4 E JN	2.3 E R		2.20 L
4,4'-DDT	6.0 U	3.8 U	4.9 U	4.5 U	5.2 E	8.3 E		1.60 L
aldrin	3.1 U	2.0 U	2.5 U	2.3 U	2.2 U	1.2 JN		-
alpha-chlordane	0.66 R	0.37 J	0.55 J	2.3 U	2.2 U	2.3 U		7.00 O
delta-BHC	1.0 R	2.0 U	2.5 U	2.3 U	2.2 U	2.3 U		-
gamma-chlordane	3.1 U	2.0 U	0.38 JN	2.3 U	2.2 U	2.3 U		7.00 O
heptachlor epoxide	3.1 U	2.0 U	2.5 U	2.3 U	0.36 JN	1.3 R		5.00 O
methoxychlor	30.0 U	20.0 U	25.0 U	23.0 U	22.0 U	3.8 R		19.0 P

TABLE 52

COMPARISON OF SEDIMENT ANALYTICAL DATA TO ARARS AND TBCS - SITE 23 NWS EARLE, COLTS NECK, NEW JERSEY

FINAL
PAGE 3

Footnotes to sample results:

- U - Compound or element was not detected. Value is the detection limit (inorganics) or quantitation limit (organics).
- UJ - Not detected. Detection limit or quantitation limit shown is considered estimated due to exceedance of data validation quality control criteria.
- No Value - Constituent was not analyzed for in this sample.
- UR - Nondetected result is considered rejected based on exceedance of data validation quality control criteria.
- J - Value is estimated because concentration is below the quantitation limit or because of exceedance of data validation quality control criteria.
- R - Positive result is considered rejected based on exceedance of data validation quality control criteria.
- N - Compound is considered to be tentatively identified based on exceedance of QC criteria for compound identification.
- E - Result exceeds one or more of the selected ARARs.

Footnotes to sediment ecological toxicity criteria:

- No standard is available for this chemical in this classification.
- B - Source: Baudo, R., J. Geisy and H. Muntau. eds. 1990. Sediments: Chemistry and Toxicity of In-Place Pollutants. Lewis Publishers, Inc. Ann Arbor, MI.
- F - Source: USEPA. 1994c. Draft Region IV Waste Management Division Sediment Screening Values for Hazardous Waste Sites. 2/16/94 Revision.
- L - Effects Range-Low. Source: Long E.R., D.D. MacDonald, S.L. Smith, and F.D. Calder. 1995. Incidence of Adverse Biological Effects within Ranges of Chemical Concentrations in Marine and Estuarine Sediments. Environmental Management. 19:81-97.
- M - Effects Range-Low. Source: Long, E. R. and L. G. Morgan. 1991. The Potential for Biological Effects of Sediment-Sorbed Contaminants Tested in the National Status and Trends Program. NOAA Technical Memorandum NOS OMA 52, National Oceanic and Atmospheric Administration, Seattle, WA.
- O - Ontario screening level. Source: Ontario Ministry of the Environment (OME). 1992. Guidelines for the Protection and Management of the Aquatic Sediment Quality in Ontario. Log 92-2309-067, PIBS 1962.
- P - Sediment quality benchmark using equipartition. Source: USEPA. 1996. ECO Update. Volume 3: Number 2. EPA 540/F-95/038.
- Q - Sediment quality criterion. Source: USEPA. 1996. ECO Update. Volume 3: Number 2. EPA 540/F-95/038.
- S - Sediment screening benchmark. Source: Suter, G. W., and J. B. Mabrey. 1994. Toxicological Benchmarks for Screening Potential Contaminants of Concern for Effects on Aquatic Biota. Oak Ridge National Laboratory, Oak Ridge, TN.
- T - Threshold for soils. Source: Direction des Substances Dangereuses. 1988. Contaminated Sites Rehabilitation Policy. Gouvernement du Quebec. Ministere de L'Environnement. Sainte-Foy, Quebec, Canada. In: R.L. Siegrist. 1989. International Review of Approaches for Establishing Cleanup Goals for Hazardous Waste Contaminated Land. Institute for Georesearch and Pollution Research. Norway.
- W - Screening value for wet soil. Source: Will, M.E., and G.W. Suter. 1994. Toxicological Benchmarks for Screening Potential Contaminants of Concern for Effects on Terrestrial Plants: 1994 Revision. Oak Ridge National Laboratory.

TABLE 53

**OCCURRENCE AND DISTRIBUTION OF INORGANICS IN GROUNDWATER AT SITE 23
NWS EARLE, COLTS NECK, NEW JERSEY
(ug/L)**

SUBSTANCE	BACKGROUND			SITE-RELATED				
	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	2 X AVERAGE CONCENTRATION	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	AVERAGE CONCENTRATION	MEAN > 2 X BKGD	REPRESENTATIVE CONCENTRATION
ALUMINUM	11 / 11	287 - 7870	5097.82	3 / 3	9500 - 41700	25600.00	YES	41700
ARSENIC	1 / 11	5.8 - 5.8	4.05	3 / 3	8.4 - 40.4	25.50	YES	40.4
BARIUM*	11 / 11	2.6 - 518	229.60	3 / 3	46 - 298	134.67	NO	298
BERYLLIUM	4 / 11	0.21 - 1.6	0.49	3 / 3	0.98 - 6.5	3.73	YES	6.5
CADMIUM	5 / 11	0.6 - 1.9	1.21	3 / 3	3 - 15	7.13	YES	15
CALCIUM	11 / 11	506 - 17200	8306.55	3 / 3	6450 - 10200	8203.33	NO	10200
CHROMIUM	NOT DETECTED	-	-	3 / 3	486 - 2380	1358.67	YES	2380
COBALT	6 / 11	0.7 - 10.1	4.06	3 / 3	9.9 - 27.2	20.23	YES	27.2
COPPER	9 / 11	0.79 - 13.5	6.53	3 / 3	11.2 - 33.5	21.77	YES	33.5
IRON	11 / 11	153 - 7690	4197.09	3 / 3	25800 - 108000	64633.33	YES	108000
LEAD	3 / 11	2.1 - 3	2.44	3 / 3	19.8 - 50.1	38.40	YES	50.1
MAGNESIUM	11 / 11	273 - 27400	8449.64	3 / 3	2860 - 9900	6733.33	NO	9900
MANGANESE	11 / 11	3.3 - 65	46.18	3 / 3	18.6 - 59.3	42.07	NO	59.3
MERCURY*	11 / 11	0.005 - 0.12	0.12	3 / 3	0.048 - 0.081	0.07	NO	0.081
NICKEL	11 / 11	0.81 - 25.5	11.98	3 / 3	13.2 - 83	58.87	YES	83
POTASSIUM	11 / 11	350 - 3245	2810.55	3 / 3	8660 - 37700	22053.33	YES	37700
SELENIUM*	1 / 11	5.3 - 5.3	4.96	1 / 3	7.5	3.97	NO	7.5
SILVER	NOT DETECTED	-	-	1 / 3	1	0.65	YES	1
SODIUM	11 / 11	1850 - 11650	8449.09	3 / 3	6360 - 28600	14470.00	YES	28600
THALLIUM*	3 / 11	4 - 5.1	5.15	1 / 3	3.9	2.50	NO	3.9
VANADIUM	10 / 11	0.69 - 42.25	16.48	3 / 3	211 - 1140	654.33	YES	1140
ZINC*	6 / 9	3.7 - 348	178.61	3 / 3	199 - 322	267.67	YES	322

Note: Selected COPCs are indicated in boldface type.
* - Indicates COPCs eliminated based on amended risk assessment.

TABLE 54
OCCURRENCE AND DISTRIBUTION OF ORGANICS IN GROUNDWATER AT SITE 23
NWS EARLE COLTS NECK, NEW JERSEY
 (ug/L)

SUBSTANCE	BACKGROUND			SITE-RELATED		
	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	REPRESENTATIVE CONCENTRATION	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	REPRESENTATIVE CONCENTRATION
4,4'-DDT	NOT DETECTED	-	-	1 / 2	0.034	0.034
CHLOROFORM	NOT DETECTED	-	-	1 / 3	6	6
DIELDRIN	NOT DETECTED	-	-	1 / 3	0.016	0.016
ENDOSULFAN I	NOT DETECTED	-	-	2 / 2	0.0078 - 0.025	0.025
GAMMA-BHC (LINDANE)	NOT DETECTED	-	-	1 / 2	0.0086	0.0086
HEPTACHLOR EPOXIDE	NOT DETECTED	-	-	1 / 1	0.013	0.013

TABLE 55

COMPARISON OF GROUNDWATER ANALYTICAL DATA TO ARARS AND TBCs - SITE 23

NWS EARLE, COLTS NECK, NEW JERSEY

SAMPLE NUMBER: LOCATION: DATA SOURCE:	23GW01	23GW02	23GW02-F	23GW03	23GW03-F	---	ARARS & TBCs		
	23GW01	23GW02	23GW02	23GW03	23GW03	---	Maximum Contaminant Level (MCL)	Drinking Water Health Advisory (Lowest Criterion Shown)	NJDEP Groundwater Quality Standard
	1995 RI	1995 RI	1995 RI	1995 RI	1995 RI		ug/L	ug/L	ug/L
INORGANICS	ug/L	ug/L	ug/L	ug/L	ug/L				
aluminum	25600 E J	9500 E J	1790 E J	41700 E J	104		-	-	200
arsenic	27.7 E	8.4 E	3.3 U	40.4 E	4.1		50.0	-	8.00
barium	46.0	298	33.3	60.0	27.3		2000	2000 a	2000
beryllium	3.7	1.0	0.11 U	6.5 E	0.11 U		4.00	4000 e	20.0
cadmium	3.4	3.0	10.9 E	15.0 E	8.5 E		5.00	5.00 e	4.00
calcium	7960	6450	6010	10200	5640		-	-	-
chromium, total	1210 E	486 E	29.9	2380 E	2.2		100	100 a	100
cobalt	23.6	9.9	6.1	27.2	10.2		-	-	-
copper	20.6	11.2	2.6	33.5	2.2		1300	-	1000
iron	60100 E	25800 E	4890 E	108000 E	452 E		-	-	300
lead	45.3 E	19.8 E	8.6 J	50.1 E	1.5 UJ		15.0	-	10.0
magnesium	7440	2860	1020	9900	478		-	-	50.0
manganese	18.6	59.3 E	60.7 E	48.3	37.3		2.00	2.00 b	2.00
mercury	0.071	0.081	0.026	0.048	0.011		100	100 a	100
nickel	80.4	13.2	17.9	83.0	25.6		-	-	-
potassium	19800 J	8660	2420	37700 J	3050		50.0	-	50.0
selenium	7.5 J	4.4 U	4.4 U	4.4 U	4.4 U		-	100 a	-
silver	1.0	0.94 U	0.94 U	0.94 U	0.94 U		-	-	50000
sodium	6360	8450	8050	28600	27100		2.00	0.400 a	10.0
thallium	3.9 E J	3.6 U	3.6 U	3.6 UJ	3.6 U		-	-	-
vanadium	612	211	1.4	1140	1.0		-	2000 a	5000
zinc	199	322	86.9	282	66.9		ug/L	ug/L	ug/L
VOLATILES	ug/L	ug/L	ug/L	ug/L	ug/L		100	100 e	6.00
chloroform	10.0 U	10.0 U	n/a	6.0 J	n/a		ug/L	ug/L	ug/L
PESTICIDES	ug/L	ug/L	ug/L	ug/L	ug/L		-	-	0.100
4,4'-DDT	0.074 R	0.034 J	n/a	0.10 U	n/a		-	0.500 e	0.0300
dieldrin	0.016 JN	0.10 U	n/a	0.10 U	n/a		-	-	0.400
endosulfan I	0.025 JN	0.0078 JN	n/a	0.038 R	n/a		-	-	-

TABLE 55

06/17/96

COMPARISON OF GROUNDWATER ANALYTICAL DATA TO ARARS AND TBCs - SITE 23

FINAL

Page 2

NWS EARLE, COLTS NECK, NEW JERSEY

SAMPLE NUMBER:	23GW01	23GW02	23GW02-F	23GW03	23GW03-F	---	ARARS & TBCs		
	23GW01	23GW02	23GW02	23GW03	23GW03	---	Maximum Contaminant Level (MCL)	Drinking Water Health Advisory (Lowest Criterion Shown)	NJDEP Groundwater Quality Standard
LOCATION:	23GW01	23GW02	23GW02	23GW03	23GW03	---			
DATA SOURCE:	1995 RI								
PESTICIDES	ug/L	ug/L	ug/L	ug/L	ug/L		ug/L	ug/L	ug/L
gamma-BHC (Lindane)	0.050 U	0.0086 J	n/a	0.034 R	n/a		0.200	0.200 a	0.200
gamma-chlordane	0.0081 R	0.050 U	n/a	0.0089 R	n/a		2.00	2.00 a	0.500
heptachlor	0.050 U	0.050 U	n/a	0.014 R	n/a		0.400	5.00 e	0.400
heptachlor epoxide	0.025 R	0.013 JN	n/a	0.032 R	n/a		0.200	0.100 e	0.200

TABLE 55
COMPARISON OF GROUNDWATER ANALYTICAL DATA TO ARARS AND TBCS - SITE 23
NWS EARLE, COLTS NECK, NEW JERSEY

FINAL
PAGE 3

Footnotes to sample results:

- U - Compound or element was not detected. Value is the detection limit (inorganics) or quantitation limit (organics).
- UJ - Not detected. Detection limit or quantitation limit shown is considered estimated due to exceedance of data validation quality control criteria.
- No Value - Constituent was not analyzed for in this sample.
- UR - Nondetected result is considered rejected based on exceedance of data validation quality control criteria.
- J - Value is estimated because concentration is below the quantitation limit or because of exceedance of data validation quality control criteria.
- R - Positive result is considered rejected based on exceedance of data validation quality control criteria.
- N - Compound is considered to be tentatively identified based on exceedance of QC criteria for compound identification.
- E - Result exceeds one or more of the selected ARARs.

Footnotes to MCLs, MCLGs, or SMCLs:

- No standard is available for this chemical in this classification.
- a - Where applicable, value(s) represent the more stringent of criteria for total, cis-, and trans- isomers.
- - Criteria are for total chromium.
- ** - Action level 1300 ug/L for water treatment technology for public water supply systems.
- *** - Action level 15 ug/L for water treatment technology for public water supply systems.

Footnotes to Health Advisories:

- No standard is available for this chemical in this classification.
- a - The listed health advisory criterion, lifetime adult, is equal to the most stringent of the EPA health advisories for this chemical.
- b - The listed health advisory criterion, long-term adult, is equal to the most stringent of the EPA health advisories for this chemical.
- c - The listed health advisory criterion, one-day child, is equal to the most stringent of the EPA health advisories for this chemical.
- d - The listed health advisory criterion, ten-day child, is equal to the most stringent of the EPA health advisories for this chemical.
- e - The listed health advisory criterion, long-term child, is equal to the most stringent of the EPA health advisories for this chemical.

TABLE 56
OCCURRENCE AND DISTRIBUTION OF INORGANICS IN SURFACE WATER AT SITE 23
NWS EARLE, COLTS NECK, NEW JERSEY
(ug/L)

SUBSTANCE	BACKGROUND			SITE-RELATED				
	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	2 X AVERAGE BKGD CONCENTRATION	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	AVERAGE CONCENTRATION	MEAN > 2 X BKGD	REPRESENTATIVE CONCENTRATION
ALUMINUM	3 / 3	265 - 409	705.33	3 / 3	148 - 3670	1333.00	YES	3670
BARIUM	3 / 3	16.3 - 34	53.73	3 / 3	15.1 - 301	110.73	YES	301
CADMIUM	1 / 3	0.18	0.23	1 / 3	1	0.46	YES	1
CALCIUM	3 / 3	462 - 10100	9128.00	3 / 3	5680 - 6140	5913.33	NO	6140
CHROMIUM	3 / 3	0.72 - 2.6	2.71	2 / 3	1.3 - 29.4	10.40	YES	29.4
COBALT	3 / 3	0.81 - 1.9	2.54	3 / 3	0.66 - 1.9	1.14	NO	1.9
COPPER	2 / 3	1.1 - 9.8	7.40	3 / 3	1.3 - 16.1	6.33	NO	16.1
IRON	3 / 3	160 - 702	1040.00	3 / 3	338.5 - 33100	11343.17	YES	33100
LEAD	1 / 3	4.4	3.43	1 / 3	10.3	3.93	YES	10.3
MAGNESIUM	3 / 3	369 - 2770	2525.33	3 / 3	1230 - 2660	2146.67	NO	2660
MANGANESE	3 / 3	14 - 55.5	59.93	3 / 3	3.65 - 36.1	15.32	NO	36.1
MERCURY	2 / 3	0.023 - 0.028	0.04	3 / 3	0.076 - 0.17	0.11	YES	0.17
POTASSIUM	2 / 3	251 - 1850	1482.33	3 / 3	524 - 1430	827.67	NO	1430
SODIUM	NOT DETECTED	-	-	3 / 3	3490 - 9050	5360.00	YES	9050
VANADIUM	2 / 3	0.89 - 0.9	1.32	1 / 3	18.8	6.47	YES	18.8
ZINC	3 / 3	7.6 - 29.4	32.67	1 / 3	253	84.87	YES	253

Note: Selected COPCs are indicated in boldface type.

TABLE 57
OCCURRENCE AND DISTRIBUTION OF ORGANICS IN SURFACE WATER AT SITE 23
NWS EARLE, COLTS NECK, NEW JERSEY
 (ug/L)

SUBSTANCE	BACKGROUND			SITE-RELATED		
	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	REPRESENTATIVE CONCENTRATION	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	REPRESENTATIVE CONCENTRATION
BIS(2-ETHYLHEXYL)PHTHALATE	NOT DETECTED			1 / 1	1	1
GAMMA-BHC (LINDANE)	NOT DETECTED			1 / 1	0.0068	0.0068

06/17/96

TABLE 58

COMPARISON OF SURFACE WATER ANALYTICAL DATA TO ARARS AND TBCs - SITE 23
NWS EARLE, COLTS NECK, NEW JERSEY

FINAL
Page 1

SAMPLE NUMBER: LOCATION: DATA SOURCE:	23SW03 23SW03 1995 RI	23SW04 23SW04 1995 RI	23SW05 23SW05 1995 RI	23SW05-DUP 23SW05 1995 RI	ARARS & TBCs				
					AWQC Freshwater Chronic Aquatic Life	AWQC Ingestion of Water and Fish	AWQC Ingestion of Fish Only	NJDEP Criteria Freshwater Chronic Aquatic Life	NJDEP Surface Water Criteria for Protection of Human Health
INORGANICS	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L
aluminum	3670 J	181	148	148	-	-	-	-	-
barium	301	16.1	15.2	15.0	-	-	-	-	2000
cadmium	1.0	0.38 U	0.38 U	0.38 U	1.10 +	-	-	-	-
calcium	6140	5920	5710	5650	-	-	-	-	-
chromium, total	29.4	1.3	1.0 U	1.0 U	209 +	-	-	-	160
cobalt	1.9	0.66	0.60 U	0.86	-	-	-	-	-
copper	16.1 E	1.6	1.3	1.3	11.0 +	-	-	-	-
iron	33100	591	330	347	-	-	-	-	-
lead	10.3 E	1.5 U	1.5 U	1.5 U	3.20 +	-	-	-	5.00
magnesium	1230	2660	2560	2540	-	-	-	-	-
manganese	36.1	6.2	3.7	3.6	-	-	-	-	-
mercury	0.17 E	0.076 E	0.077 E	0.077 E	0.0120	0.140	0.150	-	-
potassium	1430	524	513	545	-	-	-	-	-
sodium	9050	3490	3520	3560	-	-	-	-	-
vanadium	18.8	0.61 U	0.61 U	0.61 U	-	-	-	-	-
zinc	253 E	1.6 U	1.6 U	1.6 U	101 +	-	-	-	-
SEMIVOLATILES	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L
bis(2-ethylhexyl)phthalate	10.0 U	10.0 U	1.0 J	10.0 U	3.00	1.80	5.90	-	1.76
PESTICIDES	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L
4,4'-DDD	0.0012 E R	0.10 U	0.10 U	0.10 U	-	-	-	-	-
gamma-BHC (Lindane)	0.0068 J	0.050 U	0.050 U	0.050 U	0.0800	0.0190	0.0630	0.0800	-

TABLE 58
COMPARISON OF SURFACE WATER ANALYTICAL DATA TO ARARS AND TBCS - SITE 23
NWS EARLE, COLTS NECK, NEW JERSEY

FINAL
PAGE 2

Footnotes to sample results:

- U - Compound or element was not detected. Value is the detection limit (inorganics) or quantitation limit (organics).
- UJ - Not detected. Detection limit or quantitation limit shown is considered estimated due to exceedance of data validation quality control criteria.
- No Value - Constituent was not analyzed for in this sample.
- UR - Nondetected result is considered rejected based on exceedance of data validation quality control criteria.
- J - Value is estimated because concentration is below the quantitation limit or because of exceedance of data validation quality control criteria.
- R - Positive result is considered rejected based on exceedance of data validation quality control criteria.
- N - Compound is considered to be tentatively identified based on exceedance of QC criteria for compound identification.
- E - Result exceeds one or more of the selected ARARs.

Footnotes to Ambient Water Quality Criteria:

- - No standard is available for this chemical in this classification.
- + - Criterion is hardness dependent and is generated based upon an assumed hardness of 100 mg/L.

TABLE 59
REPRESENTATIVE CONCENTRATION AND STATISTICAL DISTRIBUTION OF COPCS
SUBSURFACE SOIL - SITE 23
NWS EARLE, COLTS NECK, NEW JERSEY

CHEMICAL OF CONCERN	REPRESENTATIVE CONCENTRATION (mg/kg)	STATISTICAL DISTRIBUTION
ARSENIC	16.2	NONPARAMETRIC
BERYLLIUM	0.69	NONPARAMETRIC
CADMIUM	1.40	NORMAL
CHROMIUM	91.2	NONPARAMETRIC
LEAD	9.8	NONPARAMETRIC
VANADIUM	178	NONPARAMETRIC
ACENAPHTHENE*	1243.91	NORMAL
BENZO(A)ANTHRACENE*	8097.30	NORMAL
BENZO(A)PYRENE*	5574.57	NORMAL
BENZO(B)FLUORANTHENE*	5995.03	NORMAL
BENZO(G,H,I)PERYLENE*	2967.76	NORMAL
BENZO(K)FLUORANTHENE*	2210.94	NORMAL
BIS(2-ETHYLHEXYL)PHTHALATE*	387.53	NORMAL
CARBAZOLE*	1285.95	NORMAL
CHRYSENE*	8097.30	NORMAL
DIBENZ(A,H)ANTHRACENE*	991.64	NORMAL
DIBENZOFURAN*	739.38	NORMAL
FLUORANTHENE*	16085.93	NORMAL
FLUORENE*	1328.00	NORMAL
GAMMA-BHC (LINDANE)*	0.039	LOGNORMAL
INDENO(1,2,3-CD)PYRENE*	2463.22	NORMAL
PHENANTHRENE*	8517.75	NORMAL
PYRENE*	13563.20	NORMAL

* - UNITS FOR ORGANIC CHEMICALS ARE IN ug/kg

TABLE 60
REPRESENTATIVE CONCENTRATION AND STATISTICAL DISTRIBUTION OF COPCS
SEDIMENT - SITE 23
NWS EARLE, COLTS NECK, NEW JERSEY

CHEMICAL OF CONCERN	REPRESENTATIVE CONCENTRATION (mg/kg)	STATISTICAL DISTRIBUTION
ARSENIC	4.70	NONPARAMETRIC
BARIUM	16.70	NONPARAMETRIC
CADMIUM	1.20	NONPARAMETRIC
CHROMIUM	81.36	NORMAL
IRON	12957.55	NONPARAMETRIC
LEAD	48.87	NORMAL
MANGANESE	9.95	NONPARAMETRIC
ZINC	71.30	NONPARAMETRIC
1,2,4-TRICHLOROBENZENE*	75	NONPARAMETRIC
4,4'-DDD*	4.85	NONPARAMETRIC
4,4'-DDT*	5.16	NORMAL
ALPHA-CHLORDANE*	0.55	NONPARAMETRIC
ANTHRACENE*	65	NONPARAMETRIC
BENZO(A)ANTHRACENE*	590	NONPARAMETRIC
BENZO(A)PYRENE*	480	NONPARAMETRIC
BENZO(B)FLUORANTHENE*	652.44	NORMAL
BENZO(G,H,I)PERYLENE*	165	NONPARAMETRIC
BENZO(K)FLUORANTHENE*	150	NONPARAMETRIC
BIS(2-ETHYLHEXYL)PHTHALATE*	270.61	NORMAL
CHRYSENE*	630	NONPARAMETRIC
DIBENZ(A,H)ANTHRACENE*	54	NONPARAMETRIC
DIETHYLPHTHALATE*	180	NONPARAMETRIC
FLUORANTHENE*	719.57	NORMAL
FLUORENE*	50	NONPARAMETRIC
GAMMA-CHLORDANE*	0.38	NONPARAMETRIC
INDENO(1,2,3-CD)PYRENE*	200	NONPARAMETRIC
PHENANTHRENE*	544.48	NORMAL
PYRENE*	770	NONPARAMETRIC

* - UNITS FOR ORGANIC CHEMICALS ARE IN ug/kg

TABLE 61**REPRESENTATIVE CONCENTRATION AND STATISTICAL DISTRIBUTION OF COPCS
GROUNDWATER - SITE 23 (ug/L)
NWS EARLE, COLTS NECK, NEW JERSEY**

CHEMICAL OF CONCERN	REPRESENTATIVE CONCENTRATION	STATISTICAL DISTRIBUTION
ALUMINIUM	41700	NONPARAMETRIC
ARSENIC	40.4	NONPARAMETRIC
BARIUM	298	NONPARAMETRIC
BERYLLIUM	6.5	NONPARAMETRIC
CADMIUM	15	NONPARAMETRIC
CHROMIUM	2380	NONPARAMETRIC
COBALT	27.2	NONPARAMETRIC
COPPER	33.5	NONPARAMETRIC
IRON	108000	NONPARAMETRIC
LEAD	50.1	NONPARAMETRIC
MERCURY	0.081	NONPARAMETRIC
NICKEL	83	LOGNORMAL
SELENIUM	7.5	LOGNORMAL
SILVER	1	LOGNORMAL
THALLIUM	3.9	LOGNORMAL
VANADIUM	1140	NONPARAMETRIC
ZINC	322	NONPARAMETRIC
4,4'-DDT	0.034	NONPARAMETRIC
CHLOROFORM	6	LOGNORMAL
DIELDRIN	0.016	LOGNORMAL
ENDOSULFAN I	0.025	NONPARAMETRIC
GAMMA-BHC (LINDANE)	0.0086	NONPARAMETRIC
HEPTACHLOR EPOXIDE	0.013	NONPARAMETRIC

TABLE 62
REPRESENTATIVE CONCENTRATION AND STATISTICAL DISTRIBUTION OF COPCS
SURFACE WATER - SITE 23 (ug/L)
NWS EARLE, COLTS NECK, NEW JERSEY

CHEMICAL OF CONCERN	REPRESENTATIVE CONCENTRATION	STATISTICAL DISTRIBUTION
ALUMINUM	3670	NORMAL
BARIUM	301	NORMAL
CADMIUM	1	LOGNORMAL
CHROMIUM	29.4	NONPARAMETRIC
COBALT	1.9	NONPARAMETRIC
COPPER	16.1	NORMAL
IRON	33100	NORMAL
LEAD	10.3	LOGNORMAL
MERCURY	0.17	NORMAL
VANADIUM	18.8	LOGNORMAL
ZINC	253	LOGNORMAL
BIS(2-ETHYLHEXYL)PHTHALATE	1	NONPARAMETRIC
GAMMA-BHC (LINDANE)	0.0068	NONPARAMETRIC

TABLE 63

RME CARCINOGENIC RISK TO FUTURE INDUSTRIAL RECEPTORS - SITE 23
 SUBSURFACE SOIL, AMENDED RISK
 NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SUBSURFACE SOIL INGESTION	SUBSURFACE SOIL DERMAL CONTACT	INHALATION OF COPCS IN FUGITIVE DUST
ACENAPHTHENE	N/A	N/A	N/A
BENZO(A)ANTHRACENE	2.1E-06	N/A	4.5E-10
BENZO(A)PYRENE	1.4E-05	N/A	3.1E-09
BENZO(B)FLUORANTHENE	1.5E-06	N/A	3.3E-10
BENZO(G,H,I)PERYLENE	N/A	N/A	N/A
BENZO(K)FLUORANTHENE	5.6E-08	N/A	1.2E-11
BIS(2-ETHYLHEXYL)PHTHALATE	1.9E-09	N/A	3.5E-13
CARBAZOLE	9.0E-09	N/A	1.7E-12
CHRYSENE	2.1E-08	N/A	4.5E-12
DIBENZO(A,H)ANTHRACENE	N/A	N/A	7.8E-11
DIBENZOFURAN	N/A	N/A	N/A
FLUORANTHENE	N/A	N/A	N/A
FLUORENE	N/A	N/A	N/A
GAMMA-BHC (LINDANE)	N/A	N/A	9.1E-16
INDENO(1,2,3-CD)PYRENE	6.3E-07	N/A	1.4E-10
PHENANTHRENE	N/A	N/A	N/A
PYRENE	N/A	N/A	N/A
ARSENIC	8.5E-05	8.4E-05	1.9E-08
CADMIUM	N/A	N/A	1.1E-10
CHROMIUM	N/A	N/A	5.0E-08
VANADIUM	N/A	N/A	N/A
TOTAL RISK	1.0E-04	8.4E-05	7.3E-08

* CANCER RISK FOR PAHS NOT ESTIMATED FOR DERMAL EXPOSURE

TABLE 64

**CENTRAL TENDENCY CARCINOGENIC RISK TO FUTURE INDUSTRIAL RECEPTORS - SITE 23
 SUBSURFACE SOIL, AMENDED RISK
 NWS EARLE, COLTS NECK, NEW JERSEY**

SUBSTANCE	SUBSURFACE SOIL INGESTION	SUBSURFACE SOIL DERMAL CONTACT	INHALATION OF COPCS IN FUGITIVE DUST
ACENAPHTHENE	N/A	N/A	N/A
BENZO(A)ANTHRACENE	1.7E-07	N/A	8.0E-11
BENZO(A)PYRENE	1.2E-06	N/A	5.5E-10
BENZO(B)FLUORANTHENE	1.3E-07	N/A	5.9E-11
BENZO(G,H,I)PERYLENE	N/A	N/A	N/A
BENZO(K)FLUORANTHENE	4.8E-09	N/A	2.2E-12
BIS(2-ETHYLHEXYL)PHTHALATE	1.6E-10	N/A	6.3E-14
CARBAZOLE	7.6E-10	N/A	3.0E-13
CHRYSENE	1.7E-09	N/A	8.0E-13
DIBENZ(A,H)ANTHRACENE	N/A	N/A	1.4E-11
DIBENZOFURAN	N/A	N/A	N/A
FLUORANTHENE	N/A	N/A	N/A
FLUORENE	N/A	N/A	N/A
GAMMA-BHC (LINDANE)	N/A	N/A	1.6E-16
INDENO(1,2,3-CD)PYRENE	5.3E-08	N/A	2.4E-11
PHENANTHRENE	N/A	N/A	N/A
PYRENE	N/A	N/A	N/A
ARSENIC	4.6E-06	9.1E-06	2.2E-09
CADMIUM	N/A	N/A	2.0E-11
CHROMIUM	N/A	N/A	6.9E-09
VANADIUM	N/A	N/A	N/A
TOTAL RISK	6.2E-06	9.1E-06	9.9E-09

* CANCER RISK FOR PAHS NOT ESTIMATED FOR DERMAL EXPOSURE

TABLE 65

RME NONCARCINOGENIC HQS, FUTURE INDUSTRIAL RECEPTORS - SITE 23
 SUBSURFACE SOIL, AMENDED RISK
 NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SUBSURFACE SOIL INGESTION	SUBSURFACE SOIL DERMAL CONTACT	INHALATION OF COPCS IN FUGITIVE DUST
ACENAPHTHENE	2.0E-05	N/A	3.8E-09
BENZO(A)ANTHRACENE	N/A	N/A	N/A
BENZO(A)PYRENE	N/A	N/A	N/A
BENZO(B)FLUORANTHENE	N/A	N/A	N/A
BENZO(G,H,I)PERYLENE	N/A	N/A	N/A
BENZO(K)FLUORANTHENE	N/A	N/A	N/A
BIS(2-ETHYLHEXYL)PHTHALATE	1.9E-05	N/A	3.5E-09
CARBAZOLE	N/A	N/A	N/A
CHRYSENE	N/A	N/A	N/A
DIBENZO(A,H)ANTHRACENE	N/A	N/A	N/A
DIBENZOFURAN	N/A	N/A	N/A
FLUORANTHENE	3.9E-04	N/A	7.3E-08
FLUORENE	N/A	N/A	N/A
GAMMA-BHC (LINDANE)	N/A	N/A	N/A
INDENO(1,2,3-CD)PYRENE	N/A	N/A	N/A
PHENANTHRENE	N/A	N/A	N/A
PYRENE	4.4E-04	N/A	8.2E-08
ARSENIC	5.3E-02	5.2E-02	9.8E-06
CADMIUM	2.7E-03	8.5E-04	1.4E-06
CHROMIUM	1.8E-02	N/A	3.3E-06
VANADIUM	2.5E-02	N/A	4.6E-06

TABLE 66
RME CARCINOGENIC RISK TO FUTURE INDUSTRIAL RECEPTORS - SITE 23
GROUNDWATER, AMENDED RISK
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	GROUNDWATER INGESTION	GROUNDWATER DERMAL CONTACT
4,4'-DDT	4.0E-08	1.3E-07
CHLOROFORM	1.3E-07	1.3E-09
DIELDRIN	8.9E-07	1.9E-07
ENDOSULFAN I	N/A	N/A
GAMMA-BHC (LINDANE)	3.9E-08	2.0E-09
HEPTACHLOR EPOXIDE	4.1E-07	7.5E-08
ALUMINUM	N/A	N/A
ARSENIC	2.1E-04	9.1E-08
BERYLLIUM	9.8E-05	4.0E-06
CADMIUM	N/A	N/A
CHROMIUM	N/A	N/A
COBALT	N/A	N/A
COPPER	N/A	N/A
IRON	N/A	N/A
LEAD	N/A	N/A
NICKEL	N/A	N/A
SILVER	N/A	N/A
VANADIUM	N/A	N/A
TOTAL RISK	3.1E-04	4.5E-06

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 67

CENTRAL TENDENCY CARCINOGENIC RISK TO FUTURE INDUSTRIAL RECEPTORS - SITE 23
GROUNDWATER, AMENDED RISK
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	GROUNDWATER INGESTION	GROUNDWATER DERMAL CONTACT
4,4'-DDT	4.5E-09	2.0E-08
CHLOROFORM	1.3E-08	1.8E-10
DIELDRIN	9.9E-08	3.1E-08
ENDOSULFAN I	N/A	N/A
GAMMA-BHC (LINDANE)	4.3E-09	3.2E-10
HEPTACHLOR EPOXIDE	4.6E-08	1.2E-08
ALUMINUM	N/A	N/A
ARSENIC	1.5E-05	9.1E-09
BERYLLIUM	6.2E-06	3.6E-07
CADMIUM	N/A	N/A
CHROMIUM	N/A	N/A
COBALT	N/A	N/A
COPPER	N/A	N/A
IRON	N/A	N/A
LEAD	N/A	N/A
NICKEL	N/A	N/A
SILVER	N/A	N/A
VANADIUM	N/A	N/A
TOTAL RISK	2.1E-05	4.3E-07

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 68

RME NONCARCINOGENIC HQS, FUTURE INDUSTRIAL RECEPTORS - SITE 23
 GROUNDWATER, AMENDED RISK
 NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	GROUNDWATER INGESTION	GROUNDWATER INGESTION BY TARGET ORGAN							GROUNDWATER DERMAL CONTACT	
		CARDIO- VASCULAR SYSTEM	SKIN	KIDNEY	LIVER	DIGESTIVE SYSTEM	CENTRAL NERVOUS SYSTEM	REPRO- DUCTIVE SYSTEM		THYROID
4,4'-DDT	6.7E-04				6.7E-04					2.1E-03
CHLOROFORM	5.9E-03			5.9E-03	5.9E-03					5.7E-05
DIELDRIN	3.1E-03				3.1E-03		3.1E-03	3.1E-03		6.8E-04
ENDOSULFAN I	4.1E-05	4.1E-05		4.1E-05						3.5E-06
GAMMA-BHC (LINDANE)	2.8E-04			2.8E-04	2.8E-04					1.4E-05
HEPTACHLOR EPOXIDE	9.8E-03				9.8E-03					1.8E-03
ALUMINUM	4.1E-01									3.3E-03
ARSENIC	1.3E+00		1.3E+00							5.7E-04
BERYLLIUM	1.3E-02									5.2E-04
CADMIUM	2.9E-01			2.9E-01						1.2E-03
CHROMIUM	4.7E+00			4.7E+00						9.5E-02
COBALT	4.4E-03	4.4E-03							4.4E-03	3.6E-05
COPPER	8.2E-03	8.2E-03		8.2E-03	8.2E-03					5.6E-06
IRON	3.5E+00				3.5E+00	3.5E+00				2.9E-02
LEAD	N/A	N/A					N/A			N/A
NICKEL	4.1E-02						4.1E-02			1.1E-04
SILVER	2.0E-03		2.0E-03							4.0E-06
VANADIUM	1.6E+00									6.5E-02
	HI BY TARGET ORGAN	1.3E-02	1.3E+00	5.0E+00	3.6E+00	3.5E+00	4.4E-02	3.1E-03	4.4E-03	

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 69

**CENTRAL TENDENCY NONCARCINOGENIC HQS, FUTURE INDUSTRIAL RECEPTORS - SITE 23
GROUNDWATER, AMENDED RISK
NWS EARLE, COLTS NECK, NEW JERSEY**

SUBSTANCE	GROUNDWATER INGESTION	GROUNDWATER INGESTION BY TARGET ORGAN							GROUNDWATER DERMAL CONTACT	
		CARDIO- VASCULAR SYSTEM	SKIN	KIDNEY	LIVER	DIGESTIVE SYSTEM	CENTRAL NERVOUS SYSTEM	REPRO- DUCTIVE SYSTEM		THYROID
4,4'-DDT	4.1E-04				4.1E-04					1.8E-03
CHLOROFORM	3.2E-03			3.2E-03	3.2E-03					4.5E-05
DIELDRIN	1.9E-03				1.9E-03		1.9E-03	1.9E-03		6.0E-04
ENDOSULFAN I	1.6E-05	1.6E-05		1.6E-05						2.0E-06
GAMMA-BHC (LINDANE)	1.7E-04			1.7E-04	1.7E-04					1.3E-05
HEPTACHLOR EPOXIDE	6.0E-03				6.0E-03					1.6E-03
ALUMINUM	2.5E-01									2.9E-03
ARSENIC	5.1E-01		5.1E-01							3.1E-04
BERYLLIUM	4.5E-03									2.6E-04
CADMIUM	8.6E-02			8.6E-02						5.0E-04
CHROMIUM	1.6E+00			1.6E+00						4.8E-02
COBALT	2.0E-03	2.0E-03							2.0E-03	2.4E-05
COPPER	3.3E-03	3.3E-03		3.3E-03	3.3E-03					3.2E-06
IRON	1.3E+00				1.3E+00	1.3E+00				1.5E-02
LEAD	N/A	N/A					N/A			N/A
NICKEL	1.8E-02						1.8E-02			6.9E-05
SILVER	7.8E-04		7.8E-04							2.3E-06
VANADIUM	5.6E-01									3.3E-02
HI BY TARGET ORGAN		5.3E-03	5.1E-01	1.7E+00	1.3E+00	1.3E+00	2.0E-02	1.9E-03	2.0E-03	

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 70

**RME CARCINOGENIC RISK TO FUTURE RESIDENTIAL RECEPTORS - SITE 23
SUBSURFACE SOIL, AMENDED RISK
NWS EARLE, COLTS NECK, NEW JERSEY**

SUBSTANCE	SUBSURFACE SOIL INGESTION - LIFETIME	SUBSURFACE SOIL DERMAL CONTACT - LIFETIME	INHALATION OF COPCS IN FUGITIVE DUST - LIFETIME
ACENAPHTHENE	N/A	N/A	N/A
BENZO(A)ANTHRACENE	9.3E-06	N/A	2.7E-10
BENZO(A)PYRENE	6.4E-05	N/A	1.9E-09
BENZO(B)FLUORANTHENE	6.9E-06	N/A	2.0E-10
BENZO(G,H,I)PERYLENE	N/A	N/A	N/A
BENZO(K)FLUORANTHENE	2.5E-07	N/A	7.5E-12
BIS(2-ETHYLHEXYL)PHTHALATE	8.5E-09	N/A	2.2E-13
CARBAZOLE	4.0E-08	N/A	1.0E-12
CHRYSENE	9.3E-08	N/A	2.7E-12
DIBENZO(A,H)ANTHRACENE	N/A	N/A	4.8E-11
DIBENZOFURAN	N/A	N/A	N/A
FLUORANTHENE	N/A	N/A	N/A
FLUORENE	N/A	N/A	N/A
GAMMA-BHC (LINDANE)	N/A	N/A	5.6E-16
INDENO(1,2,3-CD)PYRENE	2.8E-06	N/A	8.3E-11
PHENANTHRENE	N/A	N/A	N/A
PYRENE	N/A	N/A	N/A
ARSENIC	3.8E-04	2.8E-04	1.2E-08
CADMIUM	N/A	N/A	7.0E-11
CHROMIUM	N/A	N/A	3.0E-08
VANADIUM	N/A	N/A	N/A
TOTAL RISK	4.6E-04	2.8E-04	4.5E-08

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

* CANCER RISK FOR PAHS NOT ESTIMATED FOR DERMAL EXPOSURE

TABLE 71

CENTRAL TENDENCY CARCINOGENIC RISK TO FUTURE RESIDENTIAL RECEPTORS - SITE 23
 SUBSURFACE SOIL, AMENDED RISK
 NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SUBSURFACE SOIL INGESTION - LIFETIME	SUBSURFACE SOIL DERMAL CONTACT - LIFETIME	INHALATION OF COPCS IN FUGITIVE DUST - LIFETIME
ACENAPHTHENE	N/A	N/A	N/A
BENZO(A)ANTHRACENE	1.5E-06	N/A	8.5E-11
BENZO(A)PYRENE	1.0E-05	N/A	5.8E-10
BENZO(B)FLUORANTHENE	1.1E-06	N/A	6.3E-11
BENZO(G,H,I)PERYLENE	N/A	N/A	N/A
BENZO(K)FLUORANTHENE	4.1E-08	N/A	2.3E-12
BIS(2-ETHYLHEXYL)PHTHALATE	1.4E-09	N/A	6.7E-14
CARBAZOLE	6.5E-09	N/A	3.2E-13
CHRYSENE	1.5E-08	N/A	8.5E-13
DIBENZO(A,H)ANTHRACENE	N/A	N/A	1.5E-11
DIBENZOFURAN	N/A	N/A	N/A
FLUORANTHENE	N/A	N/A	N/A
FLUORENE	N/A	N/A	N/A
GAMMA-BHC (LINDANE)	N/A	N/A	1.7E-16
INDENO(1,2,3-CD)PYRENE	4.5E-07	N/A	2.6E-11
PHENANTHRENE	N/A	N/A	N/A
PYRENE	N/A	N/A	N/A
ARSENIC	3.9E-05	5.7E-05	2.3E-09
CADMIUM	N/A	N/A	2.2E-11
CHROMIUM	N/A	N/A	7.3E-09
VANADIUM	N/A	N/A	N/A
TOTAL RISK	5.3E-05	5.7E-05	1.0E-08

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

* CANCER RISK FOR PAHS NOT ESTIMATED FOR DERMAL EXPOSURE

TABLE 72

RME NONCARCINOGENIC HQS, FUTURE RESIDENTIAL RECEPTORS - SITE 23
 SUBSURFACE SOIL, AMENDED RISK
 NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SUBSURFACE SOIL INGESTION - CHILD	SUBSURFACE SOIL INGESTION BY TARGET ORGAN						SUBSURFACE SOIL DERMAL CONTACT - CHILD	INHALATION OF COPCS IN FUGITIVE DUST - CHILD
		CARDIO- VASCULAR SYSTEM	SKIN	KIDNEY	LIVER	CENTRAL NERVOUS SYSTEM	REPRO- DUCTIVE SYSTEM		
ACENAPHTHENE	2.7E-04			2.7E-04	2.7E-04			N/A	4.0E-09
BENZO(A)ANTHRACENE	N/A							N/A	N/A
BENZO(A)PYRENE	N/A							N/A	N/A
BENZO(B)FLUORANTHENE	N/A							N/A	N/A
BENZO(G,H,I)PERYLENE	N/A							N/A	N/A
BENZO(K)FLUORANTHENE	N/A							N/A	N/A
BIS(2-ETHYLHEXYL)PHTHALATE	2.5E-04				2.5E-04		2.5E-04	N/A	3.7E-09
CARBAZOLE	N/A							N/A	N/A
CHRYSENE	N/A							N/A	N/A
DIBENZO(A,H)ANTHRACENE	N/A							N/A	N/A
DIBENZOFURAN	N/A							N/A	N/A
FLUORANTHENE	5.1E-03	5.1E-03		5.1E-03	5.1E-03			N/A	7.7E-08
FLUORENE	N/A	N/A				N/A		N/A	N/A
GAMMA-BHC (LINDANE)	N/A			N/A	N/A			N/A	N/A
INDENO(1,2,3-CD)PYRENE	N/A							N/A	N/A
PHENANTHRENE	N/A							N/A	N/A
PYRENE	5.8E-03			5.8E-03				N/A	8.7E-08
ARSENIC	6.9E-01		6.9E-01					4.3E-01	1.0E-05
CADMIUM	3.6E-02			3.6E-02				7.0E-03	1.5E-06
CHROMIUM	2.3E-01			2.3E-01				N/A	3.5E-06
VANADIUM	3.3E-01							N/A	4.9E-06
	HI BY TARGET ORGAN	5.1E-03	6.9E-01	2.8E-01	5.7E-03		2.5E-04		

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 73

CENTRAL TENDENCY NONCARCINOGENIC HQS, FUTURE RESIDENTIAL RECEPTORS - SITE 23
 SUBSURFACE SOIL, AMENDED RISK
 NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SUBSURFACE SOIL INGESTION - CHILD	SUBSURFACE SOIL INGESTION BY TARGET ORGAN						SUBSURFACE SOIL DERMAL CONTACT - CHILD	INHALATION OF COPCS IN FUGITIVE DUST - CHILD
		CARDIO- VASCULAR SYSTEM	SKIN	KIDNEY	LIVER	CENTRAL NERVOUS SYSTEM	REPRO- DUCTIVE SYSTEM		
ACENAPHTHENE	1.3E-04			1.3E-04	1.3E-04			N/A	4.0E-09
BENZO(A)ANTHRACENE	N/A							N/A	N/A
BENZO(A)PYRENE	N/A							N/A	N/A
BENZO(B)FLUORANTHENE	N/A							N/A	N/A
BENZO(G,H,I)PERYLENE	N/A							N/A	N/A
BENZO(K)FLUORANTHENE	N/A							N/A	N/A
BIS(2-ETHYLHEXYL)PHTHALATE	1.2E-04				1.2E-04		1.2E-04	N/A	3.7E-09
CARBAZOLE	N/A							N/A	N/A
CHRYSENE	N/A							N/A	N/A
DIBENZO(A,H)ANTHRACENE	N/A							N/A	N/A
DIBENZOFURAN	N/A							N/A	N/A
FLUORANTHENE	2.6E-03	2.6E-03		2.6E-03	2.6E-03			N/A	7.7E-08
FLUORENE	N/A	N/A				N/A		N/A	N/A
GAMMA-BHC (LINDANE)	N/A			N/A	N/A			N/A	N/A
INDENO(1,2,3-CD)PYRENE	N/A							N/A	N/A
PHENANTHRENE	N/A							N/A	N/A
PYRENE	2.9E-03			2.9E-03				N/A	8.7E-08
ARSENIC	2.2E-01		2.2E-01					2.8E-01	6.7E-06
CADMIUM	1.8E-02			1.8E-02				7.0E-03	1.5E-06
CHROMIUM	9.0E-02			9.0E-02				N/A	2.7E-06
VANADIUM	1.1E-01							N/A	3.2E-06
	HI BY TARGET ORGAN	2.6E-03	2.2E-01	1.1E-01	2.8E-03		1.2E-04		

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 74

RME CARCINOGENIC RISK TO FUTURE RESIDENTIAL RECEPTORS - SITE 23
GROUNDWATER, AMENDED RISK
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	GROUNDWATER INGESTION - LIFETIME	GROUNDWATER DERMAL CONTACT - LIFETIME	INHALATION OF VOAS IN GW - ADULT
4,4'-DDT	1.7E-07	4.0E-06	3.1E-07
CHLOROFORM	5.4E-07	4.0E-08	7.0E-06
DIELDRIN	3.8E-06	6.2E-06	7.0E-06
ENDOSULFAN I	N/A	N/A	N/A
GAMMA-BHC (LINDANE)	1.7E-07	6.3E-08	4.2E-07
HEPTACHLOR EPOXIDE	1.8E-06	2.4E-06	7.3E-07
ALUMINUM	N/A	N/A	N/A
ARSENIC	9.0E-04	2.1E-06	N/A
BERYLLIUM	4.2E-04	9.4E-05	N/A
CADMIUM	N/A	N/A	N/A
CHROMIUM	N/A	N/A	N/A
COBALT	N/A	N/A	N/A
COPPER	N/A	N/A	N/A
IRON	N/A	N/A	N/A
LEAD	N/A	N/A	N/A
NICKEL	N/A	N/A	N/A
SILVER	N/A	N/A	N/A
VANADIUM	N/A	N/A	N/A
TOTAL RISK	1.3E-03	1.1E-04	1.5E-05

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 75

**CENTRAL TENDENCY CARCINOGENIC RISK TO FUTURE RESIDENTIAL RECEPTORS - SITE 23
GROUNDWATER, AMENDED RISK
NWS EARLE, COLTS NECK, NEW JERSEY**

SUBSTANCE	GROUNDWATER INGESTION - LIFETIME	GROUNDWATER DERMAL CONTACT - LIFETIME	INHALATION OF VOAS IN GW - ADULT
4,4'-DDT	2.5E-08	6.3E-07	1.8E-08
CHLOROFORM	7.0E-08	5.6E-09	3.6E-07
DIELDRIN	5.5E-07	9.8E-07	4.0E-07
ENDOSULFAN I	N/A	N/A	N/A
GAMMA-BHC (LINDANE)	2.4E-08	1.0E-08	2.4E-08
HEPTACHLOR EPOXIDE	2.5E-07	3.8E-07	4.2E-08
ALUMINUM	N/A	N/A	N/A
ARSENIC	8.2E-05	1.8E-07	N/A
BERYLLIUM	3.4E-05	7.1E-06	N/A
CADMIUM	N/A	N/A	N/A
CHROMIUM	N/A	N/A	N/A
COBALT	N/A	N/A	N/A
COPPER	N/A	N/A	N/A
IRON	N/A	N/A	N/A
LEAD	N/A	N/A	N/A
NICKEL	N/A	N/A	N/A
SILVER	N/A	N/A	N/A
VANADIUM	N/A	N/A	N/A
TOTAL RISK	1.2E-04	9.3E-06	8.4E-07

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 76

RME NONCARCINOGENIC HQS, FUTURE RESIDENTIAL RECEPTORS - SITE 23
 GROUNDWATER, AMENDED RISK
 NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	GROUNDWATER INGESTION - CHILD	GROUNDWATER INGESTION BY TARGET ORGAN							
		CARDIO- VASCULAR SYSTEM	SKIN	KIDNEY	LIVER	DIGESTIVE SYSTEM	CENTRAL NERVOUS SYSTEM	REPRO- DUCTIVE SYSTEM	THYROID
4,4'-DDT	4.3E-03				4.3E-03				
CHLOROFORM	3.8E-02			3.8E-02	3.8E-02				
DIELDRIN	2.0E-02				2.0E-02		2.0E-02	2.0E-02	
ENDOSULFAN I	2.7E-04	2.7E-04		2.7E-04					
GAMMA-BHC (LINDANE)	1.8E-03			1.8E-03	1.8E-03				
HEPTACHLOR EPOXIDE	6.4E-02				6.4E-02				
ALUMINUM	2.7E+00								
ARSENIC	8.6E+00		8.6E+00						
BERYLLIUM	8.3E-02								
CADMIUM	1.9E+00			1.9E+00					
CHROMIUM	3.0E+01			3.0E+01					
COBALT	2.9E-02	2.9E-02							2.9E-02
COPPER	5.4E-02	5.4E-02		5.4E-02	5.4E-02				
IRON	2.3E+01				2.3E+01	2.3E+01			
LEAD	N/A	N/A					N/A		
NICKEL	2.7E-01						2.7E-01		
SILVER	1.3E-02		1.3E-02						
VANADIUM	1.0E+01								
	HI BY TARGET ORGAN	8.3E-02	8.6E+00	3.2E+01	2.3E+01	2.3E+01	2.9E-01	2.0E-02	2.9E-02

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 77

RME NONCARCINOGENIC HQS, FUTURE RESIDENTIAL RECEPTORS - SITE 23
 GROUNDWATER, AMENDED RISK
 NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	GROUNDWATER DERMAL CONTACT - CHILD	GROUNDWATER DERMAL CONTACT BY TARGET ORGAN								INHALATION OF VOAS IN GW - ADULT
		CARDIO- VASCULAR SYSTEM	SKIN	KIDNEY	LIVER	DIGESTIVE SYSTEM	CENTRAL NERVOUS SYSTEM	REPRO- DUCTIVE SYSTEM	THYROID	
4,4'-DDT	7.9E-02				7.9E-02					N/A
CHLOROFORM	2.2E-03			2.2E-03	2.2E-03					N/A
DIELDRIN	2.6E-02				2.6E-02		2.6E-02	2.6E-02		N/A
ENDOSULFAN I	1.3E-04	1.3E-04		1.3E-04						N/A
GAMMA-BHC (LINDANE)	5.5E-04			5.5E-04	5.5E-04					N/A
HEPTACHLOR EPOXIDE	6.8E-02				6.8E-02					N/A
ALUMINUM	1.0E-01									N/A
ARSENIC	1.8E-02		1.8E-02							N/A
BERYLLIUM	1.6E-02									N/A
CADMIUM	3.7E-02			3.7E-02						N/A
CHROMIUM	3.0E+00		3.0E+00	3.0E+00						N/A
COBALT	1.1E-03	1.1E-03	1.1E-03						1.1E-03	N/A
COPPER	1.7E-04	1.7E-04		1.7E-04	1.7E-04					N/A
IRON	9.0E-01				9.0E-01	9.0E-01				N/A
LEAD	N/A	N/A					N/A			N/A
NICKEL	3.4E-03						3.4E-03			N/A
SILVER	1.2E-04		1.2E-04							N/A
VANADIUM	2.0E+00									N/A
	HI BY TARGET ORGAN	1.4E-03	3.0E+00	3.0E+00	1.1E+00	9.0E-01	3.0E-02	2.6E-02	1.1E-03	

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 78

**CENTRAL TENDENCY NONCARCINOGENIC HQS, FUTURE RESIDENTIAL RECEPTORS - SITE 23
GROUNDWATER, AMENDED RISK
NWS EARLE, COLTS NECK, NEW JERSEY**

SUBSTANCE	GROUNDWATER INGESTION - CHILD	GROUNDWATER INGESTION BY TARGET ORGAN							
		CARDIO- VASCULAR SYSTEM	SKIN	KIDNEY	LIVER	DIGESTIVE SYSTEM	CENTRAL NERVOUS SYSTEM	REPRO- DUCTIVE SYSTEM	THYROID
4,4'-DDT	2.0E-03				2.0E-03				
CHLOROFORM	1.6E-02			1.6E-02	1.6E-02				
DIELDRIN	9.6E-03				9.6E-03		9.6E-03	9.6E-03	
ENDOSULFAN I	8.2E-05	8.2E-05		8.2E-05					
GAMMA-BHC (LINDANE)	8.6E-04			8.6E-04	8.6E-04				
HEPTACHLOR EPOXIDE	3.0E-02				3.0E-02				
ALUMINUM	1.2E+00								
ARSENIC	2.5E+00		2.5E+00						
BERYLLIUM	2.2E-02								
CADMIUM	4.3E-01			4.3E-01					
CHROMIUM	8.1E+00			8.1E+00					
COBALT	1.0E-02	1.0E-02							1.0E-02
COPPER	1.6E-02	1.6E-02		1.6E-02	1.6E-02				
IRON	6.4E+00				6.4E+00	6.4E+00			
LEAD	N/A	N/A					N/A		
NICKEL	8.8E-02						8.8E-02		
SILVER	3.9E-03		3.9E-03						
VANADIUM	2.8E+00								
	HI BY TARGET ORGAN	2.6E-02	2.5E+00	8.6E+00	6.5E+00	6.4E+00	9.8E-02	9.6E-03	1.0E-02

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 79

CENTRAL TENDENCY NONCARCINOGENIC HQS, FUTURE RESIDENTIAL RECEPTORS - SITE 23
 GROUNDWATER, AMENDED RISK
 NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	GROUNDWATER DERMAL CONTACT - CHILD	GROUNDWATER DERMAL CONTACT BY TARGET ORGAN							INHALATION OF VOAS IN GW - ADULT	
		CARDIO- VASCULAR SYSTEM	SKIN	KIDNEY	LIVER	DIGESTIVE SYSTEM	CENTRAL NERVOUS SYSTEM	REPRO- DUCTIVE SYSTEM		THYROID
4,4'-DDT	5.3E-02				5.3E-02					N/A
CHLOROFORM	1.3E-03			1.3E-03	1.3E-03					N/A
DIELDRIN	1.7E-02				1.7E-02		1.7E-02	1.7E-02		N/A
ENDOSULFAN I	5.8E-05	5.8E-05		5.8E-05						N/A
GAMMA-BHC (LINDANE)	3.7E-04			3.7E-04	3.7E-04					N/A
HEPTACHLOR EPOXIDE	4.5E-02				4.5E-02					N/A
ALUMINUM	7.0E-02									N/A
ARSENIC	7.5E-03		7.5E-03							N/A
BERYLLIUM	6.2E-03									N/A
CADMIUM	1.2E-02			1.2E-02						N/A
CHROMIUM	1.1E+00		1.1E+00	1.1E+00						N/A
COBALT	5.6E-04	5.6E-04	5.6E-04						5.6E-04	N/A
COPPER	7.6E-05	7.6E-05		7.6E-05	7.6E-05					N/A
IRON	3.6E-01				3.6E-01	3.6E-01				N/A
LEAD	N/A	N/A					N/A			N/A
NICKEL	1.6E-03						1.6E-03			N/A
SILVER	5.4E-05		5.4E-05							N/A
VANADIUM	7.8E-01									N/A
HI BY TARGET ORGAN		7.0E-04	1.1E+00	1.1E+00	4.8E-01	3.6E-01	1.9E-02	1.7E-02	5.6E-04	

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 80
RME CARCINOGENIC RISK, WADING, FUTURE RECREATIONAL RECEPTORS - SITE 23
SEDIMENT
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SEDIMENT INGESTION	SEDIMENT DERMAL CONTACT
4,4'-DDD	1.3E-11	3.2E-12
4,4'-DDT	1.9E-11	4.8E-12
ALPHA-CHLORDANE	7.8E-12	1.9E-12
ANTHRACENE	N/A	N/A
BENZO(A)ANTHRACENE	4.7E-09	1.9E-09
BENZO(A)PYRENE	3.8E-08	5.1E-08
BENZO(B)FLUORANTHENE	5.2E-09	2.1E-09
BENZO(G,H,I)PERYLENE	N/A	N/A
BENZO(K)FLUORANTHENE	1.2E-10	4.8E-11
BIS(2-ETHYLHEXYL)PHTHALATE	4.2E-11	1.6E-11
CHRYSENE	5.0E-11	2.0E-11
DIBENZO(A,H)ANTHRACENE	4.3E-09	8.6E-09
DIETHYLPHTHALATE	1.1E-08	N/A
1,2,4-TRICHLOROBENZENE	3.8E-07	N/A
FLUORANTHENE	N/A	N/A
FLUORENE	N/A	N/A
GAMMA-CHLORDANE	5.4E-12	1.3E-12
INDENO(1,2,3-CD)PYRENE	1.6E-09	6.3E-10
PHENANTHRENE	N/A	N/A
PYRENE	N/A	N/A
ARSENIC	7.7E-08	3.2E-09
BARIUM	N/A	N/A
CADMIUM	N/A	N/A
CHROMIUM	N/A	N/A
IRON	N/A	N/A
LEAD	N/A	N/A
MANGANESE	N/A	N/A
ZINC	N/A	N/A
TOTAL RISK	5.2E-07	6.7E-08

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL
 * CANCER RISK FOR PAHS NOT ESTIMATED FOR DERMAL EXPOSURE

TABLE 81

RME NONCARCINOGENIC HQS, WADING, FUTURE RECREATIONAL RECEPTORS - SITE 23
SEDIMENT
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SEDIMENT INGESTION	SEDIMENT DERMAL CONTACT
4,4'-DDD	NA	NA
4,4'-DDT	1.3E-06	3.3E-07
ALPHA-CHLORDANE	1.2E-06	2.9E-07
ANTHRACENE	2.8E-08	1.1E-08
BENZO(A)ANTHRACENE	NA	NA
BENZO(A)PYRENE	NA	NA
BENZO(B)FLUORANTHENE	NA	NA
BENZO(G,H,I)PERYLENE	NA	NA
BENZO(K)FLUORANTHENE	NA	NA
BIS(2-ETHYLHEXYL)PHTHALATE	1.7E-06	6.9E-07
CHRYSENE	NA	NA
DIBENZ(A,H)ANTHRACENE	NA	NA
DIETHYLPHTHALATE	2.9E-08	1.1E-08
1,2,4-TRICHLOROBENZENE	9.6E-07	3.8E-07
FLUORANTHENE	2.3E-06	9.1E-07
FLUORENE	1.6E-07	6.3E-08
GAMMA-CHLORDANE	8.1E-07	2.0E-07
INDENO(1,2,3-CD)PYRENE	NA	NA
PHENANTHRENE	NA	NA
PYRENE	3.3E-06	1.3E-06
ARSENIC	2.0E-03	8.3E-05
BARIUM	3.1E-05	3.0E-05
CADMIUM	3.1E-04	2.4E-04
CHROMIUM	2.1E-03	4.1E-03
IRON	5.5E-03	4.4E-03
LEAD	NA	NA
MANGANESE	2.5E-04	3.4E-04
ZINC	3.0E-05	4.8E-06

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 82
RME CARCINOGENIC RISK, WADING, FUTURE RECREATIONAL RECEPTORS - SITE 23
SURFACE WATER
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SURFACE WATER INGESTION	SURFACE WATER DERMAL CONTACT
BIS(2-ETHYLHEXYL)PHTHALAT	1.5E-10	3.7E-09
GAMMA-BHC (LINDANE)	9.7E-11	2.5E-10
ALUMINUM	N/A	N/A
BARIUM	N/A	N/A
CADMIUM	N/A	N/A
CHROMIUM	N/A	N/A
COBALT	N/A	N/A
COPPER	N/A	N/A
IRON	N/A	N/A
LEAD	N/A	N/A
MERCURY	N/A	N/A
VANADIUM	N/A	N/A
ZINC	N/A	N/A
TOTAL RISK	2.5E-10	3.9E-09

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 83

RME NONCARCINOGENIC HQS, WADING, FUTURE RECREATIONAL RECEPTORS - SITE 23
SURFACE WATER
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SURFACE WATER INGESTION	SURFACE WATER DERMAL CONTACT
BIS(2-ETHYLHEXYL)PHTHALAT	6.4E-06	1.5E-04
GAMMA-BHC (LINDANE)	2.9E-06	7.4E-06
ALUMINUM	4.7E-04	4.4E-04
BARIUM	5.5E-04	6.4E-04
CADMIUM	2.6E-04	2.4E-04
CHROMIUM	7.5E-04	1.7E-03
COBALT	4.0E-06	3.8E-06
COPPER	5.1E-05	4.0E-06
IRON	1.4E-02	1.3E-02
LEAD	N/A	N/A
MERCURY	7.2E-05	4.8E-05
VANADIUM	3.4E-04	1.6E-03
ZINC	1.1E-04	2.0E-05

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 84

**SUMMARY OF ESTIMATED CANCER RISKS AND NONCARCINOGENIC HAZARD INDICIES - SITE 23
NWS EARLE, COLTS NECK, NEW JERSEY**

Medium	Exposure Routes	Estimated Incremental Cancer Risk				Estimated Hazard Index***				
		Current Industrial Employee	Future Industrial Employee	Future Lifetime Resident	Future Recreational Child	Current Industrial Employee	Future Industrial Employee	Future Resident		Future Recreational Child
								Child	Adult	
Surface Soil	Incidental Ingestion	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A
	Dermal Contact	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A
	Inhalation of Fugitive Dust	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A
Subsurface Soil	Incidental Ingestion	N/A	1.0E-04 [~]	4.6E-04 [~]	N/A	N/A	9.9E-02 [~]	6.9E-01@	N/A	N/A
	Dermal Contact	N/A	8.4E-05 [~]	2.8E-04 [~]	N/A	N/A	5.3E-02 [~]	4.3E-01 [~]	N/A	N/A
	Inhalation of Fugitive Dust	N/A	7.3E-08 [~]	4.5E-08 [~]	N/A	N/A	1.9E-05 [~]	2.0E-05 [~]	N/A	N/A
Sediment	Incidental Ingestion	N/A	N/A	N/A	5.2E-07	N/A	N/A	N/A	N/A	1.0E-02
	Dermal Contact	N/A	N/A	N/A	6.7E-08	N/A	N/A	N/A	N/A	9.2E-03
Groundwater	Ingestion	N/A	3.1E-04 [~]	1.3E-03 [~]	N/A	N/A	5.0E+00@	3.2E+01@	N/A	N/A
	Dermal Contact	N/A	4.5E-06 [~]	1.1E-04 [~]	N/A	N/A	2.0E-01 [~]	3.0E+00@	N/A	N/A
	Inhalation of Volatiles*	N/A	N/A	1.5E-05 [~]	N/A	N/A	N/A	N/A	N/A**	N/A
Surface Water	Incidental Ingestion	N/A	N/A	N/A	2.5E-10	N/A	N/A	N/A	N/A	1.7E-02
	Dermal Contact	N/A	N/A	N/A	3.9E-09	N/A	N/A	N/A	N/A	1.8E-02
TOTAL		-	5.0E-04	2.2E-03	5.9E-07	-	5.4E+00	3.6E+01	-	5.4E-02

N/A = Not applicable because this media is not associated with this potential receptor

N/R = Central Tendency calculation not required

N/S = Not sampled

* = During Showering, Adult Residents Only

** = No volatile noncarcinogens were detected in groundwater

*** = Hazard Indices (i.e., summation of hazard quotients) are used only for comparison purposes and do not reflect actual additive noncarcinogenic effects

[~] - Value from amended risk assessment.

@ - Result is the maximum of the HIs among the affected target organs from the amended risk assessment.

TABLE 85
SUMMARY OF CENTRAL TENDENCY CANCER RISKS AND NONCARCINOGENIC HAZARD INDICIES - SITE 23
NWS EARLE, COLTS NECK, NEW JERSEY

Medium	Exposure Routes	Estimated Incremental Cancer Risk				Estimated Hazard Index***				
		Current Industrial Employee	Future Industrial Employee	Future Lifetime Resident	Future Recreational Child	Current Industrial Employee	Future Industrial Employee	Future Resident		Future Recreational Child
								Child	Adult	
Surface Soil	Incidental Ingestion	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A
	Dermal Contact	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A
	Inhalation of Fugitive Dust	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A
Subsurface Soil	Incidental Ingestion	N/A	6.2E-06 [~]	5.3E-05 [~]	N/A	N/A	N/R	2.2E-01@	N/A	N/A
	Dermal Contact	N/A	9.1E-06 [~]	5.7E-05 [~]	N/A	N/A	N/R	2.8E-01 [~]	N/A	N/A
	Inhalation of Fugitive Dust	N/A	9.9E-09 [~]	1.0E-08 [~]	N/A	N/A	N/R	1.4E-05 [~]	N/A	N/A
Sediment	Incidental Ingestion	N/A	N/A	N/A	N/R	N/A	N/A	N/A	N/A	N/R
	Dermal Contact	N/A	N/A	N/A	N/R	N/A	N/A	N/A	N/A	N/R
Groundwater	Ingestion	N/A	2.1E-05 [~]	1.2E-04 [~]	N/A	N/A	1.7E+00@	8.6E+00@	N/A	N/A
	Dermal Contact	N/A	4.3E-07 [~]	9.3E-06 [~]	N/A	N/A	1.0E-01 [~]	1.1E+00@	N/A	N/A
	Inhalation of Volatiles*	N/A	N/A	8.4E-07 [~]	N/A	N/A	N/A	N/A	N/A**	N/A
Surface Water	Incidental Ingestion	N/A	N/A	N/A	N/R	N/A	N/A	N/A	N/A	N/R
	Dermal Contact	N/A	N/A	N/A	N/R	N/A	N/A	N/A	N/A	N/R
TOTAL		-	3.7E-05	2.4E-04	-	-	1.8E+00	1.0E+01	-	-

N/A = Not applicable because this media is not associated with this potential receptor

N/R - Central Tendency calculation is not required

N/S = Not sampled

* = During Showering, Adult Residents Only

** = No volatile noncarcinogens were detected in groundwater

*** = Hazard Indices (i.e., summation of hazard quotients) are used only for comparison purposes and do not reflect actual additive noncarcinogenic effects

[~] - Value from amended risk assessment.

@ - Amended result is maximum HI for individual target organs.

TABLE 86
SURFACE WATER CONTAMINANTS OF POTENTIAL CONCERN - SITE 23
NWS EARLE, COLTS NECK, NEW JERSEY

Contaminant of Potential Concern (COPC)	Frequency of Detection	Background Concentration (µg/L)	Maximum Concentration (µg/L)	Ecotox Threshold (µg/L)	Hazard Quotient	Reason for Retention or Elimination as Final COPC
Inorganics						
Aluminum	3/3	409	3670	87	42.2	Retained-HQ > 1
Barium	3/3	34	301	3.9	77.2	Retained-HQ > 1
Cadmium	1/3	0.18	1	1	1.0	Retained-HQ > 1
Chromium	2/3	2.6	29.4	10	2.94	Retained-HQ > 1
Cobalt	3/3	1.9	1.9	3	0.63	Eliminated-Does not exceed threshold
Copper	3/3	9.8	16.1	11	1.46	Retained-HQ > 1
Lead	1/3	4.4	10.3	2.5	4.12	Retained-HQ > 1
Manganese	3/3	55.5	36.1	80	0.45	Eliminated-Does not exceed threshold
Mercury	3/3	0.028	0.17	1.3	0.13	Eliminated-Does not exceed threshold
Vanadium	1/3	0.9	18.8	19	0.99	Eliminated-Does not exceed threshold
Zinc	1/3	29.4	253	100	2.53	Retained-HQ > 1
Organics						
Bis(2-ethylhexyl)phthalate	1/1	ND	1.0	32	0.03	Eliminated-Does not exceed threshold
Gamma-BHC (Lindane)	1/1	ND	0.0068	0.08	0.09	Eliminated-Does not exceed threshold

ND = None detected

TABLE 87

 SEDIMENT CONTAMINANTS OF POTENTIAL CONCERN - SITE 23
 NWS EARLE, COLTS NECK, NEW JERSEY

Contaminant of Potential Concern (COPC)	Frequency of Detection	Background Concentration (mg/kg) ¹	Maximum Concentration (mg/kg)	Ecotox Threshold ¹ (mg/kg)	Hazard Quotient	Reason for Retention or Elimination as Final COPC ²
Inorganics						
Aluminum	5/5	3940	2660	NA		Retained-No suitable threshold available
Arsenic	5/5	6.2	4.7	8.2	0.57	Eliminated-Does not exceed threshold
Barium	5/5	10.6	16.7	40	0.42	Eliminated-Does not exceed threshold
Cadmium	2/5	ND	1.2	1.2/9.6	1.0/0.13	Retained-HQ > 1
Chromium	5/5	56	120	81/370	1.48/0.32	Retained-HQ > 1
Copper	5/5	13	6.7	34	0.20	Eliminated-Does not exceed threshold
Lead	5/5	34.3	72.5	47/218	1.54/0.33	Retained-HQ > 1
Manganese	5/5	9.2	9.95	460	0.02	Eliminated-Does not exceed threshold
Mercury	3/5	0.068	0.06	0.15	0.33	Eliminated-Does not exceed threshold
Nickel	4/5	6	4.5	21	0.21	Eliminated-Does not exceed threshold
Vanadium	5/5	42.7	20.8	NA		Retained-No suitable threshold available
Zinc	5/5	26.9	71.3	150	0.48	Eliminated-Does not exceed threshold
Organics ³						
1,2,4-Trichlorobenzene	1/5	ND	75	9200	0.01	Eliminated-Does not exceed threshold
4,4'-DDD	3/5	21	4.85	1.6/46	3.03/0.11	Retained-HQ > 1
4,4'-DDT	1/5	19	6.75	1.6/46	4.22/0.15	Retained-HQ > 1
Alpha-Chlordane	2/5	ND	0.55	7	0.08	Eliminated-Does not exceed threshold
Anthracene	1/5	ND	65	330	0.20	Eliminated-Does not exceed threshold
Benzo(a)anthracene	2/5	560	590	330/1600	1.79/0.37	Retained-HQ > 1
Benzo(a)pyrene	2/5	590	480	430/1600	1.12/0.30	Retained-HQ > 1
Benzo(b)fluoranthene	2/5	490	895	330/1700	2.71/0.53	Retained-HQ > 1
Benzo(g,h,i)perylene	2/5	380	165	330	0.50	Eliminated-Does not exceed threshold
Benzo(k)fluoranthene	2/5	470	150	330	0.45	Eliminated-Does not exceed threshold
Bis(2-ethylhexyl)phthalate	5/5	ND	400	8.9E + 08	4.5E-07	Eliminated-Does not exceed threshold
Chrysene	2/5	940	630	330/2800	1.91/0.23	Retained-HQ > 1
Dibenzo(a,h)anthracene	1/5	ND	54	330	0.16	Eliminated-Does not exceed threshold
Diethylphthalate	1/5	44	180	630	0.29	Eliminated-Does not exceed threshold
Fluoranthene	2/5	1800	1000	2900	0.34	Eliminated-Does not exceed threshold
Fluorene	1/5	190	50	540	0.09	Eliminated-Does not exceed threshold
Gamma-Chlordane	1/5	0.095	0.38	7	0.05	Eliminated-Does not exceed threshold
Indeno(1,2,3-cd)pyrene	2/5	310	200	330	0.61	Eliminated-Does not exceed threshold
Phenanthrene	2/5	1900	725	850	0.08	Eliminated-Does not exceed threshold
Pyrene	2/5	1900	770	660/2600	1.17/0.30	Retained-HQ > 1

ND = None detected

NA = No suitable threshold was available

1 When two values are presented, the left value is the most conservative available and the right value is a less conservative value, if available. In these instances, two HQ values are presented.

2 Contaminants were retained as final COPCs if the most conservative ET value available was exceeded.

3 All organic values are in µg/kg.

TABLE 88
ANALYTICAL RESULTS
CONFIRMATORY SOIL SAMPLES
SITE 23
NWS EARLE
COLTS NECK, NJ

Analyte/Compound	23-CS01	23-CS02	23-CS03	23-CS04	23-CS05	23-CS06	23-CS07	23-CS08	Residential	Non-Residential	Impact to
	(mg/kg)	Dir. Contact (mg/kg) (1)	Dir. Contact (mg/kg) (1)	Groundwater (mg/kg) (1)							
Cyanide	<0.60	<0.61	<0.56	<0.67	<0.61	<0.63	<0.58	1.18	1,100	21,000	NS
Silver	<0.24	<0.24	<0.22	<0.27	<0.24	<0.25	<0.23	<0.22	110	4,100	NS
Aluminum	520.0	2,890.0	690.0	2,840.0	1,280.0	1,630.0	814.0	1,190.0	NS	NS	NS
Arsenic	<1.8	4.0	<1.7	<2.0	<1.8	<1.9	<1.6	<1.7	20	20	NS
Barium	4.5	7.0	2.6	10.8	13.0	5	2.4	4.9	700	47,000	NS
Beryllium	0.06	0.14	<0.04	0.19	0.13	0.18	<0.05	<0.04	1	1	NS
Calcium	201.0	437.0	391.0	357.0	260.0	260.0	209.0	440.0	NS	NS	NS
Cadmium	<0.18	<0.18	<0.17	<0.20	<0.18	<0.19	<0.18	<0.17	1	100	NS
Cobalt	<0.12	0.31	0.34	0.77	0.26	<0.13	<0.12	0.55	NS	NS	NS
Chromium	4.5	13.2	4.3	19.3	9.2	17.0	5.3	3.2	NS	NS	NS
Copper	0.65	2.4	1.4	2.4	2.7	2.4	3.9	0.78	600	600	NS
Iron	2,680.0	1,850.0	609.0	6,240.0	2,960.0	4,190.0	645.0	304.0	NS	NS	NS
Mercury	0.02	<0.01	<0.01	0.020	0.02	0.09	<0.01	0.04	14	270	NS
Potassium	273.0	565.0	141.0	1,010.0	338.0	758.0	130.0	101.0	NS	NS	NS
Magnesium	122.0	326.0	99.6	571.0	177.0	326.0	74.3	81.4	NS	NS	NS
Manganese	1.2	8.5	3.3	12.9	3.5	1.3	1.3	7.6	NS	NS	NS
Sodium	29.3	36.3	29.4	36.2	44.8	27.6	31.6	19.0	NS	NS	NS
Nickel	<1.2	<1.2	<1.1	<1.3	<1.2	<1.3	<1.2	<1.1	250	2,400	NS
Lead	3.4	17.6	4.5	8.2	8.7	6.1	2.2	3.3	400	600	NS
Antimony	5.8	4.1	4.6	3.9	4.3	<2.5	<2.3	<2.2	14	340	NS
Selenium	<1.9	<3.1	<2.8	<2.6	3.8	<3.1	<2.9	<2.8	63	3,100	NS
Thallium	<1.9	<2.4	<1.7	<2.4	<2.4	<1.9	<1.8	<1.7	2	2	NS
Vanadium	8.7	10.6	3.4	22.5	9.5	17.2	3.0	2.6	370	7,100	NS
Zinc	1.6	29.1	11.8	6.2	2.4	4.4	0.91	21.6	1,500	1,500	NS

(1) 7/11/96 CRITERIA
NS = NO STANDARD

Site: 23-01

TABLE 89

**OCCURRENCE AND DISTRIBUTION OF INORGANICS IN SUBSURFACE SOILS AT SITE 24
NWS EARLE, COLTS NECK, NEW JERSEY
(mg/kg)**

SUBSTANCE	BACKGROUND			SITE-RELATED				
	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	2 X AVERAGE BKGD CONCENTRATION	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	AVERAGE CONCENTRATION	MEAN > 2 X BKGD	REPRESENTATIVE CONCENTRATION
ALUMINUM	8 / 8	675 - 5310	5370.00	4 / 4	102 - 911	472.75	NO	911
ARSENIC	8 / 8	1.35 - 14.4	13.29	2 / 4	1.6 - 1.8	1.02	NO	1.8
BARIUM	8 / 8	0.92 - 31	17.92	4 / 4	0.23 - 1.155	0.65	NO	1.155
BERYLLIUM	2 / 8	0.12 - 0.28	0.28	2 / 4	0.035 - 0.044	0.05	NO	0.044
CADMIUM	1 / 8	0.57	0.58	2 / 4	0.27 - 0.62	0.24	NO	0.62
CALCIUM	8 / 8	28.6 - 799	577.55	4 / 4	14.9 - 27.3	22.00	NO	27.3
CHROMIUM	8 / 8	4.7 - 59.5	54.73	4 / 4	0.36 - 4.9	2.32	NO	4.9
COPPER	8 / 8	0.97 - 8.6	8.66	3 / 4	0.39 - 3.4	1.30	NO	3.4
IRON	8 / 8	3745 - 62500	40871.25	4 / 4	238 - 7350	3144.25	NO	7350
LEAD	8 / 8	1.4 - 39.4	24.33	4 / 4	0.47 - 6	2.14	NO	5.19
MAGNESIUM	8 / 8	18.5 - 619	504.05	4 / 4	3.8 - 11.8	8.20	NO	11.8
MANGANESE	8 / 8	2.6 - 214	92.51	4 / 4	0.5 - 1.915	1.12	NO	1.915
MERCURY	8 / 8	0.03 - 0.17	0.13	3 / 4	0.0065 - 0.026	0.01	NO	0.026
NICKEL	4 / 8	1.8 - 7.2	4.75	1 / 4	0.22	0.26	NO	0.22
POTASSIUM	7 / 8	95 - 792	793.35	4 / 4	34.7 - 82.9	55.85	NO	82.9
SODIUM	8 / 8	17.5 - 94.8	79.35	4 / 4	19 - 329.05	98.61	YES	279.40
VANADIUM	8 / 8	11.05 - 64	64.71	4 / 4	0.56 - 2.3	1.67	NO	2.3
ZINC	6 / 8	1.1 - 50.7	31.35	3 / 4	1 - 3.9	4.61	NO	3.9

Note: Selected COPCs are indicated in boldface type.

TABLE 90

COMPARISON OF SUBSURFACE SOIL ANALYTICAL DATA TO ARARS AND TBCs - SITE 24
NWS EARLE, COLTS NECK, NEW JERSEY

SAMPLE NUMBER: LOCATION: DATA SOURCE:	24SB01-05	24SB01-08	24SB01-08-DUP	24SB02-03	24SB02-06	---	ARARS & TBCs		
	24SB01	24SB01	24SB01	24SB02	24SB02	---	NJDEP Soil Residential Direct Contact Cleanup Criteria	NJDEP Soil Non-Residential Direct Contact Cleanup Criteria	NJDEP Soil Impact to Groundwater Cleanup Criteria
	1995 RI	1995 RI	1995 RI	1995 RI	1995 RI		mg/kg	mg/kg	mg/kg
INORGANICS	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg				
aluminum	497	168 J	911	102	381		-	-	-
arsenic	1.8	0.68 U	1.6	0.66 U	0.70 U		20.0	20.0	-
barium	0.70	0.51	1.8	0.23	0.52		700	47000	-
beryllium	0.044	0.035	0.20 U	0.022 U	0.19 U		1.00	1.00	-
cadmium	0.27	0.079 U	0.56 U	0.076 U	0.62 J		1.00	100	-
calcium	14.9	23.5	22.9	22.6	27.3		-	-	-
chromium, total	4.9 J	1.0	4.7	0.36	1.2		-	500	-
copper	3.4	0.52	1.3	0.39	1.0 U		600	600	-
iron	7350	662 J	7830 J	238	743 J		-	-	-
lead	6.0	0.77	1.8	0.47	0.80		400	600	-
magnesium	3.8	6.0	13.2	7.6	11.8		-	-	-
manganese	0.50	0.33	3.5	0.57	1.5		-	-	-
mercury	0.026	0.024	0.0027 J	0.0065	0.0021 U		14.0	270	-
nickel	0.16 U	0.22	1.3 U	0.15 U	1.3 U		250	2400	-
potassium	57.4	77.1	88.7	48.4	34.7		-	-	-
sodium	19.0	643	15.1	22.4	24.0		-	-	-
vanadium	2.3	0.54	2.9	0.56	2.1		370	7100	-
zinc	3.9 J	4.8 R	1.4 J	24.3 R	1.0 J		1500	1500	-

TABLE 90

**COMPARISON OF SUBSURFACE SOIL ANALYTICAL DATA TO ARARS AND TBCS - SITE 24
NWS EARLE, COLTS NECK, NEW JERSEY**

**FINAL
PAGE 2**

Footnotes to sample results:

- U - Compound or element was not detected. Value is the detection limit (inorganics) or quantitation limit (organics).
- UJ - Not detected. Detection limit or quantitation limit shown is considered estimated due to exceedance of data validation quality control criteria.
- No Value - Constituent was not analyzed for in this sample.
- UR - Nondetected result is considered rejected based on exceedance of data validation quality control criteria.
- J - Value is estimated because concentration is below the quantitation limit or because of exceedance of data validation quality control criteria.
- R - Positive result is considered rejected based on exceedance of data validation quality control criteria.
- N - Compound is considered to be tentatively identified based on exceedance of QC criteria for compound identification.
- E - Result exceeds one or more of the selected ARARs.

Footnotes to soil criteria:

- No standard is available for this chemical in this classification.

TABLE 91

**COMPARISON OF SUBSURFACE SOIL MISCELLANEOUS PARAMETERS DATA TO ARARS AND TBCs - SITE 24
NWS EARLE, COLTS NECK, NEW JERSEY**

SAMPLE NUMBER:	24SB01-05	24SB01-08	24SB01-08-DUP	24SB02-03	24SB02-06	ARARS & TBCs			
						NJDEP Soil Residential Direct Contact Cleanup Criteria	NJDEP Soil Non-Residential Direct Contact Cleanup Criteria	NJDEP Soil Impact to Groundwater Cleanup Criteria	
LOCATION:	24SB01	24SB01	24SB01	24SB02	24SB02				
DATA SOURCE:	1995 RI	1995 RI	1995 RI	1995 RI	1995 RI				
MISCELLANEOUS									
moisture	%	7.0	7.2	7.8	4.5	5.7	-	-	-
nitrate nitrogen	mg/kg	1.0 U	0.26 J	0.28 J	0.26 J	0.33 J	-	-	-

TABLE 91

COMPARISON OF SUBSURFACE SOIL MISCELLANEOUS PARAMETERS DATA TO ARARS AND TBCS - SITE 24 NWS EARLE, COLTS NECK, NEW JERSEY

FINAL
PAGE 2

Footnotes to sample results:

- U - Compound or element was not detected. Value is the detection limit (inorganics) or quantitation limit (organics).
- UJ - Not detected. Detection limit or quantitation limit shown is considered estimated due to exceedance of data validation quality control criteria.
- No Value - Constituent was not analyzed for in this sample.
- UR - Nondetected result is considered rejected based on exceedance of data validation quality control criteria.
- J - Value is estimated because concentration is below the quantitation limit or because of exceedance of data validation quality control criteria.
- R - Positive result is considered rejected based on exceedance of data validation quality control criteria.
- N - Compound is considered to be tentatively identified based on exceedance of QC criteria for compound identification.
- E - Result exceeds one or more of the selected ARARs.

Footnotes to soil criteria:

- No standard is available for this chemical in this classification.
- @ - Value is New Jersey guideline for maximum total concentration of all organic compounds in soil (including VOCs, SVOCs, and TPH).

TABLE 92

OCCURRENCE AND DISTRIBUTION OF INORGANICS IN SUBSURFACE SOILS AT SITE 25
 NWS EARLE, COLTS NECK, NEW JERSEY
 (mg/kg)

SUBSTANCE	BACKGROUND			SITE-RELATED				
	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	2 X AVERAGE BKGD CONCENTRATION	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	AVERAGE CONCENTRATION	MEAN > 2 X BKGD	REPRESENTATIVE CONCENTRATION
ALUMINUM	8 / 8	675 - 5310	5370.00	4 / 4	116 - 540	343.75	NO	540
ANTIMONY	NOT DETECTED	-	-	2 / 4	0.56 - 0.79	0.48	YES	0.79
ARSENIC	8 / 8	1.35 - 14.4	13.29	1 / 4	1.2	0.56	NO	1.06
BARIUM	8 / 8	0.92 - 31	17.92	4 / 4	0.24 - 1.6	0.73	NO	1.6
BERYLLIUM	2 / 8	0.12 - 0.28	0.28	2 / 4	0.025 - 0.05	0.02	NO	0.05
CALCIUM	8 / 8	28.6 - 799	577.55	4 / 4	21.8 - 26.2	23.30	NO	25.88
CHROMIUM	8 / 8	4.7 - 59.5	54.73	4 / 4	0.41 - 1.5	0.99	NO	1.5
COPPER	8 / 8	0.97 - 8.6	8.66	4 / 4	0.41 - 4.5	1.76	NO	4.5
IRON	8 / 8	3745 - 62500	40871.25	4 / 4	74.4 - 2580	1049.10	NO	2580
LEAD	8 / 8	1.4 - 39.4	24.33	4 / 4	1 - 39.7	13.30	NO	39.7
MAGNESIUM	8 / 8	18.5 - 619	504.05	4 / 4	4.3 - 6.7	6.00	NO	6.7
MANGANESE	8 / 8	2.6 - 214	92.51	4 / 4	1.7 - 5.7	2.95	NO	5.7
MERCURY	8 / 8	0.03 - 0.17	0.13	4 / 4	0.011 - 0.023	0.02	NO	0.023
NICKEL	4 / 8	1.8 - 7.2	4.75	2 / 4	0.28 - 0.3	0.19	NO	0.3
POTASSIUM	7 / 8	95 - 792	793.35	2 / 4	43.8 - 113	47.11	NO	113
SODIUM	8 / 8	17.5 - 94.8	79.35	4 / 4	19.4 - 772	379.10	YES	772
VANADIUM	8 / 8	11.05 - 64	64.71	4 / 4	0.26 - 2.7	1.27	NO	2.7
ZINC	6 / 8	1.1 - 50.7	31.35	2 / 4	1.2 - 3.4	3.09	NO	3.4

Note: Selected COPCs are indicated in boldface type.

TABLE 93

COMPARISON OF SUBSURFACE SOIL ANALYTICAL DATA TO ARARS AND TBCs - SITE 25
NWS EARLE, COLTS NECK, NEW JERSEY

SAMPLE NUMBER:	25SB01-05	25SB01-08	25SB02-03	25SB02-06	---	---	ARARS & TBCs			
	LOCATION:	25SB01	25SB01	25SB02	25SB02	---	---	NJDEP Soil Residential Direct Contact Cleanup Criteria	NJDEP Soil Non-Residential Direct Contact Cleanup Criteria	NJDEP Soil Impact to Groundwater Cleanup Criteria
DATA SOURCE:	1995 RI	1995 RI	1995 RI	1995 RI						
INORGANICS	mg/kg	mg/kg	mg/kg	mg/kg			mg/kg	mg/kg	mg/kg	
aluminum	472	540	247	116			-	-	-	
antimony	0.79	0.59 U	0.56	0.56 U			14.0	340	-	
arsenic	0.67 U	1.2	0.69 U	0.68 U			20.0	20.0	-	
barium	0.65	1.6	0.41	0.24			700	47000	-	
beryllium	0.022 U	0.050	0.025	0.023 U			1.00	1.00	-	
calcium	22.9	21.8	26.2	22.3			-	-	-	
chromium, total	1.5	1.4	0.41	0.64			-	500	-	
copper	4.5	1.6	0.53	0.41			600	600	-	
iron	1300	2580	74.4	242			-	-	-	
lead	39.7	11.1	1.0	1.4			400	600	-	
magnesium	6.5	6.5	6.7	4.3			-	-	-	
manganese	5.7	2.0	2.4	1.7			-	-	-	
mercury	0.013	0.023	0.011	0.015			14.0	270	-	
nickel	0.30	0.16 U	0.28	0.16 U			250	2400	-	
potassium	31.4 U	113	43.8	31.9 U			-	-	-	
sodium	699	26.0	19.4	772			-	-	-	
vanadium	1.8	2.7	0.26	0.30			370	7100	-	
zinc	3.4 J	9.3 R	6.2 R	1.2 J			1500	1500	-	

TABLE 93
COMPARISON OF SUBSURFACE SOIL ANALYTICAL DATA TO ARARS AND TBCS - SITE 25
NWS EARLE, COLTS NECK, NEW JERSEY

FINAL
PAGE 2

Footnotes to sample results:

- U - Compound or element was not detected. Value is the detection limit (inorganics) or quantitation limit (organics).
- UJ - Not detected. Detection limit or quantitation limit shown is considered estimated due to exceedance of data validation quality control criteria.
- No Value - Constituent was not analyzed for in this sample.
- UR - Nondetected result is considered rejected based on exceedance of data validation quality control criteria.
- J - Value is estimated because concentration is below the quantitation limit or because of exceedance of data validation quality control criteria.
- R - Positive result is considered rejected based on exceedance of data validation quality control criteria.
- N - Compound is considered to be tentatively identified based on exceedance of QC criteria for compound identification.
- E - Result exceeds one or more of the selected ARARs.

Footnotes to soil criteria:

- No standard is available for this chemical in this classification.

TABLE 94

COMPARISON OF SUBSURFACE SOIL MISCELLANEOUS PARAMETERS DATA TO ARARS AND TBCs - SITE 25
NWS EARLE, COLTS NECK, NEW JERSEY

SAMPLE NUMBER:	25SB01-05	25SB01-08	25SB02-03	25SB02-06	---	ARARS & TBCs		
	25SB01	25SB01	25SB02	25SB02	---	NJDEP Soil Residential Direct Contact Cleanup Criteria	NJDEP Soil Non-Residential Direct Contact Cleanup Criteria	NJDEP Soil Impact to Groundwater Cleanup Criteria
LOCATION:								
DATA SOURCE:	1995 RI	1995 RI	1995 RI	1995 RI				
MISCELLANEOUS								
moisture	%	4.9	8.5	7.6	4.4			
nitrate nitrogen	mg/kg	0.32 J	1.0 U	1.0 U	1.0 U	-	-	-

TABLE 94
COMPARISON OF SUBSURFACE SOIL MISCELLANEOUS PARAMETERS DATA TO ARARS AND TBCS - SITE 25
NWS EARLE, COLTS NECK, NEW JERSEY

FINAL
PAGE 2

Footnotes to sample results:

- U - Compound or element was not detected. Value is the detection limit (inorganics) or quantitation limit (organics).
- UJ - Not detected. Detection limit or quantitation limit shown is considered estimated due to exceedance of data validation quality control criteria.
- No Value - Constituent was not analyzed for in this sample.
- UR - Nondetected result is considered rejected based on exceedance of data validation quality control criteria.
- J - Value is estimated because concentration is below the quantitation limit or because of exceedance of data validation quality control criteria.
- R - Positive result is considered rejected based on exceedance of data validation quality control criteria.
- N - Compound is considered to be tentatively identified based on exceedance of QC criteria for compound identification.
- E - Result exceeds one or more of the selected ARARs.

Footnotes to soil criteria:

- - No standard is available for this chemical in this classification.
- @ - Value is New Jersey guideline for maximum total concentration of all organic compounds in soil (including VOCs, SVOCs, and TPH).

TABLE 95
REPRESENTATIVE CONCENTRATION AND STATISTICAL DISTRIBUTION OF COPCS
SUBSURFACE SOIL - SITE 24 (mg/kg)
NWS EARLE, COLTS NECK, NEW JERSEY

CHEMICAL OF CONCERN	REPRESENTATIVE CONCENTRATION	STATISTICAL DISTRIBUTION
ARSENIC	1.8	NONPARAMETRIC
BERYLLIUM	0.044	NONPARAMETRIC
CADMIUM	0.62	NONPARAMETRIC
CHROMIUM	4.9	NONPARAMETRIC
LEAD	5.19	NORMAL

TABLE 96
REPRESENTATIVE CONCENTRATION AND STATISTICAL DISTRIBUTION OF COPCS
SUBSURFACE SOIL -SITE 25 (mg/kg)
NWS EARLE, COLTS NECK, NEW JERSEY

CHEMICAL OF CONCERN	REPRESENTATIVE CONCENTRATION	STATISTICAL DISTRIBUTION
ANTIMONY	0.79	NONPARAMETRIC
ARSENIC	1.06	NORMAL
BERYLLIUM	0.05	NONPARAMETRIC
CHROMIUM	1.5	NONPARAMETRIC
LEAD	39.7	NONPARAMETRIC

TABLE 97
CARCINOGENIC RISK TO FUTURE INDUSTRIAL RECEPTORS - SITE 24
SUBSURFACE SOIL
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SUBSURFACE SOIL INGESTION	SUBSURFACE SOIL DERMAL CONTACT	INHALATION OF COPCS IN FUGITIVE DUST
ARSENIC	9.4E-06	3.1E-06	2.1E-09
BERYLLIUM	6.6E-08	2.1E-06	1.7E-11
CADMIUM	N/A	N/A	5.1E-11
CHROMIUM	N/A	N/A	2.7E-09
LEAD	N/A	N/A	N/A
ZINC	N/A	N/A	N/A
TOTAL RISK	9.5E-06	5.2E-06	4.8E-09

N/A - NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

* CANCER RISK FOR PAHS NOT ESTIMATED FOR DERMAL EXPOSURE

TABLE 98
NONCARCINOGENIC HQS, FUTURE INDUSTRIAL RECEPTORS - SITE 24
SUBSURFACE SOIL
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SUBSURFACE SOIL INGESTION	SUBSURFACE SOIL DERMAL CONTACT	INHALATION OF COPCS IN FUGITIVE DUST
ARSENIC	5.9E-03	1.9E-03	1.1E-06
BERYLLIUM	8.6E-06	2.7E-04	1.6E-09
CADMIUM	1.2E-03	7.6E-03	6.2E-07
CHROMIUM	9.6E-04	1.5E-02	1.8E-07
LEAD	N/A	N/A	N/A
ZINC	1.3E-05	1.6E-05	2.4E-09

N/A - NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 99
CARCINOGENIC RISK TO FUTURE RESIDENTIAL RECEPTORS - SITE 24
SUBSURFACE SOIL
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SUBSURFACE SOIL INGESTION - LIFETIME	SUBSURFACE SOIL DERMAL CONTACT - LIFETIME	INHALATION OF COPCS IN FUGITIVE DUST - LIFETIME
ARSENIC	4.2E-05	1.0E-05	1.3E-09
BERYLLIUM	3.0E-07	6.8E-06	1.0E-11
CADMIUM	N/A	N/A	3.1E-11
CHROMIUM	N/A	N/A	1.6E-09
LEAD	N/A	N/A	N/A
ZINC	N/A	N/A	N/A
TOTAL RISK	4.3E-05	1.7E-05	3.0E-09

N/A - NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

* CANCER RISK FOR PAHS NOT ESTIMATED FOR DERMAL EXPOSURE

TABLE 100
NONCARCINOGENIC HQS, FUTURE RESIDENTIAL CHILD RECEPTORS - SITE 24
SUBSURFACE SOIL
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SUBSURFACE SOIL INGESTION - CHILD	SUBSURFACE SOIL DERMAL CONTACT - CHILD	INHALATION OF COPCS IN FUGITIVE DUST - CHILD
ARSENIC	7.7E-02	1.6E-02	1.1E-06
BERYLLIUM	1.1E-04	2.2E-03	1.7E-09
CADMIUM	1.6E-02	6.2E-02	6.5E-07
CHROMIUM	1.3E-02	1.2E-01	1.9E-07
LEAD	N/A	N/A	N/A
ZINC	1.7E-04	1.3E-04	2.5E-09

N/A - NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 101

**SUMMARY OF ESTIMATED CANCER RISKS AND NONCARCINOGENIC HAZARD INDICIES - SITE 24
NWS EARLE, COLTS NECK, NEW JERSEY**

Medium	Exposure Routes	Estimated Incremental Cancer Risk				Estimated Hazard Index**				
		Current Industrial Employee	Future Industrial Employee	Future Lifetime Resident	Future Recreational Child	Current Industrial Employee	Future Industrial Employee	Future Resident		Future Recreational Child
								Child	Adult	
Surface Soil	Incidental Ingestion	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A
	Dermal Contact	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A
	Inhalation of Fugitive Dust	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A
Subsurface Soil	Incidental Ingestion	N/A	9.5E-06	4.3E-05	N/A	N/A	8.1E-03	1.1E-01	N/A	N/A
	Dermal Contact	N/A	5.2E-06	1.7E-05	N/A	N/A	2.5E-02	2.0E-01	N/A	N/A
	Inhalation of Fugitive Dust	N/A	4.8E-09	3.0E-09	N/A	N/A	1.9E-06	2.0E-06	N/A	N/A
Sediment	Incidental Ingestion	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/S
	Dermal Contact	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/S
Groundwater	Ingestion	N/A	N/S	N/S	N/A	N/A	N/S	N/S	N/A	N/A
	Dermal Contact	N/A	N/S	N/S	N/A	N/A	N/S	N/S	N/A	N/A
	Inhalation of Volatiles*	N/A	N/S	N/S	N/A	N/A	N/S	N/S	N/S	N/A
Surface Water	Incidental Ingestion	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/S
	Dermal Contact	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/S
TOTAL			1.5E-05	6.0E-05			3.3E-02	3.1E-01		

N/A - Not applicable because this media is not associated with this potential receptor

N/S - Not sampled

* - During Showering, Adult Residents Only

** - Hazard Indices (i.e., summation of hazard quotients) are used only for comparison purposes and do not reflect actual additive noncarcinogenic effects

TABLE 102
CARCINOGENIC RISK TO FUTURE INDUSTRIAL RECEPTORS - SITE 25
SUBSURFACE SOIL
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SUBSURFACE SOIL INGESTION	SUBSURFACE SOIL DERMAL CONTACT	INHALATION OF COPCS IN FUGITIVE DUST
ANTIMONY	N/A	N/A	N/A
ARSENIC	5.6E-06	1.8E-06	1.2E-09
BERYLLIUM	7.5E-08	2.3E-06	1.9E-11
CHROMIUM	N/A	N/A	8.2E-10
LEAD	N/A	N/A	N/A
TOTAL RISK	5.6E-06	4.2E-06	2.1E-09

N/A - NOT APPLICABLE, NO TOXICITY VALUE IS ESTABLISHED FOR THIS CHEMICAL

TABLE 103
NONCARCINOGENIC HQS, FUTURE INDUSTRIAL RECEPTORS - SITE 25
SUBSURFACE SOIL
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SUBSURFACE SOIL INGESTION	SUBSURFACE SOIL DERMAL CONTACT	INHALATION OF COPCS IN FUGITIVE DUST
ANTIMONY	1.9E-03	1.2E-02	3.6E-07
ARSENIC	3.5E-03	1.1E-03	6.4E-07
BERYLLIUM	9.8E-06	3.1E-04	1.8E-09
CHROMIUM	2.9E-04	4.6E-03	5.4E-08
LEAD	N/A	N/A	N/A

N/A - NOT APPLICABLE, NO TOXICITY VALUE IS ESTABLISHED FOR THIS CHEMICAL

TABLE 104
CARCINOGENIC RISK TO FUTURE RESIDENTIAL RECEPTORS - SITE 25
SUBSURFACE SOIL
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SUBSURFACE SOIL INGESTION - LIFETIME	SUBSURFACE SOIL DERMAL CONTACT - LIFETIME	INHALATION OF COCS IN FUGITIVE DUST - LIFETIME
ANTIMONY	N/A	N/A	N/A
ARSENIC	2.5E-05	6.0E-06	7.6E-10
BERYLLIUM	3.4E-07	7.8E-06	1.2E-11
CHROMIUM	N/A	N/A	5.0E-10
LEAD	N/A	N/A	N/A
TOTAL RISK	2.5E-05	1.4E-05	1.3E-09

N/A - NOT APPLICABLE, NO TOXICITY VALUE IS ESTABLISHED FOR THIS CHEMICAL

TABLE 105
NONCARCINOGENIC HQS, FUTURE RESIDENTIAL RECEPTORS - SITE 25
SUBSURFACE SOIL
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SUBSURFACE SOIL INGESTION - CHILD	SUBSURFACE SOIL DERMAL CONTACT - CHILD	INHALATION OF COPCS IN FUGITIVE DUST - CHILD
ANTIMONY	2.5E-02	9.9E-02	3.8E-07
ARSENIC	4.5E-02	9.3E-03	6.8E-07
BERYLLIUM	1.3E-04	2.5E-03	1.9E-09
CHROMIUM	3.8E-03	3.7E-02	5.7E-08
LEAD	N/A	N/A	N/A

N/A - NOT APPLICABLE, NO TOXICITY VALUE IS ESTABLISHED FOR THIS CHEMICAL

TABLE 106

**SUMMARY OF ESTIMATED CANCER RISKS AND NONCARCINOGENIC HAZARD INDICIES - SITE 25
NWS EARLE, COLTS NECK, NEW JERSEY**

Medium	Exposure Routes	Estimated Incremental Cancer Risk				Estimated Hazard Index**				
		Current Industrial Employee	Future Industrial Employee	Future Lifetime Resident	Future Recreational Child	Current Industrial Employee	Future Industrial Employee	Future Resident		Future Recreational Child
								Child	Adult	
Surface Soil	Incidental Ingestion	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A
	Dermal Contact	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A
	Inhalation of Fugitive Dust	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A
Subsurface Soil	Incidental Ingestion	N/A	5.6E-06	2.5E-05	N/A	N/A	5.7E-03	7.4E-02	N/A	N/A
	Dermal Contact	N/A	4.2E-06	1.4E-05	N/A	N/A	1.8E-02	1.5E-01	N/A	N/A
	Inhalation of Fugitive Dust	N/A	2.1E-09	1.3E-09	N/A	N/A	1.1E-06	1.1E-06	N/A	N/A
Sediment	Incidental Ingestion	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/S
	Dermal Contact	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/S
Groundwater	Ingestion	N/A	N/S	N/S	N/A	N/A	N/S	N/S	N/A	N/A
	Dermal Contact	N/A	N/S	N/S	N/A	N/A	N/S	N/S	N/A	N/A
	Inhalation of Volatiles*	N/A	N/S	N/S	N/A	N/A	N/S	N/A	N/S	N/A
Surface Water	Incidental Ingestion	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/S
	Dermal Contact	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/S
TOTAL			9.8E-06	3.9E-05			2.4E-02	2.2E-01		

N/A - Exposure Route not applicable for receptor

N/S - Not Samples

* - During Showering, Adult Residents Only

** - Hazard Indices (i.e., summation of hazard quotients) are used only for comparison purposes and do not reflect actual additive noncarcinogenic effects

TABLE 107
RESULTS OF CONFIRMATORY SOIL SAMPLES
SITES 24 AND 25
NWS EARLE
COLTS NECK, NEW JERSEY

SITE	LOCATION	TOTAL LEAD (MG/KG)
24	North Range Berm	3.1
24	North Range Firing Line	9.8
25	South Range Firing Line	15.4
25	South Range Berm	176.0

TABLE 108
RESULTS OF SAMPLES OF WASHED SOIL
SITES 24 AND 25
NWS EARLE
COLTS NECK, NEW JERSEY

	TOTAL LEAD
SAMPLE	(MG/KG)
1	14.6
2	38.3
3	34.9
4	66.2

TABLE 109

OCCURRENCE AND DISTRIBUTION OF INORGANICS IN SUBSURFACE SOIL AT SITE 27
 NWS EARLE, COLTS NECK, NEW JERSEY
 (mg/kg)

SUBSTANCE	BACKGROUND			SITE-RELATED				
	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	2 X AVERAGE BKGD CONCENTRATION	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	AVERAGE CONCENTRATION	MEAN > 2 X BKGD	REPRESENTATIVE CONCENTRATION
ALUMINUM*	8 / 8	675 - 5310	5370.00	9 / 9	1370 - 7530	3598.89	NO	5718.97
ANTIMONY	NOT DETECTED	-	-	1 / 9	3	1.47	YES	1.82
ARSENIC	8 / 8	1.35 - 14.4	13.29	8 / 9	0.73 - 3.9	1.58	NO	3.49
BARIUM	8 / 8	0.92 - 31	17.92	9 / 9	4.2 - 109	25.04	YES	45.07
BERYLLIUM*	2 / 8	0.12 - 0.28	0.28	6 / 9	0.096 - 0.42	0.16	NO	0.42
CADMIUM	1 / 8	0.57	0.58	6 / 9	0.67 - 52.4	6.99	YES	17.57
CALCIUM	8 / 8	28.6 - 799	577.55	9 / 9	46.3 - 572	243.59	NO	351.54
CHROMIUM*	8 / 8	4.7 - 59.5	54.73	9 / 9	5.8 - 191	48.10	NO	91.15
COBALT*	4 / 8	0.75 - 5	2.77	5 / 9	0.89 - 4.1	1.21	NO	1.94
COPPER	8 / 8	0.97 - 8.6	8.66	9 / 9	1.7 - 150	25.50	YES	55.34
IRON*	8 / 8	3745 - 62500	40871.25	9 / 9	2750 - 11800	6333.33	NO	9168.25
LEAD	8 / 8	1.4 - 39.4	24.33	9 / 9	2.9 - 369	63.97	YES	137.72
MAGNESIUM	8 / 8	18.5 - 619	504.05	9 / 9	162 - 1090	419.22	NO	602.25
MANGANESE*	8 / 8	2.6 - 214	92.51	9 / 9	18 - 104	36.93	NO	53.75
MERCURY*	8 / 8	0.03 - 0.17	0.13	9 / 9	0.029 - 0.12	0.05	NO	0.06
NICKEL*	4 / 8	1.8 - 7.2	4.75	9 / 9	0.91 - 10.6	3.49	NO	5.33
POTASSIUM	7 / 8	95 - 792	793.35	9 / 9	113 - 392	215.67	NO	299.90
SELENIUM*	2 / 8	0.57 - 0.93	0.79	2 / 9	0.74	0.39	NO	0.51
SILVER	2 / 8	0.37 - 0.67	0.51	1 / 9	15	1.86	YES	4.91
SODIUM	8 / 8	17.5 - 94.8	79.35	9 / 9	11.8 - 48	28.10	NO	41.05
VANADIUM*	8 / 8	11.05 - 64	64.71	9 / 9	7.2 - 18.6	10.84	NO	13.58
ZINC	6 / 8	1.1 - 50.7	31.35	9 / 9	5.2 - 323	110.53	YES	199.55

Note: Selected COPCs are indicated in boldface type.

* - Indicates COPCs eliminated based on amended risk assessment.

TABLE 110
OCCURRENCE AND DISTRIBUTION OF ORGANICS IN SUBSURFACE SOIL AT SITE 27
NWS EARLE, COLTS NECK, NEW JERSEY
(mg/kg)

SUBSTANCE	BACKGROUND			SITE-RELATED		
	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	REPRESENTATIVE CONCENTRATION	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	REPRESENTATIVE CONCENTRATION
4,4'-DDD	NOT DETECTED	-	-	4 / 9	0.28 - 33	11.98
4,4'-DDE	2 / 8	16 - 330	121.91	4 / 9	1.8 - 16	8.81
4,4'-DDT	2 / 8	43 - 420	157.34	5 / 8	1.5 - 47	19.61
ALPHA-CHLORDANE	NOT DETECTED	-	-	5 / 9	0.2 - 3.2	1.81
AROCLOR-1254	NOT DETECTED	-	-	3 / 9	30 - 150	69.10
AROCLOR-1260	NOT DETECTED	-	-	5 / 9	12 - 300	115.39
BIS(2-ETHYLHEXYL)PHTHALATE	NOT DETECTED	-	-	2 / 9	840 - 5600	1969.54
DI-N-BUTYLPHTHALATE	2 / 8	45 - 48	48	1 / 9	58	58
DIELDRIN	1 / 8	0.49	0.49	1 / 9	1.6	1.6
ENDRIN ALDEHYDE	NOT DETECTED	-	-	1 / 9	15	6.01
HEPTACHLOR	NOT DETECTED	-	-	1 / 9	0.27	0.27
NAPHTHALENE	NOT DETECTED	-	-	1 / 9	89	89

06/17/96

TABLE 111

COMPARISON OF SUBSURFACE SOIL ANALYTICAL DATA TO ARARS AND TBCs - SITE 27

NWS EARLE, COLTS NECK, NEW JERSEY

FINAL

Page 1

SAMPLE NUMBER: LOCATION: DATA SOURCE:	27SB01-01	27SB01-03	27SB01-10	27SB02-01	27SB02-03	27SB02-10	ARARS & TBCs			
	27SB01	27SB01	27SB01	27SB02	27SB02	27SB02	NJDEP Soil Residential Direct Contact Cleanup Criteria	NJDEP Soil Non-Residential Direct Contact Cleanup Criteria	NJDEP Soil Impact to Groundwater Cleanup Criteria	
	1995 RI, Dec.									
INORGANICS	mg/kg	mg/kg	mg/kg	mg/kg						
aluminum	5090	1690	7530	3680	3350	2500	-	-	-	
antimony	2.5 U	2.4 U	2.7 U	2.5 U	2.5 U	2.6 U	14.0	340	-	
arsenic	2.8	1.1	0.73	1.8	1.6	0.61 U	20.0	20.0	-	
barium	21.5	4.2	23.1	19.7	5.3	11.0	700	47000	-	
beryllium	0.10	0.078 U	0.42	0.083 U	0.081 U	0.13	1.00	1.00	-	
cadmium	2.1 E J	0.67 J	0.62 U	4.0 E J	0.57 U	0.61 U	1.00	100	-	
calcium	156	46.3	179	502	232	176	-	-	-	
chromium, total	191	18.8	10.4	26.7	9.3	5.8	-	500	-	
cobalt	1.4	0.80 U	1.6	0.85 U	0.83 U	0.89 U	-	-	-	
copper	11.6	3.0	4.2	39.9	1.7	4.5	600	600	-	
iron	10100	3850	6250	7320	5300	2750	-	-	-	
lead	105 J	9.9 J	4.6 J	46.4 J	2.9	4.6 J	400	600	-	
magnesium	424	162	1090	341	216	364	-	-	-	
manganese	18.4 J	18.0 J	45.6 J	31.3 J	19.1 J	20.7 J	-	-	-	
mercury	0.044	0.029	0.033	0.053	0.037	0.033	14.0	270	-	
nickel	3.0	0.91	5.0	3.4	1.8	1.0	250	2400	-	
potassium	280	186	392	176	121	113	-	-	-	
selenium	0.74	0.53 U	0.60 U	0.57 U	0.55 U	0.59 U	63.0	3100	-	
silver	0.62 U	15.0	0.67 U	0.63 U	0.62 U	0.66 U	110	4100	-	
sodium	19.6	18.8	34.2	19.2	11.8	33.2	-	-	-	
vanadium	18.6 J	7.2	12.2 J	12.5 J	10.1	7.3	370	7100	-	
zinc	323	14.0	16.7	258	5.2	18.5	1500	1500	-	
SEMIVOLATILES	ug/kg	ug/kg	ug/kg							
bis(2-ethylhexyl)phthalate	840	340 U	380 U	360 U	350 U	380 U	49000	210000	100000	
di-n-butylphthalate	350 U	340 U	380 U	360 U	350 U	380 U	5700000	10000000	100000	
naphthalene	89.0 J	340 U	380 U	360 U	350 U	380 U	230000	4200000	100000	

TABLE 111

COMPARISON OF SUBSURFACE SOIL ANALYTICAL DATA TO ARARS AND TBCs - SITE 27
NWS EARLE, COLTS NECK, NEW JERSEY

SAMPLE NUMBER:	27SB01-01	27SB01-03	27SB01-10	27SB02-01	27SB02-03	27SB02-10	ARARS & TBCs		
	LOCATION: 27SB01	27SB01	27SB01	27SB02	27SB02	27SB02	NJDEP Soil Residential Direct Contact Cleanup Criteria	NJDEP Soil Non-Residential Direct Contact Cleanup Criteria	NJDEP Soil Impact to Groundwater Cleanup Criteria
DATA SOURCE:	1995 RI, Dec.	1995 RI, Dec.	1995 RI, Dec.	1995 RI, Dec.	1995 RI, Dec.	1995 RI, Dec.			
PESTICIDES	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg
4,4'-DDD	33.0	3.4 U	3.8 U	3.6 U	3.5 U	6.7	3000	12000	50000
4,4'-DDE	15.0 J	3.4 U	3.8 U	4.3	3.5 U	1.8 J	2000	9000	50000
4,4'-DDT	1.7 NJ	0.67 R	3.8 U	14.0 J	3.5 U	3.7 U	2000	9000	500000
Aroclor-1254	35.0 U	30.0 J	38.0 U	79.0	35.0 U	150	490	2000	50000
Aroclor-1260	35.0 U	12.0 J	38.0 U	94.0	35.0 U	37.0 U	490	2000	50000
alpha-BHC	1.8 U	1.8 U	2.0 U	1.9 U	1.8 U	0.14 R	-	-	-
alpha-chlordane	1.8 U	0.26 NJ	2.0 U	0.80 J	1.8 U	2.5 J	-	-	-
dieldrin	3.5 U	3.4 U	3.8 U	3.6 U	3.5 U	3.7 U	42.0	180	50000
endrin aldehyde	3.5 U	3.4 U	3.8 U	3.6 U	3.5 U	3.8 U	-	-	-
gamma-BHC (Lindane)	1.8 U	1.8 U	2.0 U	1.9 U	1.8 U	1.9 U	520	2200	50000
gamma-chlordane	1.8 U	1.8 U	2.0 U	0.33 R	1.8 U	0.41 R	-	-	-
heptachlor	1.8 U	1.8 U	0.27 J	1.9 U	1.8 U	1.9 U	150	650	50000
heptachlor epoxide	1.8 U	1.8 U	2.0 U	1.9 U	1.8 U	0.45 R	-	-	-

06/17/96

TABLE 111

COMPARISON OF SUBSURFACE SOIL ANALYTICAL DATA TO ARARS AND TBCs - SITE 27
NWS EARLE, COLTS NECK, NEW JERSEY

FINAL
Page 3

SAMPLE NUMBER:	27SB03-01	27SB03-03	27SB03-06	---	---	---	ARARS & TBCs		
	LOCATION: 27SB03	27SB03	27SB03	---	---	---	NJDEP Soil Residential Direct Contact Cleanup Criteria	NJDEP Soil Non-Residential Direct Contact Cleanup Criteria	NJDEP Soil Impact to Groundwater Cleanup Criteria
DATA SOURCE:	1995 RI, Dec.	1995 RI, Dec.	1995 RI, Dec.				mg/kg	mg/kg	mg/kg
INORGANICS	mg/kg	mg/kg	mg/kg						
aluminum	1370	2660	4520						
antimony	3.0	2.5 U	2.7 U				-	-	-
arsenic	3.9	1.2	0.79				14.0	340	-
barium	109	10.0	21.6				20.0	20.0	-
beryllium	0.16	0.18	0.32				700	47000	-
cadmium	52.4 E	1.5 E	1.3 E				1.00	1.00	-
calcium	572	168	161				1.00	100	-
chromium, total	146	10.4	14.5				-	-	-
cobalt	4.1	0.89	1.2				-	500	-
copper	150 J	4.8	9.8 J				-	-	-
iron	11800	4660	4970				600	600	-
lead	369	11.9	21.4				-	-	-
magnesium	180	323	673				400	600	-
manganese	104	37.2	38.1				-	-	-
mercury	0.12	0.030	0.033				-	-	-
nickel	10.6	2.2	3.5				14.0	270	-
potassium	149	278	246				250	2400	-
selenium	0.74 J	0.56 UJ	0.60 UJ				-	-	-
silver	0.072 U	0.068 U	0.074 U				63.0	3100	-
sodium	48.0	23.3	44.8				110	4100	-
vanadium	8.4	8.8	12.5				-	-	-
zinc	320 J	16.1 J	23.3 J				370	7100	-
							1500	1500	-
SEMIVOLATILES	ug/kg	ug/kg	ug/kg				ug/kg	ug/kg	ug/kg
bis(2-ethylhexyl)phthalate	5600	350 U	430 U				49000	210000	100000
di-n-butylphthalate	58.0 J	350 U	380 U				5700000	10000000	100000
naphthalene	370 U	350 U	380 U				230000	4200000	100000

TABLE 111

COMPARISON OF SUBSURFACE SOIL ANALYTICAL DATA TO ARARS AND TBCs - SITE 27
NWS EARLE, COLTS NECK, NEW JERSEY

SAMPLE NUMBER:	27SB03-01	27SB03-03	27SB03-06	---	---	---	ARARS & TBCs			
	LOCATION:	27SB03	27SB03	27SB03	---	---	---	NJDEP Soil Residential Direct Contact Cleanup Criteria	NJDEP Soil Non-Residential Direct Contact Cleanup Criteria	NJDEP Soil Impact to Groundwater Cleanup Criteria
DATA SOURCE:	1995 RI, Dec.	1995 RI, Dec.	1995 RI, Dec.							
PESTICIDES	ug/kg	ug/kg	ug/kg				ug/kg	ug/kg	ug/kg	
4,4'-DDD	3.7 U	0.34 J	0.28 J				3000	12000	50000	
4,4'-DDE	16.0	3.6 U	3.9 U				2000	9000	50000	
4,4'-DDT	47.0	1.5 J	1.5 J				2000	9000	500000	
Aroclor-1254	37.0 U	35.0 U	38.0 U				490	2000	50000	
Aroclor-1260	300	15.0 J	16.0 J				490	2000	50000	
alpha-BHC	1.9 U	1.8 U	2.0 U				-	-	-	
alpha-chlordane	3.2	1.8 U	0.20 J				-	-	-	
dieldrin	1.6 NJ	3.5 U	3.8 U				42.0	180	50000	
endrin aldehyde	15.0 J	3.6 U	3.9 U				-	-	-	
gamma-BHC (Lindane)	0.22 R	1.8 U	2.0 U				520	2200	50000	
gamma-chlordane	1.4 R	1.8 U	2.0 U				-	-	-	
heptachlor	1.9 U	1.8 U	2.0 U				150	650	50000	
heptachlor epoxide	0.17 R	1.8 U	2.0 U				-	-	-	

TABLE 111

COMPARISON OF SUBSURFACE SOIL ANALYTICAL DATA TO ARARS AND TBCS - SITE 27 NWS EARLE, COLTS NECK, NEW JERSEY

FINAL
PAGE 5

Footnotes to sample results:

- U - Compound or element was not detected. Value is the detection limit (inorganics) or quantitation limit (organics).
- UJ - Not detected. Detection limit or quantitation limit shown is considered estimated due to exceedance of data validation quality control criteria.
- No Value - Constituent was not analyzed for in this sample.
- UR - Nondetected result is considered rejected based on exceedance of data validation quality control criteria.
- J - Value is estimated because concentration is below the quantitation limit or because of exceedance of data validation quality control criteria.
- R - Positive result is considered rejected based on exceedance of data validation quality control criteria.
- N - Compound is considered to be tentatively identified based on exceedance of QC criteria for compound identification.
- E - Result exceeds one or more of the selected ARARs.

Footnotes to soil criteria:

- No standard is available for this chemical in this classification.

TABLE 112

COMPARISON OF SUBSURFACE SOIL MISCELLANEOUS PARAMETERS DATA TO ARARS AND TBCs - SITE 27

NWS EARLE, COLTS NECK, NEW JERSEY

SAMPLE NUMBER: LOCATION: DATA SOURCE:	27SB01-01	27SB01-03	27SB01-10	27SB02-01	27SB02-03	ARARS & TBCs		
	27SB01 1995 RI, Dec.	27SB01 1995 RI, Dec.	27SB01 1995 RI, Dec.	27SB02 1995 RI, Dec.	27SB02 1995 RI, Dec.	NJDEP Soil Residential Direct Contact Cleanup Criteria	NJDEP Soil Non-Residential Direct Contact Cleanup Criteria	NJDEP Soil Impact to Groundwater Cleanup Criteria
MISCELLANEOUS								
moisture %	6.0	3.3	14.1	9.1	6.7	-	-	-
pH	5.6	5.2	5.7	7.7	7.7	-	-	-

06/18/96

TABLE 112

**COMPARISON OF SUBSURFACE SOIL MISCELLANEOUS PARAMETERS DATA TO ARARS AND TBCs - SITE 27
NWS EARLE, COLTS NECK, NEW JERSEY**

FINAL
Page 2

SAMPLE NUMBER:	27SB02-10	27SB03-01	27SB03-03	27SB03-06	---	ARARS & TBCs		
						NJDEP Soil Residential Direct Contact Cleanup Criteria	NJDEP Soil Non-Residential Direct Contact Cleanup Criteria	NJDEP Soil Impact to Groundwater Cleanup Criteria
LOCATION:	27SB02	27SB03	27SB03	27SB03	---			
DATA SOURCE:	1995 RI, Dec.	1995 RI, Dec.	1995 RI, Dec.	1995 RI, Dec.				
MISCELLANEOUS								
moisture %	12.1	11.2	6.4	14.2		-	-	-
pH	7.1	6.6	7.0	5.7		-	-	-

TABLE 112
COMPARISON OF SUBSURFACE SOIL MISCELLANEOUS PARAMETERS DATA TO ARARS AND TBCS - SITE 27
NWS EARLE, COLTS NECK, NEW JERSEY

FINAL
PAGE 3

Footnotes to sample results:

- U - Compound or element was not detected. Value is the detection limit (inorganics) or quantitation limit (organics).
- UJ - Not detected. Detection limit or quantitation limit shown is considered estimated due to exceedance of data validation quality control criteria.
- No Value - Constituent was not analyzed for in this sample.
- UR - Nondetected result is considered rejected based on exceedance of data validation quality control criteria.
- J - Value is estimated because concentration is below the quantitation limit or because of exceedance of data validation quality control criteria.
- R - Positive result is considered rejected based on exceedance of data validation quality control criteria.
- N - Compound is considered to be tentatively identified based on exceedance of QC criteria for compound identification.
- E - Result exceeds one or more of the selected ARARs.

Footnotes to soil criteria:

- No standard is available for this chemical in this classification.
- @ - Value is New Jersey guideline for maximum total concentration of all organic compounds in soil (including VOCs, SVOCs, and TPH).

TABLE 113
REPRESENTATIVE CONCENTRATION AND STATISTICAL DISTRIBUTION OF COPCS
SUBSURFACE SOIL - SITE 27 (mg/kg)
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	REPRESENTATIVE CONCENTRATION	STATISTICAL DISTRIBUTION
ANTIMONY	1.82	NONPARAMETRIC
ARSENIC	3.49	NONPARAMETRIC
BARIUM	45.07	NONPARAMETRIC
CADMIUM	17.57	NONPARAMETRIC
COPPER	55.34	NONPARAMETRIC
LEAD	137.72	NONPARAMETRIC
SILVER	4.91	NONPARAMETRIC
ZINC	199.55	NONPARAMETRIC
4,4'-DDD*	11.98	NORMAL
4,4'-DDE*	8.81	NORMAL
4,4'-DDT*	19.61	NORMAL
ALPHA-CHLORDANE*	1.81	NORMAL
AROCLOR-1254*	69.10	NORMAL
AROCLOR-1260*	115.39	NORMAL
BIS(2-ETHYLHEXYL)PHTHALATE*	1969.54	NORMAL
DI-N-BUTYLPHTHALATE*	58.00	NORMAL
DIELDRIN*	1.60	NORMAL
ENDRIN ALDEHYDE*	6.01	NORMAL
HEPTACHLOR*	0.27	NORMAL
NAPHTHALENE*	89.00	NORMAL

* = Organics are in (ug/kg)

TABLE 114
RME CARCINOGENIC RISK TO FUTURE INDUSTRIAL RECEPTORS - SITE 27
SUBSURFACE SOIL, AMENDED RISK
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SUBSURFACE SOIL INGESTION	SUBSURFACE SOIL DERMAL CONTACT	INHALATION OF COPCS IN FUGITIVE DUST
BIS(2-ETHYLHEXYL)PHTHALATE	9.6E-09	N/A	1.8E-12
DI-N-BUTYLPHTHALATE	N/A	N/A	N/A
DIELDRIN	9.0E-09	N/A	2.0E-12
ENDRIN ALDEHYDE	N/A	N/A	N/A
NAPHTHALENE	N/A	N/A	N/A
4,4'-DDD	1.0E-09	N/A	1.9E-13
4,4'-DDE	1.0E-09	N/A	1.9E-13
4,4'-DDT	2.3E-09	N/A	5.2E-13
ALPHA-CHLORDANE	8.2E-10	N/A	1.8E-13
AROCLOR-1254	1.9E-07	1.4E-06	3.4E-11
AROCHLOR-1260	3.1E-07	2.3E-06	5.7E-11
HEPTACHLOR	4.2E-10	N/A	9.5E-14
ANTIMONY	N/A	N/A	N/A
ARSENIC	1.8E-05	1.8E-05	4.1E-09
BARIUM	N/A	N/A	N/A
CADMIUM	N/A	N/A	1.4E-09
COPPER	N/A	N/A	N/A
LEAD	N/A	N/A	N/A
SILVER	N/A	N/A	N/A
ZINC	N/A	N/A	N/A
TOTAL RISK	1.9E-05	2.2E-05	5.6E-09

N/A = NOT APPLICABLE, NO TOXICITY VALUE OR ABSORPTION FACTOR HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 115

RME NONCARCINOGENIC HQS, FUTURE INDUSTRIAL RECEPTORS - SITE 27
 SUBSURFACE SOIL, AMENDED RISK
 NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SUBSURFACE SOIL INGESTION	SUBSURFACE SOIL DERMAL CONTACT	INHALATION OF COPCS IN FUGITIVE DUST
BIS(2-ETHYLHEXYL)PHTHALATE	9.6E-05	N/A	1.8E-08
DI-N-BUTYLPHTHALATE	5.7E-07	N/A	1.1E-10
DIELDRIN	3.1E-05	N/A	5.8E-09
ENDRIN ALDEHYDE	N/A	N/A	N/A
NAPHTHALENE	2.2E-06	N/A	4.0E-10
4,4'-DDD	N/A	N/A	N/A
4,4'-DDE	N/A	N/A	N/A
4,4'-DDT	3.8E-05	N/A	7.1E-09
ALPHA-CHLORDANE	2.9E-05	N/A	5.5E-09
AROCLOR-1254	N/A	N/A	N/A
AROCHLOR-1260	N/A	N/A	N/A
HEPTACHLOR	5.3E-07	N/A	9.8E-11
ANTIMONY	4.5E-03	N/A	8.3E-07
ARSENIC	1.1E-02	1.1E-02	2.1E-06
BARIUM	6.3E-04	N/A	1.2E-05
CADMIUM	3.4E-02	1.1E-02	1.8E-05
COPPER	1.4E-03	N/A	2.5E-07
LEAD	N/A	N/A	N/A
SILVER	9.6E-04	N/A	1.8E-07
ZINC	6.5E-04	N/A	1.2E-07

N/A = NOT APPLICABLE, NO TOXICITY VALUE OR ABSORPTION FACTOR HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 116

**RME CARCINOGENIC RISK TO FUTURE RESIDENTIAL RECEPTORS - SITE 27
 SUBSURFACE SOIL, AMENDED RISK
 NWS EARLE, COLTS NECK, NEW JERSEY**

SUBSTANCE	SUBSURFACE SOIL INGESTION - LIFETIME	SUBSURFACE SOIL DERMAL CONTACT - LIFETIME	INHALATION OF COPCS IN FUGITIVE DUST - LIFETIME
BIS(2-ETHYLHEXYL)PHTHALATE	4.3E-08	N/A	1.1E-12
DI-N-BUTYLPHthalATE	N/A	N/A	N/A
DIELDRIN	4.0E-08	N/A	1.2E-12
ENDRIN ALDEHYDE	N/A	N/A	N/A
NAPHTHALENE	N/A	N/A	N/A
4,4'-DDD	4.5E-09	N/A	1.1E-13
4,4'-DDE	4.7E-09	N/A	1.2E-13
4,4'-DDT	1.0E-08	N/A	3.2E-13
ALPHA-CHLORDANE	3.7E-09	N/A	1.1E-13
AROCLOR-1254	8.3E-07	4.5E-06	2.1E-11
AROCHLOR-1260	1.4E-06	7.5E-06	3.5E-11
HEPTACHLOR	1.9E-09	N/A	5.8E-14
ANTIMONY	N/A	N/A	N/A
ARSENIC	8.2E-05	6.0E-05	2.5E-09
BARIUM	N/A	N/A	N/A
CADMIUM	N/A	N/A	8.8E-10
COPPER	N/A	N/A	N/A
LEAD	N/A	N/A	N/A
SILVER	N/A	N/A	N/A
ZINC	N/A	N/A	N/A
TOTAL RISK	8.4E-05	7.2E-05	3.4E-09

N/A = NOT APPLICABLE. NO TOXICITY VALUE OR ABSORPTION FACTOR HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 117

CENTRAL TENDENCY CARCINOGENIC RISK TO FUTURE RESIDENTIAL RECEPTORS - SITE 27
 SUBSURFACE SOIL, AMENDED RISK
 NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SUBSURFACE SOIL INGESTION - LIFETIME	SUBSURFACE SOIL DERMAL CONTACT - LIFETIME	INHALATION OF COPCS IN FUGITIVE DUST - LIFETIME
BIS(2-ETHYLHEXYL)PHTHALATE	6.9E-09	N/A	3.4E-13
DI-N-BUTYLPHTHALATE	N/A	N/A	N/A
DIELDRIN	6.5E-09	N/A	3.8E-13
ENDRIN ALDEHYDE	N/A	N/A	N/A
NAPHTHALENE	N/A	N/A	N/A
4,4'-DDD	7.2E-10	N/A	3.5E-14
4,4'-DDE	7.5E-10	N/A	3.7E-14
4,4'-DDT	1.7E-09	N/A	9.8E-14
ALPHA-CHLORDANE	5.9E-10	N/A	3.5E-14
AROCLOR-1254	1.3E-07	1.4E-06	6.5E-12
AROCHLOR-1260	2.2E-07	2.4E-06	1.1E-11
HEPTACHLOR	3.1E-10	N/A	1.8E-14
ANTIMONY	N/A	N/A	N/A
ARSENIC	1.3E-05	1.9E-05	7.7E-10
BARIUM	N/A	N/A	N/A
CADMIUM	N/A	N/A	2.7E-10
COPPER	N/A	N/A	N/A
LEAD	N/A	N/A	N/A
SILVER	N/A	N/A	N/A
ZINC	N/A	N/A	N/A
TOTAL RISK	1.4E-05	2.3E-05	1.1E-09

N/A = NOT APPLICABLE, NO TOXICITY VALUE OR ABSORPTION FACTOR HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 118

RME NONCARCINOGENIC HQS, FUTURE RESIDENTIAL RECEPTORS - SITE 27
 SUBSURFACE SOIL, AMENDED RISK
 NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SUBSURFACE SOIL INGESTION - CHILD	SUBSURFACE SOIL DERMAL CONTACT - CHILD	INHALATION OF COPCS IN FUGITIVE DUST - CHILD
BIS(2-ETHYLHEXYL)PHTHALATE	1.3E-03	N/A	1.9E-08
DI-N-BUTYLPHthalATE	7.4E-06	N/A	1.1E-10
DIELDRIN	4.1E-04	N/A	6.1E-09
ENDRIN ALDEHYDE	N/A	N/A	N/A
NAPHTHALENE	2.8E-05	N/A	4.3E-10
4,4'-DDD	N/A	N/A	N/A
4,4'-DDE	N/A	N/A	N/A
4,4'-DDT	5.0E-04	N/A	7.5E-09
ALPHA-CHLORDANE	3.8E-04	N/A	5.8E-09
AROCLOR-1254	N/A	N/A	N/A
AROCHLOR-1260	N/A	N/A	N/A
HEPTACHLOR	6.9E-06	N/A	1.0E-10
ANTIMONY	5.8E-02	N/A	8.7E-07
ARSENIC	1.5E-01	9.2E-02	2.2E-06
BARIUM	8.2E-03	N/A	1.2E-05
CADMIUM	4.5E-01	8.8E-02	1.9E-05
COPPER	1.8E-02	N/A	2.6E-07
LEAD	N/A	N/A	N/A
SILVER	1.3E-02	N/A	1.9E-07
ZINC	8.5E-03	N/A	1.3E-07

N/A = NOT APPLICABLE, NO TOXICITY VALUE OR ABSORPTION FACTOR HAS BEEN
 ESTABLISHED FOR THIS CHEMICAL

TABLE 119
SUMMARY OF ESTIMATED RME CANCER RISKS AND NONCARCINOGENIC HAZARD INDICIES - SITE 27
NWS EARLE, COLTS NECK, NEW JERSEY

Medium	Exposure Routes	Estimated Incremental Cancer Risk				Estimated Hazard Index**				
		Current Industrial Employee	Future Industrial Employee	Future Lifetime Resident	Future Recreational Child	Current Industrial Employee	Future Industrial Employee	Future Resident		Future Recreational Child
								Child	Adult	
Surface Soil	Incidental Ingestion	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A
	Dermal Contact	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A
	Inhalation of Fugitive Dust	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A
Subsurface Soil	Incidental Ingestion	N/A	1.9E-05 [^]	8.4E-05 [^]	N/A	N/A	5.4E-02 [^]	7.1E-01 [^]	N/A	N/A
	Dermal Contact	N/A	2.2E-05 [^]	7.2E-05 [^]	N/A	N/A	2.2E-02 [^]	1.8E-01 [^]	N/A	N/A
	Inhalation of Fugitive Dust	N/A	5.6E-09 [^]	3.4E-09 [^]	N/A	N/A	3.3E-05 [^]	3.4E-05 [^]	N/A	N/A
Sediment	Incidental Ingestion	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/S
	Dermal Contact	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/S
Groundwater	Ingestion	N/A	N/S	N/S	N/A	N/A	N/S	N/S	N/A	N/A
	Dermal Contact	N/A	N/S	N/S	N/A	N/A	N/S	N/S	N/A	N/A
	Inhalation of Volatiles*	N/A	N/A	N/S	N/A	N/A	N/A	N/S	N/A	N/A
Surface Water	Incidental Ingestion	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/S	N/A
	Dermal Contact	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/S
TOTAL		-	4.1E-05	1.6E-04	-	-	7.6E-02	8.9E-01	-	-

N/A = Not applicable because this media is not associated with this potential receptor

N/S = Not sampled

* = During Showering, Adult Residents Only

** = Hazard Indices (i.e., summation of hazard quotients) are used only for comparison purposes and do not reflect actual additive noncarcinogenic effects

[^] - Value from amended risk assessment.

TABLE 120

**SUMMARY OF CENTRAL TENDENCY CANCER RISKS AND NONCARCINOGENIC HAZARD INDICIES - SITE 27
NWS EARLE, COLTS NECK, NEW JERSEY**

Medium	Exposure Routes	Estimated Incremental Cancer Risk				Estimated Hazard Index**				
		Current Industrial Employee	Future Industrial Employee	Future Lifetime Resident	Future Recreational Child	Current Industrial Employee	Future Industrial Employee	Future Resident		Future Recreational Child
								Child	Adult	
Surface Soil	Incidental Ingestion	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A
	Dermal Contact	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A
	Inhalation of Fugitive Dust	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A
Subsurface Soil	Incidental Ingestion	N/A	N/R	1.4E-05 [^]	N/A	N/A	N/R	N/R	N/A	N/A
	Dermal Contact	N/A	N/R	2.3E-05 [^]	N/A	N/A	N/R	N/R	N/A	N/A
	Inhalation of Fugitive Dust	N/A	N/R	1.1E-09 [^]	N/A	N/A	N/R	N/R	N/A	N/A
Sediment	Incidental Ingestion	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/S
	Dermal Contact	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/S
Groundwater	Ingestion	N/A	N/S	N/S	N/A	N/A	N/S	N/S	N/A	N/A
	Dermal Contact	N/A	N/S	N/S	N/A	N/A	N/S	N/S	N/A	N/A
	Inhalation of Volatiles*	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/S	N/A
Surface Water	Incidental Ingestion	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/S
	Dermal Contact	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/S
TOTAL		-	-	3.7E-05	-	-	-	-	-	-

N/A = Not applicable because this media is not associated with this potential receptor

N/R - Central tendency calculation not required

N/S = Not sampled

* = During Showering, Adult Residents Only

** = Hazard Indices (i.e., summation of hazard quotients) are used only for comparison purposes and do not reflect actual additive noncarcinogenic effects

[^] - Value from amended risk assessment.

TABLE 121
SEDIMENT CONTAMINANTS OF POTENTIAL CONCERN - SITE 27
NWS EARLE, COLTS NECK, NEW JERSEY

Contaminant of Potential Concern (COPC)	Frequency of Detection	Background Concentration (mg/kg)	Maximum Concentration (mg/kg)	Ecotox Threshold (mg/kg) ¹	Hazard Quotient	Reason for Retention or Elimination as Final COPC ²
Inorganics						
Aluminum	2/2	3940	1190	NA		Retained-No suitable threshold available
Antimony	1/2	ND	15.2	2.0	7.6	Retained-HQ > 1
Arsenic	2/2	6.2	4.3	8.2	0.52	Eliminated-Does not exceed threshold
Barium	2/2	10.6	199	40	4.98	Retained-HQ > 1
Cadmium	2/2	ND	36.3	1.2/9.6	30.3/3.78	Retained-HQ > 1
Chromium	7/8	56	471	81/370	5.81/1.27	Retained-HQ > 1
Copper	7/8	13	434	34/270	12.8/1.61	Retained-HQ > 1
Cyanide	1/2	ND	1.84	0.1/0.25	18.0/7.36	Retained-HQ > 1
Lead	8/8	34.3	786	47/218	16.7/3.60	Retained-HQ > 1
Manganese	2/2	9.2	165	460	0.36	Eliminated-Does not exceed threshold
Mercury	2/2	0.07	0.2	0.15/0.71	1.33/0.28	Retained-HQ > 1
Nickel	2/2	6	15.8	21	0.75	Eliminated-Does not exceed threshold
Selenium	1/2	ND	1.6	NA		Retained-No suitable threshold available
Silver	1/2	ND	2.5	1.0/3.7	2.50/0.68	Retained-HQ > 1
Zinc	7/8	26.9	840	150/410	5.60/2.05	Retained-HQ > 1
Organics³						
4,4'-DDE	1/2	1.7	7.3	2.2/27	3.22/0.27	Retained-HQ > 1
4,4'-DDT	1/2	19	21	1.6/46	13.1/0.45	Retained-HQ > 1
Acetone	1/2	ND	20	64	0.31	Eliminated-Does not exceed threshold
Benzo(a)anthracene	1/2	560	19	330	0.06	Eliminated-Does not exceed threshold
Chrysene	1/2	940	31	330	0.09	Eliminated-Does not exceed threshold
Di-n-butylphthalate	2/2	160	32	11000	2.90E-03	Eliminated-Does not exceed threshold
Gamma-chlordane	1/2	0.095	0.37	7	0.05	Eliminated-Does not exceed threshold
Fluoranthene	1/2	1800	62	2900	0.02	Eliminated-Does not exceed threshold
Methylene chloride	2/2	ND	34	427	0.08	Eliminated-Does not exceed threshold
Phenanthrene	1/2	1900	46	850	0.05	Eliminated-Does not exceed threshold
Pyrene	1/2	1900	57	660	0.09	Eliminated-Does not exceed threshold
Toluene	1/2	480	3	670	4.48E-02	Eliminated-Does not exceed threshold

ND = None detected

NA = No suitable benchmark was available

1 When two values are presented, the left value is the most conservative available and the right value is a less conservative value, if available. In these instances, two HQ values are presented.

2 Contaminants were retained as final COPCs if the most conservative ET value available was exceeded.

3 All organic values are in µg/kg

TABLE 122
ANALYTICAL RESULTS
CONFIRMATORY SOIL SAMPLES
SITE 27
NWS EARLE
COLTS NECK, NJ

Analyte/Compound	27-CS01	27-CS02	27-CS03	27-CS04	27-CS05	27-CS06	27-CS07	27-CS08	27-CS09	27-CS10	Residential	Non-Residential	Impact to
	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	Dir. Contact (mg/kg) (1)	Dir. Contact (mg/kg) (1)	Groundwater (mg/kg) (1)
Cyanide	6.7	<0.54	<0.54	3.2	10.8	<0.56	<0.60	<0.54	0.64	1.53	1,100	21,000	NS
Silver	<0.22	<0.22	<0.22	<0.22	<0.23	<0.23	<0.24	<0.22	0.36	2.38	110	4,100	NS
Aluminum	3,500.0	4,740.0	4,610.0	1,840.0	1,590.0	4,420.0	1,680.0	4,050.0	1,970.0	5,220.0	NS	NS	NS
Arsenic	<1.7	<1.6	<1.6	<1.6	<1.7	<1.7	<189	<1.6	1.6		20	20	NS
Barium	141.0	11.3	9.3	206.0	199.0	11.6	4.8	10.0	67.0	162.0	700	47,000	NS
Beryllium	0.17	0.21	0.19	0.09	0.23		0.17	0.15	0.11		1	1	NS
Calcium	493.0	253.0	550.0	328.0	452.0	302.0	257.0	393.0	285.0	20500.0	NS	NS	NS
Cadmium		0.42					<0.18	0.29			1	100	NS
Cobalt	6.4	1.9	0.51	10.8	8.5	1.8	0.18	0.78	3.00	22.50	NS	NS	NS
Chromium	187.0	81.9	14.0	358.0	410.0	47.6	14.2	14.7	73.6	43.2	NS	NS	NS
Copper	416.0	3.7	4.1		398.0	8.0	1.9	3.6	91.7	38.5	600	600	NS
Iron	15,800.0	8,270.0	6,720.0	15,500.0	16,400.0	7,200.0	2,920.0	5,520.0	13,000.0	8,070.0	NS	NS	NS
Mercury	0.13	0.02	<0.01	0.090	0.15	0.01	0.02	<0.01	0.05	0.03	14	270	NS
Potassium	334.0	417.0	384.0	163.0	178.0	294.0	705.0	267.0	225.0	585.0	NS	NS	NS
Magnesium	489.0	532.0	490.0	328.0	404.0	322.0	288.0	377.0	229.0	5730.0	NS	NS	NS
Manganese	293.0	21.3	20.0	538.0	265.0	22.9	2.3	12.9	95.0	824.0	NS	NS	NS
Sodium	33.5	43.6	36.1	37.2	43.9	58.0	35.8	37.0	38.4	284.0	NS	NS	NS
Nickel	36.0	3.4	2.7	55.2	22.6	3.7	<1.2	<1.1	10.1	27.0	250	2,400	NS
Lead	371.0	24.0	7.2			10.7	7.5	9.1	147.0	114.0	400	600	NS
Antimony		6.7	5.5			8.1	5.8	3.2	5.7	10.2	14	340	NS
Selenium	3.2	<2.3	<1.9	<2.7	8.9	3.1	<3.0	<1.3	5.5		63	3,100	NS
Thallium									1.6		2	2	NS
Vanadium	19.4	18.0	14.4	25.6	14.3	14.7	13.9	12.6	9.6	34.4	370	7,100	NS
Zinc	452.0	503.0	13.2	981.0	569.0	705.0	5.4	58.0	155.0	105.0	1,500	1,500	NS

(1) 7/11/96 CRITERIA
NS = NO STANDARD

TABLE 123
OCCURRENCE AND DISTRIBUTION OF ORGANICS IN SUBSURFACE SOIL AT SITE 29
NWS EARLE, COLTS NECK, NEW JERSEY
 (ug/kg)

SUBSTANCE	BACKGROUND			SITE-RELATED		
	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	REPRESENTATIVE CONCENTRATION	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	REPRESENTATIVE CONCENTRATION
4,4'-DDD	NOT DETECTED	-	-	2 / 2	35.6 - 38	38
4,4'-DDE	2 / 8	16 - 330	121.91	2 / 2	28.9 - 34	34
4,4'-DDT	2 / 8	43 - 420	157.34	2 / 2	28.6 - 39	39
ALPHA-BHC	NOT DETECTED	-	-	1 / 2	0.067	0.067
ALPHA-CHLORDANE	NOT DETECTED	-	-	1 / 2	0.64	0.64
GAMMA-CHLORDANE	NOT DETECTED	-	-	1 / 2	0.84	0.84

TABLE 124

COMPARISON OF SUBSURFACE SOIL ANALYTICAL DATA TO ARARS AND TBCs - SITE 29

NWS EARLE, COLTS NECK, NEW JERSEY

SAMPLE NUMBER:	29SB01-02	29SB02-02	---	---	---	---	ARARS & TBCs			
	LOCATION:	29SB01	29SB02	---	---	---	---	NJDEP Soil Residential Direct Contact Cleanup Criteria	NJDEP Soil Non-Residential Direct Contact Cleanup Criteria	NJDEP Soil Impact to Groundwater Cleanup Criteria
DATA SOURCE:	1995 RI	1995 RI								
PESTICIDES	ug/kg	ug/kg					ug/kg	ug/kg	ug/kg	
4,4'-DDD	35.6	38.0	J				3000	12000	50000	
4,4'-DDE	28.9	34.0					2000	9000	50000	
4,4'-DDT	28.6	39.0					2000	9000	500000	
alpha-BHC	1.9	0.067	U J				-	-	-	
alpha-chlordane	1.9	0.64	U NJ				-	-	-	
endrin	3.7	0.36	U R				17000	310000	50000	
gamma-chlordane	1.9	0.84	U J				-	-	-	

TABLE 124
COMPARISON OF SUBSURFACE SOIL ANALYTICAL DATA TO ARARS AND TBCS - SITE 29
NWS EARLE, COLTS NECK, NEW JERSEY

FINAL
PAGE 2

Footnotes to sample results:

- U - Compound or element was not detected. Value is the detection limit (inorganics) or quantitation limit (organics).
- UJ - Not detected. Detection limit or quantitation limit shown is considered estimated due to exceedance of data validation quality control criteria.
- No Value - Constituent was not analyzed for in this sample.
- UR - Nondetected result is considered rejected based on exceedance of data validation quality control criteria.
- J - Value is estimated because concentration is below the quantitation limit or because of exceedance of data validation quality control criteria.
- R - Positive result is considered rejected based on exceedance of data validation quality control criteria.
- N - Compound is considered to be tentatively identified based on exceedance of QC criteria for compound identification.
- E - Result exceeds one or more of the selected ARARs.

Footnotes to soil criteria:

- No standard is available for this chemical in this classification.

TABLE 125

**COMPARISON OF SUBSURFACE SOIL MISCELLANEOUS PARAMETERS DATA TO ARARS AND TBCs - SITE 29
NWS EARLE, COLTS NECK, NEW JERSEY**

SAMPLE NUMBER:	29SB01-02	29SB02-02	---	---	---	ARARS & TBCs			
	LOCATION:	29SB01	29SB02	---	---	---	NJDEP Soil Residential Direct Contact Cleanup Criteria	NJDEP Soil Non-Residential Direct Contact Cleanup Criteria	NJDEP Soil Impact to Groundwater Cleanup Criteria
DATA SOURCE:	1995 RI	1995 RI							
MISCELLANEOUS									
moisture	%	10.1	15.1				-	-	-
pH		6.3	n/a				-	-	-
petroleum hydrocarbons	mg/kg	130	90.0				10000 @	10000 @	-

TABLE 125
COMPARISON OF SUBSURFACE SOIL MISCELLANEOUS PARAMETERS DATA TO ARARS AND TBCS - SITE 29
NWS EARLE, COLTS NECK, NEW JERSEY

FINAL
PAGE 2

Footnotes to sample results:

- U - Compound or element was not detected. Value is the detection limit (inorganics) or quantitation limit (organics).
- UJ - Not detected. Detection limit or quantitation limit shown is considered estimated due to exceedance of data validation quality control criteria.
- No Value - Constituent was not analyzed for in this sample.
- UR - Nondetected result is considered rejected based on exceedance of data validation quality control criteria.
- J - Value is estimated because concentration is below the quantitation limit or because of exceedance of data validation quality control criteria.
- R - Positive result is considered rejected based on exceedance of data validation quality control criteria.
- N - Compound is considered to be tentatively identified based on exceedance of QC criteria for compound identification.
- E - Result exceeds one or more of the selected ARARs.

Footnotes to soil criteria:

- - No standard is available for this chemical in this classification.
- @ - Value is New Jersey guideline for maximum total concentration of all organic compounds in soil (including VOCs, SVOCs, and TPH).

TABLE 126
OCCURRENCE AND DISTRIBUTION OF INORGANICS IN GROUNDWATER AT SITE 29
NWS EARLE, COLTS NECK, NEW JERSEY
 (ug/L)

SUBSTANCE	BACKGROUND			SITE-RELATED				
	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	2 X AVERAGE CONCENTRATION	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	AVERAGE CONCENTRATION	MEAN > 2 X BKGD?	REPRESENTATIVE CONCENTRATION
ALUMINUM	11 / 11	287 - 7870	5097.82	2 / 2	562 - 575	568.50	NO	575
ARSENIC	1 / 11	5.8 - 5.8	4.05	1 / 2	3.7	2.68	NO	3.7
BARIUM	11 / 11	2.6 - 518	229.60	2 / 2	17.1 - 21.3	19.20	NO	21.3
CADMIUM*	5 / 11	0.6 - 1.9	1.21	1 / 2	0.94	0.57	NO	0.94
CALCIUM	11 / 11	506 - 17200	8306.55	2 / 2	25400 - 41400	33400.00	YES	41400
CHROMIUM	NOT DETECTED	-	-	2 / 2	8.3 - 14.1	11.20	YES	14.1
IRON	11 / 11	153 - 7690	4197.09	2 / 2	13900 - 34800	24350.00	YES	34800
LEAD	3 / 11	2.1 - 3	2.44	1 / 2	2	1.38	NO	2
MAGNESIUM	11 / 11	273 - 27400	8449.64	2 / 2	4070 - 6720	5395.00	NO	6720
MANGANESE	11 / 11	3.3 - 65	46.18	2 / 2	92.7 - 102	97.35	YES	102
MERCURY	11 / 11	0.005 - 0.12	0.12	2 / 2	0.04 - 0.065	0.05	NO	0.065
NICKEL	10 / 11	0.81 - 25.5	11.98	2 / 2	1 - 1.5	1.25	NO	1.5
POTASSIUM	11 / 11	350 - 3245	2810.55	2 / 2	2910 - 3270	3090.00	YES	3270
SODIUM	11 / 11	1850 - 11650	8449.09	2 / 2	7310 - 42900	25105.00	YES	42900
VANADIUM	10 / 11	0.69 - 42.25	16.48	2 / 2	2.8 - 3.4	3.10	NO	3.4
ZINC	6 / 9	3.7 - 348	178.61	2 / 2	3.4 - 3.8	3.60	NO	3.8

Note: Selected COPCs are indicated in boldface type.

* - Indicates COPCs eliminated based on amended risk assessment.

TABLE 127
OCCURRENCE AND DISTRIBUTION OF ORGANICS IN GROUNDWATER AT SITE 29
NWS EARLE, COLTS NECK, NEW JERSEY
 (ug/L)

SUBSTANCE	BACKGROUND			SITE-RELATED		
	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	REPRESENTATIVE CONCENTRATION	FREQUENCY OF DETECTION	RANGE OF POSITIVE DETECTION	REPRESENTATIVE CONCENTRATION
1,2-DICHLOROETHENE (TOTAL)	NOT DETECTED			1 / 2	1	1

TABLE 128

COMPARISON OF GROUNDWATER ANALYTICAL DATA TO ARARS AND TBCs - SITE 29

NWS EARLE, COLTS NECK, NEW JERSEY

SAMPLE NUMBER:	29GW01	29GW02	---	---	---	---	ARARS & TBCs		
	LOCATION:	29GW01	29GW02	---	---	---	Maximum Contaminant Level (MCL)	Drinking Water Health Advisory (Lowest Criterion Shown)	NJDEP Groundwater Quality Standard
DATA SOURCE:	1995 RI	1995 RI							
INORGANICS	ug/L	ug/L					ug/L	ug/L	ug/L
aluminum	562 E J	575 E J					-	-	200
arsenic	3.3 U	3.7					50.0	-	8.00
barium	17.1	21.3					2000	2000 a	2000
cadmium	0.94	0.38 U					5.00	5.00 e	4.00
calcium	25400	41400					-	-	-
chromium, total	14.1	8.3					100	100 a	100
iron	34800 E	13900 E					-	-	300
lead	2.0 J	1.5 U					15.0	-	10.0
magnesium	4070	6720					-	-	-
manganese	102 E	92.7 E					-	-	50.0
mercury	0.065	0.040					2.00	2.00 b	2.00
nickel	1.0	1.5					100	100 a	100
potassium	3270	2910					-	-	-
sodium	42900	7310					-	-	50000
vanadium	2.8	3.4					-	-	-
zinc	3.8	3.4					-	2000 a	5000
VOLATILES	ug/L	ug/L					ug/L	ug/L	ug/L
1,2-dichloroethene (total)	1.0 J	10.0 U					70.0 a	70.0 a	10.0

TABLE 128

COMPARISON OF GROUNDWATER ANALYTICAL DATA TO ARARS AND TBCS - SITE 29 NWS EARLE, COLTS NECK, NEW JERSEY

FINAL
PAGE 2

Footnotes to sample results:

- U - Compound or element was not detected. Value is the detection limit (inorganics) or quantitation limit (organics).
- UJ - Not detected. Detection limit or quantitation limit shown is considered estimated due to exceedance of data validation quality control criteria.
- No Value - Constituent was not analyzed for in this sample.
- UR - Nondetected result is considered rejected based on exceedance of data validation quality control criteria.
- J - Value is estimated because concentration is below the quantitation limit or because of exceedance of data validation quality control criteria.
- R - Positive result is considered rejected based on exceedance of data validation quality control criteria.
- N - Compound is considered to be tentatively identified based on exceedance of QC criteria for compound identification.
- E - Result exceeds one or more of the selected ARARs.

Footnotes to MCLs, MCLGs, or SMCLs:

- - No standard is available for this chemical in this classification.
- a - Where applicable, value(s) represent the more stringent of criteria for total, cis-, and trans- isomers.
- * - Criteria are for total chromium.
- ** - Action level 1300 ug/L for water treatment technology for public water supply systems.
- *** - Action level 15 ug/L for water treatment technology for public water supply systems.

Footnotes to Health Advisories:

- - No standard is available for this chemical in this classification.
- a - The listed health advisory criterion, lifetime adult, is equal to the most stringent of the EPA health advisories for this chemical.
- b - The listed health advisory criterion, long-term adult, is equal to the most stringent of the EPA health advisories for this chemical.
- c - The listed health advisory criterion, one-day child, is equal to the most stringent of the EPA health advisories for this chemical.
- d - The listed health advisory criterion, ten-day child, is equal to the most stringent of the EPA health advisories for this chemical.
- e - The listed health advisory criterion, long-term child, is equal to the most stringent of the EPA health advisories for this chemical.

TABLE 129
REPRESENTATIVE CONCENTRATION AND STATISTICAL DISTRIBUTION OF COPCS
SUBSURFACE SOIL - SITE 29 (ug/kg)
NWS EARLE, COLTS NECK, NEW JERSEY

CHEMICAL OF CONCERN	REPRESENTATIVE CONCENTRATION	STATISTICAL DISTRIBUTION
4,4'-DDD	38	NONPARAMETRIC
4,4'-DDE	34	NONPARAMETRIC
4,4'-DDT	39	NONPARAMETRIC
ALPHA-BHC	0.067	NONPARAMETRIC
ALPHA-CHLORDANE	0.64	NONPARAMETRIC
GAMMA-CHLORDANE	0.84	NONPARAMETRIC

TABLE 130
REPRESENTATIVE CONCENTRATION AND STATISTICAL DISTRIBUTION OF COPCS
GROUNDWATER - SITE 29 (ug/L)
NWS EARLE, COLTS NECK, NEW JERSEY

CHEMICAL OF CONCERN	REPRESENTATIVE CONCENTRATION	STATISTICAL DISTRIBUTION
ARSENIC	3.7	NONPARAMETRIC
CADMIUM	0.94	NONPARAMETRIC
IRON	34800	NONPARAMETRIC
1,2-DICHLOROETHENE (TOTAL)	1	NONPARAMETRIC

TABLE 131

RME CARCINOGENIC RISK TO FUTURE INDUSTRIAL RECEPTORS - SITE 29
SUBSURFACE SOIL
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SUBSURFACE SOIL INGESTION	SUBSURFACE SOIL DERMAL CONTACT	INHALATION OF COPCS IN FUGITIVE DUST
4,4'-DDD	3.2E-09	6.2E-09	5.9E-13
4,4'-DDE	4.0E-09	7.9E-09	7.5E-13
4,4'-DDT	4.6E-09	9.0E-09	1.0E-12
ALPHA-BHC	1.5E-10	2.3E-10	3.3E-14
ALPHA-CHLORDANE	2.9E-10	5.7E-10	6.5E-14
GAMMA-CHLORDANE	3.8E-10	7.4E-10	8.5E-14
TOTAL RISK	1.3E-08	2.5E-08	2.6E-12

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 132

RME NONCARCINOGENIC HQS, FUTURE INDUSTRIAL RECEPTORS - SITE 29
SUBSURFACE SOIL
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SUBSURFACE SOIL INGESTION	SUBSURFACE SOIL DERMAL CONTACT	INHALATION OF COPCS IN FUGITIVE DUST
4,4'-DDD	N/A	N/A	N/A
4,4'-DDE	N/A	N/A	N/A
4,4'-DDT	7.6E-05	1.5E-04	1.4E-08
ALPHA-BHC	N/A	N/A	N/A
ALPHA-CHLORDANE	1.0E-05	2.0E-05	1.9E-09
GAMMA-CHLORDANE	1.4E-05	2.7E-05	2.5E-09

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 133

RME CARCINOGENIC RISK TO FUTURE INDUSTRIAL RECEPTORS - SITE 29
GROUNDWATER, AMENDED RISK
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	GROUNDWATER INGESTION	GROUNDWATER DERMAL CONTACT
1,2-DICHLOROETHENE (TOTAL)	N/A	N/A
ARSENIC	1.9E-05	8.4E-09
IRON	N/A	N/A
TOTAL RISK	1.9E-05	8.4E-09

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 134

RME NONCARCINOGENIC HQS, FUTURE INDUSTRIAL RECEPTORS - SITE 29
 GROUNDWATER, AMENDED RISK
 NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	GROUNDWATER INGESTION	GW INGESTION BY TARGET ORGAN				GROUNDWATER DERMAL CONTACT
		CARDIO- VASCULAR SYSTEM	SKIN	LIVER	DIGESTIVE SYSTEM	
1,2-DICHLOROETHENE (TOTAL)	1.1E-03	1.1E-03		1.1E-03		1.0E-05
ARSENIC	1.2E-01		1.2E-01			5.2E-05
IRON	1.1E+00			1.1E+00	1.1E+00	9.3E-03
	HI BY TARGET ORGAN	1.1E-03	1.2E-01	1.1E+00	1.1E+00	

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 135

CENTRAL TENDENCY NONCARCINOGENIC HQS, FUTURE INDUSTRIAL RECEPTORS - SITE 29
GROUNDWATER, AMENDED RISK
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	GROUNDWATER INGESTION	GW INGESTION BY TARGET ORGAN				GROUNDWATER DERMAL CONTACT
		CARDIO- VASCULAR SYSTEM	SKIN	LIVER	DIGESTIVE SYSTEM	
1,2-DICHLOROETHENE (TOTAL)	6.7E-04	6.7E-04		6.7E-04		8.9E-06
ARSENIC	5.4E-02		5.4E-02			3.3E-05
IRON	4.9E-01			4.9E-01	4.9E-01	5.7E-03
	HI BY TARGET ORGAN	6.7E-04	5.4E-02	4.9E-01	4.9E-01	

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 136

RME CARCINOGENIC RISK TO FUTURE RESIDENTIAL RECEPTORS - SITE 29
SUBSURFACE SOIL
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SUBSURFACE SOIL INGESTION - LIFETIME	SUBSURFACE SOIL DERMAL CONTACT - LIFETIME	INHALATION OF COPCS IN FUGITIVE DUST - LIFETIME
4,4'-DDD	1.4E-08	2.1E-08	3.6E-13
4,4'-DDE	1.8E-08	2.6E-08	4.6E-13
4,4'-DDT	2.1E-08	3.0E-08	6.3E-13
ALPHA-BHC	6.6E-10	7.6E-10	2.0E-14
ALPHA-CHLORDANE	1.3E-09	1.9E-09	4.0E-14
GAMMA-CHLORDANE	1.7E-09	2.5E-09	5.2E-14
TOTAL RISK	5.7E-08	8.2E-08	1.6E-12

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 137
 RME NONCARCINOGENIC HQS, FUTURE RESIDENTIAL RECEPTORS - SITE 29
 SUBSURFACE SOIL
 NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	SUBSURFACE SOIL INGESTION - CHILD	SUBSURFACE SOIL DERMAL CONTACT - CHILD	INHALATION OF COPCS IN FUGITIVE DUST - CHILD
4,4'-DDD	N/A	N/A	N/A
4,4'-DDE	N/A	N/A	N/A
4,4'-DDT	1.0E-03	1.2E-03	1.5E-08
ALPHA-BHC	N/A	N/A	N/A
ALPHA-CHLORDANE	1.4E-04	1.7E-04	2.0E-09
GAMMA-CHLORDANE	1.8E-04	2.2E-04	2.7E-09

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 138

RME CARCINOGENIC RISK T FUTURE RESIDENTIAL RECEPTORS - SITE 29
GROUNDWATER, AMENDED RISK
NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	GROUNDWATER INGESTION - LIFETIME	GROUNDWATER DERMAL CONTACT - LIFETIME	INHALATION OF VOAS IN GW - ADULT
1,2-DICHLOROETHENE (TOTAL)	N/A	N/A	N/A
ARSENIC	8.3E-05	2.0E-07	N/A
IRON	N/A	N/A	N/A
TOTAL RISK	8.3E-05	2.0E-07	N/A

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 139

RME NONCARCINOGENIC HQS, FUTURE RESIDENTIAL RECEPTORS - SITE 29
 GROUNDWATER, AMENDED RISK
 NWS EARLE, COLTS NECK, NEW JERSEY

SUBSTANCE	GROUNDWATER INGESTION - CHILD	GW INGESTION BY TARGET ORGAN				GROUNDWATER DERMAL CONTACT - CHILD	INHALATION OF VOAS IN GW - ADULT
		CARDIO- VASCULAR SYSTEM	SKIN	LIVER	DIGESTIVE SYSTEM		
1,2-DICHLOROETHENE (TOTAL)	7.1E-03	7.1E-03		7.1E-03		3.9E-04	N/A
ARSENIC	7.9E-01		7.9E-01			1.6E-03	N/A
IRON	7.4E+00			7.4E+00	7.4E+00	2.9E-01	N/A
	HI BY TARGET ORGAN	7.1E-03	7.9E-01	7.4E+00	7.4E+00		

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 140

**CENTRAL TENDENCY NONCARCINOGENIC HQS, FUTURE RESIDENTIAL RECEPTORS - SITE 29
GROUNDWATER, AMENDED RISK
NWS EARLE, COLTS NECK, NEW JERSEY**

SUBSTANCE	GROUNDWATER INGESTION - CHILD	GW INGESTION BY TARGET ORGAN				GROUNDWATER DERMAL CONTACT - CHILD	INHALATION OF VOAS IN GW - ADULT
		CARDIO- VASCULAR SYSTEM	SKIN	LIVER	DIGESTIVE SYSTEM		
1,2-DICHLOROETHENE (TOTAL)	3.3E-03	3.3E-03		3.3E-03		2.6E-04	N/A
ARSENIC	2.7E-01		2.7E-01			7.8E-04	N/A
IRON	2.4E+00			2.4E+00	2.4E+00	1.4E-01	N/A
	HI BY TARGET ORGAN	3.3E-03	2.7E-01	2.4E+00	2.4E+00		

N/A = NOT APPLICABLE, NO TOXICITY VALUE HAS BEEN ESTABLISHED FOR THIS CHEMICAL

TABLE 141

**SUMMARY OF ESTIMATED RME CANCER RISKS AND NONCARCINOGENIC HAZARD INDICIES - SITE 29
NWS EARLE, COLTS NECK, NEW JERSEY**

Medium	Exposure Routes	Estimated Incremental Cancer Risk				Estimated Hazard Index***				
		Current Industrial Employee	Future Industrial Employee	Future Lifetime Resident	Future Recreational Child	Current Industrial Employee	Future Industrial Employee	Future Resident		Future Recreational Child
								Child	Adult	
Surface Soil	Incidental Ingestion	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A
	Dermal Contact	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A
	Inhalation of Fugitive Dust	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A
Subsurface Soil	Incidental Ingestion	N/A	1.3E-08	5.7E-08	N/A	N/A	1.0E-04	1.3E-03	N/A	N/A
	Dermal Contact	N/A	2.5E-08	8.2E-08	N/A	N/A	2.0E-04	1.6E-03	N/A	N/A
	Inhalation of Fugitive Dust	N/A	2.6E-12	1.6E-12	N/A	N/A	1.9E-08	2.0E-08	N/A	N/A
Sediment	Incidental Ingestion	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/S
	Dermal Contact	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/S
Groundwater	Ingestion	N/A	1.9E-05 [^]	8.3E-05 [^]	N/A	N/A	1.1E+00@	7.4E+00@	N/A	N/A
	Dermal Contact	N/A	8.4E-09 [^]	2.0E-07 [^]	N/A	N/A	9.4E-03 [^]	2.9E-01 [^]	N/A	N/A
	Inhalation of Volatiles*	N/A	N/A	N/A**	N/A	N/A	N/A	N/A	N/A**	N/A
Surface Water	Incidental Ingestion	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/S
	Dermal Contact	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/S
TOTAL		-	1.9E-05	8.3E-05	-	-	1.1E+00	7.7E+00	-	-

N/A = Not applicable because this media is not associated with this potential receptor

N/S = Not sampled

* = During Showering, Adult Residents Only

** = No volatiles were detected in groundwater

*** = Hazard Indices (i.e., summation of hazard quotients) are used only for comparison purposes and do not reflect actual additive noncarcinogenic effects

[^] - Value from amended risk assessment.

@ - Result is the maximum of the HIs among the affected target organs from the amended risk assessment.

TABLE 142
SUMMARY OF CENTRAL TENDENCY CANCER RISKS AND NONCARCINOGENIC HAZARD INDICIES - SITE 29
NWS EARLE, COLTS NECK, NEW JERSEY

Medium	Exposure Routes	Estimated Incremental Cancer Risk				Estimated Hazard Index***				
		Current Industrial Employee	Future Industrial Employee	Future Lifetime Resident	Future Recreational Child	Current Industrial Employee	Future Industrial Employee	Future Resident		Future Recreational Child
								Child	Adult	
Surface Soil	Incidental Ingestion	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A
	Dermal Contact	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A
	Inhalation of Fugitive Dust	N/S	N/A	N/S	N/A	N/S	N/A	N/S	N/A	N/A
Subsurface Soil	Incidental Ingestion	N/A	N/R	N/R	N/A	N/A	N/R	N/R	N/A	N/A
	Dermal Contact	N/A	N/R	N/R	N/A	N/A	N/R	N/R	N/A	N/A
	Inhalation of Fugitive Dust	N/A	N/R	N/R	N/A	N/A	N/R	N/R	N/A	N/A
Sediment	Incidental Ingestion	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/S
	Dermal Contact	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/S
Groundwater	Ingestion	N/A	N/R	N/R	N/A	N/A	4.9E-01@	2.4E+00@	N/A	N/A
	Dermal Contact	N/A	N/R	N/R	N/A	N/A	5.7E-03^	1.4E-01^	N/A	N/A
	Inhalation of Volatiles*	N/A	N/A	N/A**	N/A	N/A	N/A	N/A	N/A**	N/A
Surface Water	Incidental Ingestion	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/S
	Dermal Contact	N/A	N/A	N/A	N/S	N/A	N/A	N/A	N/A	N/S
TOTAL		-	-	-	-	-	5.0E-01	2.5E+00	-	-

N/A = Not applicable because this media is not associated with this potential receptor

N/R - Central Tendency calculation not required

N/S = Not sampled

* = During Showering, Adult Residents Only

** = No volatiles were detected in groundwater

*** = Hazard Indices (i.e., summation of hazard quotients) are used only for comparison purposes and do not reflect actual additive noncarcinogenic effects

^ - Value from amended risk assessment.

@ - Result is the maximum of the HIs among the affected target organs from the amended risk assessment.

