

N60201.AR.002831
NS MAYPORT
5090.3a

EMAIL DISCUSSING REQUESTS FOR REMEDIAL ACTION ALTERNATIVES WAIVERS FOR
SOLID WASTE MANAGEMENT UNITS 8, 9, 11 AND 51 (SWMU 8, 9, 11 AND 51) NS
MAYPORT FL
1/7/2013
TETRA TECH

Claggett, Libby

From: Fears, Diane
Sent: Thursday, August 07, 2014 9:29 AM
To: Claggett, Libby
Subject: FW: Request for RAA waiver for four SWMUs at NAVSTA Mayport
Attachments: Figure 3-2_030411.pdf; Figure 3-3_030411.pdf; Figure 3-4_030411.pdf; Figure 3-8_030311.pdf; Figure 1 - Selected SWMU Locations.pdf

Waiver request for SWMUs 8, 9, 11, and 51

From: Fears, Diane
Sent: Monday, January 07, 2013 12:54
To: Hayworth, Dana
Cc: Roof, Gregory
Subject: Request for RAA waiver for four SWMUs at NAVSTA Mayport

Dana,

To keep from spending hours (and money we don't have) to put together RAAs for the sites at Mayport, Mike Maughon suggested we request waivers from the RAA requirement. He helped me draft this email, which you can send to Tom Spriggs, copy to Mike Maughon, requesting the waivers.

Let me know if you have any questions.

thanks

Diane

TetraTech is working on a CMS for four sites: SWMUs 8, 9, 11 and 51. The four sites each have low concentration, fuel-related contamination, and are located adjacent to or in the same vicinity of each other in an industrial area containing a fuel farm and related facilities. (See Selected SWMU Location Map, Figure 1.) LUCs are already in-place at adjacent SWMUs 6 and 7. The RFI was completed for these sites in 1996. The RFI Addendum was completed in 2012. In accordance with the NAVFAC RAA Guidance, each of these sites is likely eligible for an RAA waiver because the CMS for each site will only include two alternatives, No Action and Land Use Controls. Additional supporting information for each site is provided below.

SWMU 8 is the percolation pond for SWMU 9, which is the Oily Waste Treatment Plant (OWTP). SWMU 8 was used from 1979 to 1994, when it was removed from service. After sampling the surface soil, subsurface soil, and groundwater, the only impact is one monitoring well with elevated iron (11,100 µg/L). The well is upgradient from SWMU 8, and downgradient wells do not exceed the Florida groundwater criteria target levels (GCTLs) promulgated in Chapter 62-777 Florida Administrative Code (F.A.C.). Since the groundwater is classified as G-III (non-potable use) due to the total dissolved solids greater than 10,000, and this level does exceed the Poor Quality GCTL (ten times the drinking water GCTL), no treatment other than institutional controls would be considered for this elevated constituent.

SWMU 9 is the OWTP. One surface soil sample exceeds benzo(a)pyrene (BAP) and BAP equivalents. Four subsurface soil samples exceed for BAP, BAP equivalents and polycyclic aromatic


hydrocarbons (PAH) at 9 ft below land surface (bls). One monitoring well exceeds the drinking water GCTL for iron, but does not exceed the Poor Quality GCTL. The groundwater is G-III (non-potable). The area of the OWTP is rife with piping, and an excavation would be ineffective due to the utility and piping interferences. There is not a particular plume, as noted in the attached figure 3-2, and LUC would be the most effective way to manage the risk.

SWMU 11 was identified as a fuel spill area in the Initial Assessment Study conducted in 1986 and is located in the NAVSTA Mayport Fuel Farm. The Fuel Farm was completely renovated in 2001, and the truck fill stand is now located adjacent to the area identified as SWMU 11. Four subsurface soil samples exceed soil CTLs (SCTLs) for residential and industrial criteria for total petroleum hydrocarbons (TPH), as shown in the attached figure 3-3. The depth of the contamination is 13 ft bls. Groundwater is not impacted. Excavation is difficult and probably ineffective due to the underground piping and utilities, and LUCs are the most effective method of risk management.

SWMU 51 is a trio of Waste Oil Tanks, cut and cover tanks which were constructed in 1954. They were also used as the oily wastewater receiving tanks for SWMU 9, the OWTP. SWMU 51 is located in the NAVSTA Mayport Fuel Farm. The tanks were removed with the renovation in 2001, and the area was configured into a truck parking area. One surface soil sample exceeds the residential and leachability SCTL for TPH, and 8 subsurface soil samples exceed SCTLs for PAH, BAP, BAP equivalents, and TPH at depths of 11 to 13 ft bls, as shown in Figure 3-4. This is an active fuel farm, with piping and utilities making soil excavation ineffective. The groundwater also has impacts, as shown in Figure 3-8. This area is downgradient, and adjacent to, SWMUs 6 and 7, which are the oily waste sludge drying beds that have LUCs for both soil and groundwater. The groundwater in this area is G-III (non-potable), is being monitored for petroleum constituents, and the impacts at SWMU 51 are associated with SWMUs 6 and 7. This is another site where LUCs are the most effective method of risk management.

We believe that it wouldn't be in the Navy's best interest to do an RAA for each of these sites due to the simplicity of the contamination, the existing LUC in the vicinity, the agreement of the IR Partnering Team to do LUCs for these sites, and the ineffectiveness of any treatment strategy.

P:\GIS\MAYPORT_NS\MAPDOCS\MXD\SWMU09_SB_LOCS.MXD 3/04/11 SS



Legend

- Soil Sample Location
- SWMU 9 Boundary
- Former Building
- Installation Area




DRAWN BY	DATE
T. WHEATON	06/29/10
CHECKED BY	DATE
B. MARSHALL	3/04/11
REVISED BY	DATE
SCALE	
AS NOTED	



SOIL SAMPLE EXCEEDANCE TAG MAP
SWMU 9 - OILY WASTE
TREATMENT PLANT
NAVAL STATION MAYPORT
JACKSONVILLE, FLORIDA


CONTRACT NUMBER CTO 0033	
OWNER NUMBER 	
APPROVED BY	DATE
FIGURE NO.	REV
FIGURE 3-2	0

P:\GIS\MAYPORT_NSMAPDOCS\MXD\SWMU11_SB_LOCS.MXD 3/04/11 SS



Legend

- Soil Sample Location
- SWMU 11 Boundary
- Former Building
- Installation Area




DRAWN BY	DATE
K. MOORE	1/12/11
CHECKED BY	DATE
B. MARSHALL	3/04/11
REVISED BY	DATE
—	—
SCALE AS NOTED	



SOIL SAMPLE EXCEEDANCE TAG MAP
SWMU 11 - FUEL SPILL AREA
NAVAL STATION MAYPORT
JACKSONVILLE, FLORIDA

CONTRACT NUMBER CTO 0033	
OWNER NUMBER —	
APPROVED BY	DATE
—	—
FIGURE NO. FIGURE 3-3	REV 0



Legend

- Soil Sample Location
- SWMU 51 Boundary
- Installation Area

DRAWN BY	DATE
K. MOORE	1/12/11
CHECKED BY	DATE
C. PIKE	3/03/11
REVISED BY	DATE
SCALE	
AS NOTED	



SOIL SAMPLE EXCEEDANCE TAG MAP
SWMU 51 - WASTE OIL TANKS
NAVAL STATION MAYPORT
JACKSONVILLE, FLORIDA


CONTRACT NUMBER CTO 0033	
OWNER NUMBER 	
APPROVED BY	DATE
FIGURE NO. FIGURE 3-4	REV 0



Legend

-  Monitoring Well Location
-  Former Building
-  SWMU 51 Boundary
-  Installation Area

DRAWN BY	DATE
K. MOORE	1/13/11
CHECKED BY	DATE
B. MARSHALL	1/13/11
REVISED BY	DATE
SCALE	AS NOTED



GROUNDWATER EXCEEDANCE TAG MAP
SWMU 51 - WASTE OIL TANKS
NAVAL STATION MAYPORT
JACKSONVILLE, FLORIDA

CONTRACT NUMBER	
CTO 033	
OWNER NUMBER	

APPROVED BY	DATE
---	---
FIGURE NO.	REV
FIGURE 3-8	0